FINAL REPORT
PHASE II


PRELIMINARY DESIGN

(20)

VERTICAL
STORES
HANDLING
CONVEYOR

RESEARCH AND DEVELOPMENT

CONTRACT NO. N00024-72-C-5500



NAVAL SHIP ENGINEERING CENTER

MATERIAL HANDLING SYSTEMS
KORNYLAK CORPORATION
400 HEATON ST. - HAMILTON, OHIO 45011
MAY 1977

DISTRIBUTION STATEMENT A

Approved for public releases

Distribution Unlimited





Final Report.
Phase II

Detail Design and Preliminary Design Drawings

Research and Development

Contract No.

5) NØ0024-72-C-5500

Naval Ship Engineering Center

Preliminary Design, Vertical Stores Handling Conveyor

Submitted By:

KORNYLAK CORPORATION 400 Heaton Street Hamilton, Ohio 45011

May, 1977

49 11-1

Approved for public release;
Distribution Unlimited

Introduction

The primary purpose of Phase II of Research and Development Contract No. N00024-72-C-5500 was to prepare detailed preliminary design drawings based on the concepts developed and approved in Phase II also required the preparation and submittal of:

a Final Reliability Program,

-- a Final Maintainability Program,

-v a Failure Modes and Effects Selection Criteria Report,

-- va Final Failure Modes and Effects Analysis,

-- detailed design calculations,

-- various Engineering Studies and Investigations.

Drawings, programs, plans, studies, investigations and reports have been completed and submtted fulfilling all requirements of Phase II.

ACCESSION TOR

NEIC WRITE SECTION (1)

OPC DEN SECTION (1)

UNANTIFICATION

FILE OF THE SECTION (1)

BY

C. TRIVITION AVAILABLE OF THE SECTION

DIST. 155-11

A

Distribution

Copies of this Final Report for Phase II of R & D Contract No. N00024-72-C-5500 were distributed by Kornylak Corporation as follows:

Distributed to:	Date	Copies	Reproducibles
Director Defense Documentation Cameron Station	May, 1977 Center	20	0
Alexandria, Virginia Atth: Code SL4200	22314		
Commander Naval Ship Engineering Department of the Nav Code 6164D Washington, D. C. 20	9	6	0

Section II

Transmittal Log for Phase II

The following pages comprize a chronological listing of all significant transmittals made by the Kornylak Corporation from the start of Phase II through May 12, 1977. Opposite the "Description" of the transmittal are columns listing the "date of report", "date of transmittal", to whom the transmittal was sent and appropriate remarks.

R&D Contract #N00024-72-G-5500

R&D Contract #NUCOZ4-/Z-C-3300	Phase II	Date of R.jt. Date of Transmittal To Remarks	04 Nov. 1974 C4 Nov. 1974 T.A.Satterthwaite	B T.A.Satterthwaite	30 Oct. 1974 30 Oct. 1974 Various See Distribution Schedule	Assy.	Assy.	B T.A.Satterthwaite	17 Jan. 1975 Commander, Nukc Code 6164	21 Jan. 1975 Z1 Jan. 1975 Various See Distribution Schedule	eport 21 Jan. 1975 21 Jan. 1975 Various See Distribution Schedule	
K&D C		- 		13	1974	01	01	0	11	1975	Jan. 1975	21 Jan. 1975 21
		Description	Schedule of Work Phase II	.Dwg. #2-1026-PlO Rev. B Loader/Unloader Assy. With Jam Sensing Device	.E003 Contract Funds Status Report	.Dwg. #2-1026-P41 Top Overtravel Limit Assy. (Front Loading)	.Dwg. #2-1026-P42 Top Overtravel Limit Assy. (Rear Loading)	.Dwg. #2-1026-P19 Rev. B Roller Bed Loader/Unloader Assy. with Jam Sensing Device	.Dwg. #2-1026-P43 Lubrication Access.	.E003 Contract Runds Status Report	.E002 Milestone/Gost Report	POSI Milestone/Cost Dien

		Phase II		
Description	Date of Rept.	Date of Transmittal	7	Remarks
.Public Voucher II-01	22 Jan. 1975	22 Jan. 1975	Defense Contract Audit Agency Columbus, Ohio	
.Agenda for Design Review Meeting	22 Jan. 1975	22 Jan. 1975	Commander, NSEC Code 6164	
.Final-Reliability and Maintainability Program Plans CDRL Item BOOIAA	28 Jan. 1975	04 Feb. 1975	Commander, NSEC Code 6164	
.Letter on Design "D" vs. Design "B" type motors	17 March 1975	17 March 1975	Commander, NSEC Code 6164	
.Drawing Lists: 2-1026-DL1 2-1026-DL2	19 March 1975	21 March 1975	Commander, NSEC Code 6164	
2-1026-DL3				
2-1026-D1.4 2-1026-D1.5				
2-1026-DI.6				
2-1026-DL7 2-1026-DL8				
2-1026-DL9				
2-1026-DL10 2-1026-DL11				
2-1026-DL12				
2-1026-11.13				
2-1026-DL14 2-1026-DL15				
2-1026-DL16				
2-1026-DL47 2-1026-DL48			eritoria, est	
2-1020-0110				

The state of the s

Report Transmittal Log R&P Contract #N00024-72-G-5500

•	-	
١	-	
	Š	
,	ë	
į	Ē	

₫		Phase II		
Description	Date of Rept.	Date of Transmittal	To	Remarks
.Letter on brake selection and location	31 March 1975	6	Commander, NSEC Code 6164	
.Dwg. #2-1026-SCB Dwg. #2-1026-SC9 Panel sizing with and without stiffeners	***************************************	31 March 1975	Commander, NSEC	
.fatter on motor speed	31 March 1975	31 March 1975	Commander, NSEC Code 6164	
Letter on various methods for conveyor control and use of 440V for control circultry	07 April 1975	07 Apríl 1975	Commander, NSEC	
FMEA Selection and Griteria Report CDRL #B001AB	10 April 1975	14 April 1975	Commander, NSEC Code 6164	
•Fublic Voucher II-02	14 April 1975	14 April 1975	Defense Contract Audit Agency Coiumbus, Ohio	
.EOO3 Contract Fund Status Report	14 April 1975	14 April 1975	Various	See Distribution Schedule
• E002 Milestone/Cost Report	14 April 1975	14 April 1975	Various	See Distribution Schedule
Design Review Hecting minutes CDRL BOOLAE	1) Dec. 19 & 20, 1974 2) Mar. 3 & 4, 1975	14 April 1975	Code 6165	

the second se

Date of Transmittal 15 April 1975 -AS OF 15 APRIL 1975 -7 June 1975 Commander, NSEC Code 6164 Commander, NSEC Code 6164 Commander, NSEC Code 6164

Report Transmittal Log R&D Contract #N00024-72-C-5500

	Renarks	See Distribution Schedule	See Distribution Schedule		
	To	Various	Various	Defense Contract Audit Agency Columbus, Ohio	Code 6164
Phase II	Date of Transmittal		18 July 1975	18 July 1975	18 July 1975
•	Date of Rept.	18 July	18 July 1975	13 July 1975	18 July 1975 Rev. D Rev. D
	Description	nds Sta 3)	.Milestone cost report	. Public Vouch #11-03	Drawing transmittal Drawing #2-1026-P10F Sht. 1 Drawing #2-1026-P10R Sht. 2 Drawing #2-1026-51F Drawing #2-1026-52F Drawing #2-1026-53F Drawing #2-1026-54F Drawing #2-1026-55F Drawing #2-1026-55F Drawing #2-1026-56F Drawing #2-1026-55F Drawing #2-1026-55F Drawing #2-1026-55F Drawing #2-1026-65F Drawing #2-1026-65F Drawing #2-1026-65F Drawing #2-1026-65F Drawing #2-1026-65F Drawing #2-1026-64F

Drawing transmittal brawing #2-1026-SC8 Drawing #2-1026-SC9 Drawing #2-1026-P17 brawing #2-1026-P8N Drawing #2-1026-P8N Drawing #2-1026-95F Drawing #2-1026-94F Drawing #2-1026-93F	<pre>.Contractors proposal for a "push-pull" illuminated switch.</pre>	.Contractor's proposal for a hardware visualization and concept testing unit.	.Submittal of DD Form 882		Description
05 Sept. 1975	14 Aug. 1975	14 Aug. 1975	19 Aug. 1975	28 July 1975	Date of Rept.
05 Sept. 1975	14 Aug. 1975	14 Aug. 1975	19 Aug. 1975	28 July 1975	Date of Transmittal
Commander, NSEC Code 6164	Commander, NSEC Code 6164	Commander, NSEC Code 6164	E. J. Wahle, Administrative Officer	Commander, NSEG Gode 6164	То
					Remarks

R&D Contract #N00024-72-G-5500

	Remarks			See Distribution Schedule	See Mistribution Schedule			
•	To		Code 6164	Various	Various	Defense Contract Audit Agency	Commander, NSEC Code 6164	Code 6164
44 9998	Date of Transmittel		26 Sept. 1975	01 Oct. 1975	01 Oct. 1975	01 Oct. 1975	28 Oct. 1975	28 Oct. 1975
•	Date of Rept.		26 Sept. 1975	01 Oct. 1975	01 Oct. 1975	01 Oct. 1975	28 Oct. 1975	28 Oct. 1975
,	Description	Drawing #2-1026-73F Urawing #2-1026-74F Drawing #2-1026-72F Drawing #2-1026-80F Drawing #2-1026-84F Drawing #2-1026-79F Drawing #2-1026-79F	Drawing transmittal Drawing #2-1026-P25F Drawing #2-1026-116F Drawing #2-1026-P23FB Drawing #2-1026-88F Drawing #2-1026-87F	.EDO3 Contract fund status report	.E002 Milestone cost report	.Public Voucher #11-04	.Contractors proposal for improved contacts for conveyor.	.Contractors proposal to delite ML-G-2212 from contract because of hi-shock requirement.

fon Date of Rept. transmittal 03 Nov. 1975 #2-1026-P31F #2-1026-114F #2-1026-114F #2-1026-120F #2-1026-121F	t. Date of Transmittal 5 03 Nov. 1975
03 Nov.	03 Nov.

The state of the s

R&D Contract #N00024-72-G-5500

Phase II

Remarks				
To		Defense Contract Audit Agency	E. J. Wahle, Administrative Officer DCASR-Cinti.	Code 6164
Date of Transmittal		05 Nov. 1975	17 Nov. 1975	18 Nov. 1975
Date of Rept.	•	05 Nov. 1975	3e 17 Nov. 1975	18 Nov. 1975
	Drawing #2-1026-146F Drawing #2-1026-71F Drawing #2-1026-77F Drawing #2-1026-81F Drawing #2-1026-89F Drawing #2-1026-99F Drawing #2-1026-99F Drawing #2-1026-99F Drawing #2-1026-19F Drawing #2-1026-112F Drawing #2-1026-113F Drawing #2-1026-119F Drawing #2-1026-119F Drawing #2-1026-119F Drawing #2-1026-149F Drawing #2-1026-149F Drawing #2-1026-149F Drawing #2-1026-149F Drawing #2-1026-149F Drawing #2-1026-149F	.Public Voucher #11-05	.Notification of work stoppage for lack of funds	COMPletion of BOOTAL of CDRL-drawing transmittal. Brawing #2-1026-GG Rev.A Drawing #2-1026-DG Rev.A Brawing #2-1026-SGJ Rev. A Brawing #2-1026-SGJ Rev. A

ensymmetriche ausgebereichen die eine Vereiche Westellereiche ausgebereiche der eurhalbereiche verstelle Ausber

Description	Date of Rept	Phase II Date of Transmittal	9.1	Remarks
•Minutes of Design Review Meeting. (Nov. 19 & 20,175) re. BOOlAE of the DCRL	25 Nov. 1975	25 Nov. 1975	Commander, NSEC Code 6164	
.Contractor proposal to delete door interlock switches.	25 Nov. 1975	25 Nov. 1975	Commander, NSEC Code 6164	
.Engineering Progress Report	21 Jan. 1976	21 Jan. 1976	Commander, NSEC Code 6164	
Request for Additonal Funds	21 Jan. 1976	21 Jan. 1976	E. J. Wahle, Contract Admini- strative Officer DCASDCinti.	
.Report Transmittal Log	21 Jan. 1976	22 Jan. 1976	Commander, NSEC Code 6164	
•Drawing List 2-1026 DLA Type "A" Conveyor		22 Jan. 1976	Commander, NSEC	
•Drawing List 2-1026-DLB Type "B" Conveyor		22 Jan. 1976	Commander, NSEC	
*Drawing List 201026 DLC Type "G" Conveyor		22 Jan. 1976	Commander, NSEC Code 6164	
Return of MOD P00012 Unsigned	13 Feb. 1976	13 Feb. 1976	Dept. of the Navy Code SEA 9244	Out-of-Funds. Unable to establish new data schedule
•Milestone Cost Rept	9 Mar. 1976	9 March 1976	Various	See Distribution Schedule
•Contract Funds Status Report •Return of MOD P00013 Signed	t 9 March 1976 10 March 1976	9 March 1976 10 March 1976	Various Commander,NSSC Code 0244	See Distribution Schedule
				ī

Report Transmittal Log R&D Contract #N00024-72-G-5500

	Remarks											
	To	Commander, NSEC Code 6164	Commander, NSSC 0244	Commander, NSEC Code 6164	Defense Contract Audit Agency	DCASD, Cinti	Commander, NSEC Code 6164	DGASD, Ginti.	Code 6164	Code 6164	Commander, NSEC Code 6164	•
* * * * * * * * * * * * * * * * * * *	Date of Transmittal	23 Mar. 1976	6 May 1976	29 June 1976	2 July 1976	16 July 1976	17 July 1976	30 July 1976	4 Aug. 1976	4 Aug. 1976	10 Oct. 1976	•
	Date of Rept.	s 24 Mar. 1976	6 May 1976	25 June 1976	2 July 1976	16 July 1976	17 July 1976	30 July 1976	4 Aug. 1976	4 Aug. 1976	14 Oct. 1976	:
	Descript on	Transmittal of Failure Modernderd Effect Analysis Report	•Return of MOD00014	Transmittal of Preliminary copy of the posidyne clutch brake trade-off study.	. Public Voucher II-06	.Report of Inventions	.Transmittal of Final copies of the posidyne clutch/brake trade-off study.	Revised Schedule for Phase II	•Transmittal of Minutes of Design Review Meeting held June 21 & 22, 1976	Sketches of Four Alternate Track Designs: 1026-T1 1026-T2 1026-T3	.Transmittal of the folbwing data:	Shock Load Galculations. shts. 1 thru 5

	_	Phase II	_	
Description	Date of Rept.	Date of Transmittal	To	Renarks
Impair test results, shts. 1 thru 4	14 Oct. 1976	15 Oct. 1976	Commander, NSEC Code 6164	
Protective Cover Drawing 2-1026-CL	=	:	=	
Track Calculations Dwg. 2-1026-SG7 sht. 1 Rev. B	=	:	8	
Track Calculations Jam Conditions Dwg. 2-1026-SCi /J sht. 1 of 3	=	=	:	
Track Calculations Jam Conditions Dwg. 2-1026-SC /J sht. 2 of 3	2	=	:	
Track Calculations Jam Conditions Dwg. 2-1026-SC: /J sht. 3 of 3	2	2	:	
Intermediate Track Dwg. 2-1026-315 sht l of l	:	£	:	
Cam follower clearance Dwg. 2-1026-T5 sht. 1 of	=	ŧ	:	
.Contract Funds Status Report	8 Nov. 1976	8 Nov. 1976	Various	See Distribution Schedule
.Milestone Cost Report	8 Nov. 1976	8 Nov. 1976 8 Nov. 1976	Various Defense Contract	See Distribution Schedule
.Transmittal for Final Cal-	10 Nov. 1976		Audit Agency-Gollmbus Commander, NSEC Code 6164	mbus
Carrier Assy. Carrier Fingers	: :	= =	= =	

R&D Contract #N00024-72-G-5500

	Remarks																				
-	To	Code 6164	z	=	=	•	=	*	=	*	=	:	Code 6164	Code 6164	=	=	=	=	•	<u>.</u>	2
Phase II	Date of Transmittal	10 Nov. 1976	:		•	•		•	=	•	•	•	9 Nov. 1976	29 Mar. 1977	:		•	2	:	•	=
•	Date of Bept.	10 Nov. 1976	:	=	:	2	•	2	=	8	=	*	9 Nov. 1976	29 Mar. 1977	=	=	:	=	2	8	:
-	Description	Finger Welds	Fingers with and without gussets	Carrier Backbone	Carrier Shaft Mounting Bolts	Carrier Shaft Welds	Garrier Shaft	Carrier Shaft Key & Keywa	Guide Arm	Camrol Mounting Arm	Guide Arm Cap	Cap Mounting Bolts	Transmittal of study on Internal bracing.	.Transmittal of Drawings	2-1026-136F	2-1026-137F	2-1026-145F	2-1026-161F	2-1026-165F	2-1026-169F	2-1026-172F

				•
Description	Date of Rept.	Date of Transmittal	To	Remarks
2-1026-174F	29 Mar. 1977	29 Mar. 1977	Commander, NAVSEC Code 6164	v
2-1026-175F		=	:	
2-1026-178F	:	•	:	
2-1026-182F	:	:	=	
2-1026-228F	:	•	:	
2-1026-292F	•	•	*	
2-1026-293F	•	•	:	
2-1026-295F	=	•	=	
2-1026-298F	•	:	:	
2-1026-300F	•	•	:	
2-1026-318F	•	•	:	
2-1026-319F	=	=	:	
2-!026-320F	•	•	•	
2-1026-336F	*	•	3	
2-1026-337F	:	•	:	
2-1026-74F	•		:	
2-1026-76F	:	*	:	
2-1026-125F	•	:	2	
2-1026-126F	:	•	=	
2-1u26-128F	2	•	2	
2-1026-130F	3	•	=	
2-1026-132F	:	•	:	

Report Transmittal Log R&D Contract #N00024-72-G-5500

	Remarks																						
	To	Commander, NAVSEC Code 6164	2	=		=	=	=	2	=	**	=	=	=	=	\$	=		=	Ξ	2	**************************************	*
Phase II	Date of Transmittal	29 Mar. 1977	:	=	=	:	:	•	2	:		ŧ	:	=	2	=	:	:	:	•	•	*	=
	Date of Rept.	29 Mar. 1977	2	2	•	=	*	•	•	8	=	*	2	2		•	Ξ	=	8	=	\$	*	:
	Description	2-1026-134F	2-1026-135F	2-1026-153F	2-1026-154F	2-1026-160F	2-1026-170F	2-1026-173F	2-1026-177F	2-1026-183F	2-1026-184F	2-1026-185F	2-1026-289F	2-1026-290F	2-1026-291F	2-1026-296F	2-1026-297F	2-1026-301F	2-1026-302F	2-1026-303F	2-1026-304F	2-1026-305F	2-1026-306F

12 May 1977 Page 16

Report Transmittal Log
R&D Contract #N00024-72-G-5500

		Phase II		
Description	Date of Rept.	Date of Transmittal	ď	Remarks
2-1026-307F	29 Mar. 1977	29 Mar. 1977	Commander, NAVSEC	
2-1026-308F	=	•	3	
2-1026-309F	2	=	•	
2-1026-310F	2	=	:	
2-1026-311F	=	=	:	
2-1026-312F	•	:	3	
2-1026-314F	**	•	:	
2-1026-323F	3	:	:	
2-1026-324F	=	:	:	
2-1026-325F	=	•	:	
2-1026-326F	=	:	=	
2-1026-327F	=	:	=	
2-1026-328F	=	:	8	
2-1026-331F	2	:	=	
2-1026-332F	=	:	=	
2-1026-333F	=	•	z	
2-1026-338F	=	=	5	
2-1026-339F	3	=	=	
2-1026-127F	Z	=	*	
2-1026-267F	2	:	=	
2-1026-167F	=	:	*	
2-1026-168F	=	:	=	
2-1026-171F	:	:		

The second of th

R&D Contract #N00024-72-G-5500

	Remarks																						
	To	, NAVSEC	•	=	=		=	•	•	2	=	:	2	=	=	=	•			, NAVSEC	=	=	
		Commander, NAVSEC		-			-	-	•		-	-			-	•	•		•	Commander, NAVSEC			_
Phase II	Date of Transmittal	29 Har. 1977	=	s	=	z	=	:	=	=	£	=	=	=	:	=	=	2	:	29 Mar. 1977	=	=	
•	Date of Rept	29 Mar. 1977	2	*	\$	2	*		•	:	5	•	2	2	*	•		:	2	29 Mar. 1977	:	=	
	Description	2-1026-176F	2-1026-179F	2-1026-181F	2-1026-322F	2-1026-329F	2-1026-330F	2-1026-P37F	2-1026-50F	2-1026-124F	2-1026-129F	2-1026-151F	2-1026-152F	2-1026-156F	2-1025-159F	2-1026-166F	2-1026-180F	2-1026-188F	2-1026-133F	.Letter Transmitting:	New Firm Schedule	P00016 (Signed)	

Report Transmittal Log
R&D Contract #N00024-72-G-5500

		Phase II		
escription	Date of Rept.	Date of Transmittal	To	Remarks
.Transmittal of Drawings:	04 April 1977	04 April 1977	Commander, NAVSEC Code 6164	
2-1026-P21F-A	:	=	3	
2-1026-P21F-B	=	=	2	
2-1026-P21F-G	=	=	2	
2-1026-71F (Sht. 1)	3	=	=	
2-1026-71F (Sht. 2)	=	=	2	
2-1026-71F (Sht. 3)	:	:	3	
2-1026-157F (Sht. 1)	:	:	:	
2-1026-157F (Sht. 2)	3	=	\$	
2-1026-158F (Sht. 1)	s	:	:	
2-1026-158F (Sht. 2)	3	=	•	
2-1026-159F	=	=	*	
·Transmittal of Drawings:	06 Apr11 1977	06 April 1977	Commander, NAVSEC Code 6164	
2-1026-P-3A-F	*	:	:	
2-1026-128F		:	:	
2-1026-162F	:	:	*	
2-1026-164F	:	=	:	
2-1026-189F	:	•	:	
2-1026-190F	:	:	:	
2-1026-191F	*	=	•	
2-1026-193F	:	=	=	
2-1026-197F	2	=	-	

Į

R&D Contract #N00024-72-G-5500

	Remarks																							
	To	Commander, NAVSEC Code 6164	=	=	*	*	2	*		*	•	2	2	•	*	•	•	*	•	•	=	=	:	
Phase II	Date of Transmittal	06 April 1977	=	=	*	=	•	an de	•		•	•	•	=	•	=		•	•	=	•	=	=	
	Date of Rept.	06 April 1977	•	•	:	*	•	•	=	:	•	-	•	:	=	•	:	•	:	=	=	=	•	•
	Description	2-1026-198F	2-1026-259F	2-1026-260F	.,2-1026-299F	2-1026-316F	2-1026-317F	2-1026-334F	2-1026-335F	2-1026-340F	2-1026-348F	2-1026-349F	2-1026-350F	2-1026-351F	2-1026-352F	2-1026-353F	2-1026-354F	2-1026-355F	2-1026-356F	2-1026-357F	2-1026-358F	2-1026-359F	2-1026-360F	

	_	Phase II	-	-
Description	Date of Rept.	Date of Transmittal	To	Remarks
•	06 April 1977	06 April 1977	Code 6164, NAVSEC	
2-1026-362F	*	a	•	
2-1026-363F	=	=	*	
2-1026-364F	3	=	=	
2-1026-365F	=	:	2	
2-1026-366F	=	=	:	-
2-1026-367F	:	•	2	
2-1026-368F	:	•	:	
2-1026-369F	:		:	
2-1026-321F	:	•	=	
2-1026-200F	=	=	:	
.Transmittal of Drawings:	11 April 1977	11 April 1977	Gode 6164 NAVSEG	
2-1026-272F	3	=	:	
2-1026-273F	•		:	
2-1026-274F	:	:	3	
2-1026-276F	:	•	:	
2-1026-278F	2	•	:	
2-1026-284F	*	:	=	
••2-1026-286F	=	:	=	
••2-1026-277F	•	•	=	
2-1026-275F	3	•	:	
2-1026-279F	:	=	=	

Report Transmittal Log R&D Contract #N00024-72-C-5500

	 Renarks	, NAVSEC	=	, NAVSEC		•	, NAVSEC		-		se Distribution List	ns Sec Distribution List	ontract ney Ohio	, NAVSEC		-	•		••
-	To	Commander, NAVSEC	-	gomander, NAVSEC	•	-	Commander, NAVSEC		-		Various	Various	Defense Contract Audit Agency Columbus, Ohio	Commander, NAVSEC	•	-	Ŧ	•	
Phase II	Date of Transmittal	11 April 1977	=	12 April 1977	=	=	14 April 1977	=	•	*	22 April 1977	22 April 1977	22 April 1977	05 May 1977	\$:	:	2	
	Date of Rept.	11 April 1977	•	12 April 1977	:	8	16 April 1977	=	:	8	17 April 1977	17 April 1977	22 April 1977	05 May 1977	:	•	*	*	
	Description	æ	2-1026-270F	.Transmittal of Drawings	2-1026-347F (Sht. 1)	2-1026-347F (Sht. 2)	.Letter Includings	Supplement to Calculations (BOUIAI)	DD250 #KCB0010	DD250 #CB0011	.Milestone Cost Report	.Contract Funds Status Report	.Public Voucher No. 11-06	.Letter Including:	Response to NAVSEC letter SER 278	Transmittal of Brawlugs	2-1026-F26 Rov G	2-1026-P20F Rev A	•

Page 22

Report Transmittal Log R&D Contract #N00024-72-C-5500

DD250 #KCB0012	Drawing Transmittal and Useable - on List	Report Transmittal Log to 12 May 1977	.Engr. Progress Report GDRL Item B001AF	2-1026-P47 Rev A	2-1026-P27 Rev A	Description	
:	=	=	12 May, 1977	:	05 May 1977	Date of Rept.	
z		:	12 May 1977	=	05 May 1977	Date of Transmittal	Phase II
:	•	•	Commander, NAVSEC	:	Commander, NAVSEC	То	
						Renarks	

Section III

Preliminary Engineering Drawing List

A. Conposit List

Shows which drawings apply to each of the three conveyors; shows latest revision letter and date; shows date of transmittal to NAVSEC.

B. Style "A" Conveyor -- 2-1026-DLA Rev B

Shows drawing needed to build and assemble a Style "A" Conveyor-top front loading conveyor.

C. Style "B" Conveyor -- 2-1026-DLB Rev B

Shows drawings needed to build and assemble a Style "B" Conveyor-top rear loading.

D. Style "C" Conveyor -- 2-1026-DLC Rev B

Shows drawings needed to build and assemble a Style "C" Conveyor-recess leading.

Since all the drawings shown on these list have already been transmitted to NAVSEC, and, since all the drawings are subject to further revision until they become approved final drawings during Phase III, the Contractor has elected to save space and cost by not including the preliminary drawings in the report.

	VYEY TYPE		DRAWIN	G NO.	ѕнтѕ.	DRAWING TITLE	REV. DATE	SUB. TO NAVSEC:	PRINT SIZE
Top Front	Page Page Page Page Page Page Page Page	Rocess							
Α	8	С	2-1026	REV.					
X	x	x	P21 FA P21 FB P21 FC		1 1 1	GENERAL ARRANGEMENT GENERAL ARRANGEMENT GENERAL ARRANGEMENT		4-4-77 4-4-77 4-4-77	E E
X X	X X	X	347F		1 of 2 2 of 2	ELECTRICAL CONTROLS ELECTRICAL CONTROLS		4-12-77 4-12-77	8
X X X	X X	×	P-3-AF 71F 157F 158F		1 1 of 3 2 of 3 3 of 3 1 of 2 2 of 2 1 of 2 2 of 2	CROSS SECTION .TRUNK ASSEMBLY		4-8-77 4-4-77 4-4-77 4-4-77 4-4-77 4-4-77 4-4-77	
X	x	×	97F 159F 160F	В	1 1 1	HEAD FRAME HEAD FRAME SPREADER	6-7-76	11-3-75 4-4-77 3-29-77	E E B
*****	*****	*****	98F 100F 85F 101F 102F 114F 301F 306F 307F 308F 310F 311F 312F 314F 336F 337F 338F 339F 302F 302F 302F 107F 108F 106F	AAAAA AAA	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	INTERMEDIATE FRAMELOWER FRAMEDOUBLE CROSS BARSIDE SHIELD LEFT HANDSIDE SHIELD RIGHT HANDSHIELD SUPPORTTRACK ANGLETRACK LOWER FRAMETRACK TIE PLATEJOINT BLOCKSUPPORT BLOCKSIDE SHIELD, LOWER LEFT HANDSIDE SHIELD, LOWER RIGHT HANDSINGLE CROSS BAR	1	11-3-75 11-3-75 11-3-75 11-3-75 11-3-75 11-3-75 11-3-75 3-29-77	
						-1-		 	,

X		YPE		DRAWIN	G NO.	SHTS.	DRAWING TITLE	REV. DATE	SUB. TO	PRINT SIZE
A 8 C 2-1026 REV. X X 99F B 1TAIL FRAME		E i	34							
X	7									
X	A	В	ပ	2-1026	REV.					
X	×	x	x	995			TAIL FRAME	24270	11.2.75	E
X				1					3-29-77	8
X	x	x	X	147F			LUBRICATION ACCESS HEAD END		11.2.75	E
X		İ							11-3-73	-
X						1 1	· · · · · · · · · · · · · · · · · · ·		11-3-75	E
X									1	E E
X						1 1			_	E
X						1 1				8
X	x								1	В
X	X					1 : 1	·		1	В
X	X		1							8
X	X					1				В
X	X									8
X		X	X	_		1			11-3-75	8
X	x	x	x	104F	Δ	1 of 3	SHIFI D ASSEMBLY	04070	11.275	E
X	X			1941	1 1					ε
X	x				,			8-16-76		٤
X	χÌ			77 5	1 ^		·	0-10-/0	i de la companya de	E
X	Ω.			1						
X	x					;	· · · · · · · · · · · · · · · · · · ·			E
X	x			_	1 . 1					
X	x		•	-	^	,	- · · · · · · · · · · · · · · · · · · ·	7-29-76		C
X	x						,	3 00 50		C
X	x				1 1			_		E
X			,		1 1	;				C
X					^	;		7-29-76		_
X							_ - _	7.00.00	_	E
X X X 140F A 1 INTERMEDIATE FRONT SHIELD 7-29-76 11-3-78 X X X 316F A 1 LOWER FRONT SHIELD 7-29-76 11-3-78 X X X 316F 1 ANGLE CLIP 4-6-77 X X X 7-29-76 11-3-78 4-6-77 X X X 7-29-76 11-3-78 4-6-77 X X X 7-29-76 11-3-78 4-6-77 X X X P25 F B 1 HEAD UNIT ASSEMBLY 6-7-76 9-26-78 X X X P24 F A 1 HEAD SHAFT 9-26-78 X X X P23 F8 A 1 HEAD CAM PLATE RIGHT HAND 5-14-76 9-26-78 X X X 87 F A 1 HEAD CARRIER SPROCKET 5-14-76 6-7-76 9-26-78 X X X 88 F A 1 HEAD CARRIER SPROCKET 5-14-76 6-15-76 6-15-76	x				1 ' 1					O
X X X P25 F B 1 .HEAD UNIT ASSEMBLY 6-7-76 9-26-75 X X X P24 F A 1 HEAD SHAFT 9-20-76 9-26-75 X X X P23 FB A 1 HEAD CAM PLATE RIGHT HAND 5-14-76 9-26-75 X X X REARING HOUSING, HEAD SHAFT 6-7-76 9-26-75 X X X 88F A 1 HEAD CARRIER SPROCKET 5-14-76 9-26-75 X X X X 116F A 1 LUBRICATION MOUNTING ASSEMBLY 6-15-76 9-26-75	X				1	1	3			C
X X X P25 F B 1 .HEAD UNIT ASSEMBLY 6-7-76 9-26-75 X X X P24 F A 1 HEAD SHAFT 9-20-76 9-26-75 X X X P23 FB A 1 HEAD CAM PLATE RIGHT HAND 5-14-76 9-26-75 X X X REARING HOUSING, HEAD SHAFT 6-7-76 9-26-75 X X X 88F A 1 HEAD CARRIER SPROCKET 5-14-76 9-26-75 X X X X 116F A 1 LUBRICATION MOUNTING ASSEMBLY 6-15-76 9-26-75	x				1 '' 1	1				C
X X X P25 F B 1 .HEAD UNIT ASSEMBLY 6-7-76 9-26-75 X X X P24 F A 1 HEAD SHAFT 9-20-76 9-26-75 X X X P23 FB A 1 HEAD CAM PLATE RIGHT HAND 5-14-76 9-26-75 X X X REARING HOUSING, HEAD SHAFT 6-7-76 9-26-75 X X X 88F A 1 HEAD CARRIER SPROCKET 5-14-76 9-26-75 X X X X 116F A 1 LUBRICATION MOUNTING ASSEMBLY 6-15-76 9-26-75	X		•			1		7-23-70		A
X X X X P25 F B 1 .HEAD UNIT ASSEMBLY 6-7-76 9-26-75 X X X P24 F A 1 .HEAD SHAFT 9-26-75 X X X P23 FA A 1 .HEAD CAM PLATE LEFT HAND 5-14-76 9-26-75 X X X P23 FB A 1 .HEAD CAM PLATE RIGHT HAND 5-13-78 9-26-75 X X X 87F A 1 .BEARING HOUSING, HEAD SHAFT 6-7-76 9-26-75 X X X 88F A 1 .HEAD CARRIER SPROCKET 5-14-76 9-26-75 X X X X 116F A 1 .LUBRICATION MOUNTING ASSEMBLY 6-15-76 9-26-75	X		,			1		ļ	4-6-77	8
X X X 116F A 1LUBRICATION MOUNTING ASSEMBLY 6-15-76 9-26-75				000 0				i		
X X X 116F A 1LUBRICATION MOUNTING ASSEMBLY 6-15-76 9-26-75)]	· · · · · · · · · · · · · · · · · · ·	_	9-26-75	E
X X X 116F A 1LUBRICATION MOUNTING ASSEMBLY 6-15-76 9-26-75					1 1 1]			9-26-75	C
X X X 116F A 1LUBRICATION MOUNTING ASSEMBLY 6-15-76 9-26-75	\Diamond				1 1	1	· · · · · · · · · · · · · · · · · · ·	_	ì	E E
X X X 116F A 1LUBRICATION MOUNTING ASSEMBLY 6-15-76 9-26-75	Q)				1 ' 1		_		9-26-75	E
X X X 116F A 1LUBRICATION MOUNTING ASSEMBLY 6-15-76 9-26-75					1 1	' 1		-		
3/3/0) 1	٠,				C
X X X P22 F A 1 .TAIL UNIT ASSEMBLY 6-10-76 9-5-75 X X X P8 A A 1TAIL CAM PLATE, RIGHT HAND 5-17-76 9-5-75	1	^	^	1105	A	'	LUBRICATION MOUNTING ASSEMBLY	6-15-76	9-26-75	С
X X X PB A A 1 TAIL CAM PLATE, RIGHT HAND 5-17-76 9-5-75	X				: 1		· · · · · · · · · · · · · · · · · · ·	6-10-78	9.5-75	E
	X					i i	,	5-17-76	9-5-75	E
X X X P8 8 A 1 TAIL CAM PLATE, LEFT HAND 6-2-76 9-5-75	X				1 1	1	· · · · · · · · · · · · · · · · · · ·	6-2-76	9-5-75	ε
311.76		,	,		1	1	1	7 1	9-5-75	A
X X X 73 F A 1SPRING SPACER 5-12-76 9-5-75	X	X	x	73 F	A	1	SPRING SPACER	5-12-76	9-3-75	Д
-2-							-2-	. !		

	NVEY TYPE		DRAWIN	G NO.	SHTS.	DRAWING TITLE	REV.	SUB. TO	PRINT
Top Frant Losding	op Rear	Recess Lasting		,					
A	В	С	2-1026	REV.					
	**************************************	**************************************	75 F 90 F F 93 F F P26 P27 P28 F F F F F F F F F F F F F F F F F F F	A AAAAAAA ACACBAA7AAAAAA mmaa aaaaaaaaa	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	BUSHINGADJUSTING ROD, CAM PLATETRACK RIGHT FRONTTRACK LEFT FRONTTRACK LEFT REARBEARING RETAINERTAIL CARRIER SPROCKETEND CAPBUSHINGSPRINGCARRIER ASSEMBLYCARRIER SHAFTCARRIER CHAINBUSHINGCARRIER LINK OUTER ASSEMBLYCARRIER LINK OUTER PLATECAM FOLLOWERCAPCARRIER LINK INNER ASSEMBLYCARRIER LINK INNER PLATECAM FOLLOWERCAM FOLLOWERCHAIN PIN LOADER-UNLOADER ASSEMBLYDOADER-UNLOADER ASSEMBLYPLATFORMPLATFORMUNLOADER BRACKET LEFT HANDUNLOADER BRACKET LEFT HANDUNLOADER BRACKET RIGHT HANDCLEVISCLEVIS PINSPRING RODCONNECTING ARMPIVOT BLOCKSHIFTER ARMGUIDE SHAFTGUIDE PLATEPIVOT STUDSPLIT COUPLING	5-11-76 5-14-76 5-14-76 5-14-76 5-11-76 5-11-76 5-13-76 5-13-76 5-13-76 5-10-76 5-10-76 5-10-76 5-13-76 5-13-76 5-13-76 5-12-76 5-12-76 5-12-76 5-12-76 5-12-76 5-11-76 5-11-76 5-11-76 5-11-76 5-11-76 5-11-76 5-11-76 5-11-76 5-11-76 5-11-76 5-11-76 5-11-76 5-11-76 5-11-76 5-11-76 5-11-76 5-11-76 5-11-76 5-11-76	9-5-75 9-5-75 9-5-75 9-5-75 9-5-75 9-5-75 9-5-75 9-5-75 9-5-75 9-5-75 9-5-75 6-27-75 6-27-75 6-27-75 6-27-75 6-27-75 6-27-75 6-27-75 6-27-75 6-27-75 6-27-75 6-27-75 6-27-75 6-27-75 6-27-75 6-27-75 6-27-75 7-18-75	ABBCCCBCAAA MDCCCABBBABBBA EMMEMCCBAAABBCBBAB
						-3-			

1	IVEY TYPE		DRAWIN	g no.	SHTS.	DRAWING TITLE	REV.	SUB. TO NAVSĒC	PRINT SIZE
p Frent	. 1 d .	e dies		_					
- 12 3 7 A	В	C	2-1026	REV.					
× × × × × × × × × × × × × × × × × × ×	× × × × × × × × × × × × × × × × × × ×	××××××	76 F 145 F 54 F 161 F 165 F 132 F 300 F 66 F 67 F 68 F 69 F 70 F 151 F 152 F 153 F 154 F	A	1 1 1 1 1 1 1 1 1	SPRINGSLEEVE BEARINGCROSS SHAFTTHRUST BEARINGTHRUST BEARINGFLANGED BUSHINGBALL HANDLETOP FRONT LOADER-UNLOADERROLLER ASSEMBLYLOAD BARBRACKETMOUNTING CLIPTOP REAR LOADER-UNLOADER ASSEMBLYTOP REAR LOADER-UNLOADERMOUNTING BRACKETMOUNTING BRACKETLOAD BAROVERTRAVEL LIMIT ASSEMBLY	5-11-76 5-14-76 5-11-76 5-11-76	3-29-77 3-29-77 3-29-77 3-29-77 7-18-75 7-18-75 7-18-75 7-18-75 7-18-75 7-18-75 7-18-77 3-29-77 3-29-77 3-29-77	BABAAAA ECBBB EESB Eu
x x x x x x x x x x x x x x x x x x x	× ××××××××××××××××××××××××××××××××××××	×××××××××××××××××××××××××××××××××××××××	166 F 180 F 181 F 169 F 170 F 171 F 172 F 173 F 184 F 185 F 289 F 291 F 292 F 293 F 295 F 296 F 297 F 298 F 319 F	AA	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	OVERTRAVEL LIMIT ASSEMBLY OVERTRAVEL LIMIT ASSEMBLY PLATFORM PLATFORM PLATFORM MOUNTING BRACKET CONTROL ARM ASSEMBLY LIMIT SWITCH BRACKET GUIDE PLATE DOOR ARM SPRING BRACKET ASSEMBLY CONTROL SHAFT DEFLECTOR MOUNTING BRACKET SPRING ROD YOKE PIVOT CHANNEL MOUNTING BRACKET BASE PLATE MOUNTING PLATE CONTROL ARM GUIDE PLATE THRUST BEARING SPRING	5-12-78	3-29-77	EECCABCA8C8888888AAA88AAA
						-4-		•	•

	TYPE	OR	DRAWIN	G NO.	ѕнтѕ.	DRAWING TITLE	REV. DATE	SUB. TO NAVSEC	PRINT SIZE
op Frent Sading	op Bear Dading	scess arting		,					
Α	B	C	2-1026	REV.					
×	×	X X	P37 F 200 F		1	.VERTICAL BACK MOUNTED 10 HP. DRIVE .HORIZONTAL RH AND LH SIDE 10 HP. DRIVE		3-29-77 4-6-77	E
X X X	X X X	X X X				MOTOR BRAKE REDUCER		Commercial Commercial Commercial	
*****************************	x xxxxxxx	·	124 F 125 F 126 F 127 F 128 F 132 F 133 F 134 F 135 F 136 F 137 F 324 F 325 F 327 F 328 F 329 F 329 F 320 F 321 F 320 F 321 F 325 F 327 F 328 F 329 F 329 F 320 F 321 F 325 F 327 F 328 F 329 F 329 F 320 F 321 F 321 F 322 F 323 F 325 F 326 F 327 F 328 F 329 F 329 F 320 F 321 F 322 F 323 F 325 F 326 F 327 F 328 F 329 F 329 F 320 F 321 F 322 F 325 F 326 F 327 F 328 F 329 F 329 F 320 F 321 F 322 F 323 F 325 F 326 F 327 F 328 F 329 F 320 F 320 F 320 F 320 F 321 F 322 F 323 F 325 F 326 F 327 F 328 F 328 F 329 F 329 F 320 F	A	111111111111111111111111111111111111111	DRIVE BASEJACK SHAFTCOUPLINGPILLOW BLOCKREDUCER DRIVE SPROCKETCHAIN GUARDTORQUE LIMITER GUARDBRAKE ADAPTER PLATEHEAD SHAFT SPACERHEAD SHAFT END CAPJACK SHAFT END CAPJACK SHAFT END CAPMOTOR SHAFT ADAPTORREDUCER SHAFT ADAPTORHEAD SHAFT DRIVE SPROCKETADJUSTING LUGADJUSTING LUGADJUSTING BRACKETHUBSPROCKET BASEWASHERSPROCKETTORQUE LIMITER ASSEMBLYCHAIN TAKE-UPTAKE-UP BRACKETTAKE-UP SLIDEIDLER SPROCKETPILLOW BLOCK BURN-OUTDRIVE BASEJACK SHAFT DRIVE SPROCKETJACK SHAFT DRIVE SPROCKETJACK SHAFT DRIVE SPROCKETJACK SHAFT DRIVE SPROCKETJACK SHAFT END CAPJACK SHAFT SPACER	4-1-77	3-29-77 3-29-77	医路路区路距路区路路路路路路路路路路路路路路路路路路路路路路路路路路路路路路路
dia ya an		من المناقع				-5-			:

•	NVEY TYPE		DRAWIN	G NO.	SHTS.	DRAWING TITLE	REV.	SUB. TO NAVSEC	PRINT SIZE
French	Per S	25.4 E							
-23-	-13:	: قِيْ							
_A	В	С	2-1026	REV.					
A XXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXX	B XXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXXX	××××××××××××××××××××××××××××××××××××××	352 F 349 F 354 F 357 F 356 F 355 F 353 F 360 F 361 F 362 F 363 F 364 F 365 F 366 F 367 F 174 F 175 F 176 F 177 F 178 F 179 F 228 F	REV.	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	JACK SHAFT SPACERREDUCERHEAD SHAFT DRIVE SPROCKETHUBSPROCKET BASESPROCKETADJUSTING SCREWCHAIN GUARD, UPPERCHAIN GUARD, LOWERPILLOW BLOCK SPACERCHAIN TAKE UPTAKE-UP BRACKETTAKE-UP SLIDEIDLER TAKE-UP SPROCKETLIMIT SWITCH ASSEMBLYMOUNTING BRACKETSWITCH ACTUATORMOUNTING PLATESTUD BOLTSPACER JAM LIMIT ASSEMBLYMOUNTING BLOCKMOUNTING BLOCKMOUNTING BLOCKCABLE GUIDE ASSEMBLYCOUNTERWEIGHTCABLE ASSEMBLYCOUNTERWEIGHT BRACKET ASSEMBLYCABLE BRACKET CLEANOUT COVERPACKAGE GUARDSERIAL PLATELUBE CHART	5-20-78	4-6-77 4-6-77 4-6-77 4-6-77 4-6-77 4-6-77 4-6-77 4-6-77 4-6-77 4-6-77 4-6-77 4-6-77 4-6-77 4-6-77 4-6-77 4-6-77 4-6-77 3-29-77 3-29-77 3-29-77 3-29-77 3-29-77 3-29-77 3-29-77 3-29-77 3-29-77 3-29-77 3-29-77 3-29-77 3-29-77 3-29-77 3-29-77 3-29-77 3-29-77 3-29-77 3-29-77 4-6-77 4-6-77 4-6-77 4-6-77	BBEBCBUECCSBCBBAAAA EAACBACA CCBC
× × × × × × ×	X X X X X X	X X X X X X	270 F 284 F 273 F 274 F 286 F 277 F 287 F 299 F 272 F 275 F 276 F 279 F		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	CONTROL STATIONMOUNTING PLATELOCK-OUT COVERHINGED COVERMOUNTING CLIPLOCK PLATEINSTRUCTION CHART INTERMEDIATE STATIONWARNING PLATEHINGED PLATEINSTRUCTION CHART MASTER STATIONSPACERINSTRUCTION CHART MACHINE CONTROL STA.		4-11-77 4-11-77 4-11-77 4-11-77 4-11-77 4-11-77 4-11-77 4-11-77 4-11-77 4-11-77 4-11-77	C E B C C A B C B B C A C

	REVISIONS	3	
REV.	DESCRIPTION	DATE	APPROVED
в/с	GEN. REVISION	5/20/77	

Α.	SUPPLEMENTING SHIP EQUIPMENT DRAWING:
	EQUIPMENT MFGR'S. DRAWING NUMBER VERTICAL STORES HANDLING CONVEYOR
В.	APPLICABLE SPECIFICATION
C.	NAVY CONTRACT
	MFGR. ORDER NUMBER
E.	MFGR'S. IDENTIFICATION: SERIAL NO.
	RATING:
	DESCRIPTION:
F.	APPLICATION: SHIPBOARD STORE HANDLING
G.	SHIP IDENTIFICATION:
Н•	NO. ITEMS PER SHIP NO. SHIPS INVOLVED
I.	REFFRENCE DRAWINGS: DRAWING LIST SHEETS 2 THROUGH 13
J.	TECHNICAL MANUAL NO.
K•	COMPONENT IDENTIFICATION NO.
L.	NOTES:

		ECOR NEY LASK CORPORATION 400 HEATON ST + HAMILTON, OHIO 45011 + 513 663-1277	
	PREPARED	DRAWING LIST	
•	CHECKED	VERTICAL 100 LB. PACKAGE CONVEYOR	
	ENGINEER	TRUNK STYLE TOP FRONT LOADING TYPE A	
		SIZE CODE IDENT. NO. DRAWING NO.	REV
		A 07586 2-1076-DIA	۳.
		SCALE SHEET OF 1	٠,

CODE IDENT. NO.	DWG. NO.	REV.		DWG. TIT	LE		CATE	GORY
	2-1026							
	P21FA			eneral Arrangem op Front Loadin			Ã,	B,C,G
	347F (1 347F (2	of 2) of 2)		lectrical Contr lectrical Contr			G G	
	P3-AF		С	ross Section			Α	
	71F (1 o	£ 3)		Trunk Assembly Trunk Assembly Trunk Assembly			A, A, A,	В
	97F	В		.Head Frame			F	
	98F	A		.Intermediate F	rame		F	
	99F	В		.Tail Frame			F	
	100F	A		.Lower Frame		į	F	
	101F	A		Side Shield	LH		F	
	102F	Α	•	Side Shield	RH		F	
	114F	Α	•	Shield Suppor	t		F	
	106F	A	•	Single Cross	Bar		F	
	107I [.]	A	•	Side Shield	LH		F	
	108F	A		Side Shield	RH		F	
	301F			Track Angle			F	
	306F			Track Lower F	rame		F	
	307F			Track Lower F	rame		F	
	308F			Track Lower F	rame		F	
	309F		•	Track Lower F	rame		F	
	310F			Track Lower F	rame		F	
	311F		•	Track Lower F	rame		F	
····	85F			. DOUBLE CROS			۴	
			SIZE	O7 586	DWG. N 2-1026			REV.
					1	SHEET 2		

A STATE OF THE PARTY OF THE PAR

THE PERSON NAMED IN

CODE IDENT, NO.	DWG. NO.	REV.			DWG. TITI	_E		CATE	GORY
	2-1026								
	312F			Track	Lower F	rame		F	
	314F			Track	Lower F	rame		F	
	336F			Track	Tie Pla	te		F	
	337F			Track	Tie Pla	te		F	
	338F			Joint	Block			F	
	339F		•	Suppor	t Block			F	
	304F			LH Cha	nnel Su	pport		F	
	305F			RH Cha	nnel Su	pport		F	
	302F			Joint	Block			F	
	303F			Suppor	t Block			F	
	74F	A		Rod Ho	older			F	
	147F			Tubri cai	ion Acc	ess Head End		н	
},	14/1			Dubtica	LON ACC	css nead and			
								ļ.	
1	<u> </u>		SIZE	1	ENT. NO.	1	. NO.		REV.
			A	37	786	2-1026	, DLA		В
				-			SHEET	3	

CODE IDENT. NO.	DWG. NO.	REV.		DWG. TIT	LE		CATE	GORY
	2-1026							
	104F	A	•	Shield Assembly	,		A,B,	3
	83F	A	•	.Front Shield E	ext.		F	
	113F	A		.Int. Front Shi	eld		F	
	140F	Α		.Int. Front Shi	.eld		F	
	105F	Α		.Lower Front Sh	ield		F	
	81F	A		.Head Rear Shie	eld		F	
	77F			.Int. Rear Shie	eld		F	
	89F			.Filler Rear Sh	ield		F	
	109F	A	•	.Lower Rear Shi	eld		F	
	112F		•	.Lower Rear Shi	.eld		F	
	111F	A	•	.Side Shield Ta	il Ext.		F	
	146F	Α		.Lower Front Sh	ield		F	
i 	82F	A	•	.Head Side Shie	eld		F	
	115F	A	•	.Filler Front S	hield		F	
	316F		•	.Angle Clip			ř.	
	317F		•	.Clip			F	
						;		
	L		SIZE	CODE IDENT. NO.	DWG. I	NO.		REV.
			A	07586	2-1026	DLA		C
						SHEET	<u>_</u>	

CODE IDENT. NO.	DWG. NO.	REV.		DWG.	TITLE		CATE	GORY
	2-1026							
	117F			.Door Frame U	pper		F	
	118F			.Door Frame	nter. Square Co	rner	F	
	119F			.Door Frame	nter. Round Cor	ner	F	
	148F			.Door Frame I	ower		F	
	120F			Side Plate			F	
	121F			Corner Plat	e		F	
	122F			Side Plate			F	
	138F			Bottom Plat	e		F	
	139F			Top Plate			F	
	142F	i		Top Plate			F	
	144F		•	Bottom Plat	e		F	
:	P25F	В		Head Unit Ass	embly		A,1	R
	P23FA	D A		.Head Cam Pla	-		F	
	P23FB	A		.Head Cam Pla			F	
	P24F	A	}	.Head Shaft	141		F	
	87F	A	1		ing (Head Shaft	.)	F	
	88F	A		.Carrier Spro	-		F	
	116F	A			Mounting Assemb	olv	H	
	1101	^	•	• nabi i ca ci on	nocherny Assemb	,14	**	
······································			SIZE	CODE IDENT. N	[REV.
			A	07586	2-1026	DLA		В
						SHEET 5		

CODE IDENT. NO.	DWG. NO.	REV.		DWG. TIT	LE	CAT	regory
	2-1026						
	P22F	A		Tail Unit Assem	bly	А	, В
	P8A	A		.Tail Cam Plate	RH	F	,
	P8B	A		.Tail Cam Plate	LH	F	ı
	72F	A		.Spring Retaine	r	F	1
	73F	A		.Spring Spacer		F	ı
	75F	A		.Bushing		F	ı
	78F			.Adj. Rod		F	1
	90F	A		.Track Right Re	ar	F	1
	91F	A		.Track Right Re	ar	F)
	92F	A		.Track Lift Fro	nt	F)
	93F	A		.Track Lift Rea	r	F	•
}	94F	A		.Bearing Retain	er	F	•
	95F	A		.Tail Sprocket		F	•
	96F	A		.End Cap		F	•
	103F	A		.Bushing		F	•
	318F			.Spring		F	•
						•	
'	1	1	SIZE	CODE IDENT. NO.	DWG.	NO.	REV.
			A	07586	2-1026	DLA	C
					1	SHEET 6	<u> </u>
<u> </u>						- سحت	

CODE IDENT. NO.	DWG. NO.	REV.		C	WG. TITI	.Ε		CATE	GORY
	2-1026								
	P20F	Ą	. (Carrier A	ssembly	Ž.	į	A,G,	, Н
	P26	٥	•	.Carrier				F	
	P27	Α	•	.Guide Ar	rm			F	
	P28	c	•	.Carrier	Shaft			F	
	41F	В		.Chain Dr	awing			F	
	162F	A	•	Chain P	in			F	
	49F	A		.Carrier	Link I	nner Assembly		F	
	45F	A		Carrier	Link	Inner		F	
	43F	A		Bushing	ſ		!	F	
	46F	A		.Cam Foll	.ower		İ	F	
	164F	A		.Cam Foll	ower F	langed	i	F	
1	47F	A		.Cap				F	
	163F	Α		.Spacer				F	
	48F	A		.Carrier	Link -	Outer Assemb	ly	F	
	44F	A		Carrier	Link	- Outer		F	
			·						
	:							 	
									:
	,								
									ļ
	<u> </u>	<u> </u>	SIZE	CODE IDE	NT. NO.	DWG. I	NO.	1	REV.
			A	075		2-1026			B
							SHEET	7	

CODE IDENT. NO.	DWG. NO.	REV.		DWG. TIT	LE	CATEGOR	۹Y
	2-1026	_					
		₽ pf 2) pf 2)		Loader Unloader Loader Unloader		A,B A,B	
	P150F	A		Loader Unloader	Assembly	A,B	
	51F	Α		.Platform		F	
	149F			.Platform		F	
	52F	A		.Bracket Assemb	oly RH	F	
	182F			Flanged Bushi	.ng	F	
	53F	A		.Bracket Assemb	oly LH	F	
	182F		.	Flanged Bushi	.ng	F	
	54F	Α		.Cross Shaft		F	
	55F	A		.Clevis Arm		F	
	56F	A		.Clevis		F	
	57F	A		.Clevis Pin		F	
	58F	A		.Spring Rod		F	
	59F	A		.Connecting Arm	ı	F	
	60F	Α		.Pivot Block		F	
	61F	A		.Shifter Arm		F	
	62F	A		.Guide Shaft		F	
	63F	A		.Guide Plate		F	
	64F	A		.Pivct Stud		F	
	65F			.Split Coupling		F	
	76F			.Spring		F	
	145F			.Sleeve Bearing		F	
	161F			.Thrust Bearing		F	
	165F			.Thrust Bearing		F	
	300F			.Ball Handle		F	
			SIZE	CODE IDENT. NO.	DWG. N	1	E۷
			A	07586	2-10261	DLA B	ı
						SHEET 8	

	CODE IDENT. NO.	DWG. NO.	REV.		DWG. TIT	LE		CATE	GORY
		2-1026							
ł		66F	A		Top Front Loade	er Unloader		Α,	В
		69F			.Bracket RH &	LH		F	
		70F			.Mounting Clip			F	
		67F	A	•	.Roller Assembl	У		F	
		68F	A		.Load Bar			F	
		166F	Α		Top Overtravel	Limit Assembl	.y	Α,	В
		167F			.Platform			F	
		168F			.Spring Bracket	Assembly		F	
		289F		•	Mounting Brac	ket	i	F	
		290F			Spring Rod			F	
		291F		•	Yoke			F	
		29 2F			Pivot			F	
		293F			Channel			F	
		295F		•	.Mounting Brack	et		F	
		170F		•	.Control Arm			F	
		171F		•	.Limit Switch B	racket		F	
		296F		•	Base Plate			F	
		297F		•	Mounting Plat	e		F	
		298F		•	Control Arm G	uide Plat e		F	
		172F		•	.Guide Plate			F	
		173F			.Door Arm			F	
		320F		•	.Spring		i	F	
		319F		•	.Thrust Bearing	1		F	
1	<u></u>		L	SIZE	CODE IDENT. NO.	DWG.	NO.		REV.
				A	07586	2-1026	DLA		C
							SHEET	l 3	
Ĺ	orm No. 177-8			L			1 011221		

CODE IDENT. NO.	DWG. NO.	REV.		DWG. TIT	LE		CATEGORY	Υ
	2 1026							
	2-1026							
	50F	A		Jam Limit Assen	nbly		A,B	
	174F			.Mounting Block	тор		F	
	175F			.Mounting Block	•		F	
	176F			.Cable Guide As	sembly		F	
	177F			.Counterweight			F	
	178F			.Cable Assembly	•		F	
	228F			Cable Bracket	:		F	
	179F			.Counterweight	Bracket Assemb	oly	F	
	P37F		•	Vertical Back N	iounted 10 HP I	rive	G, Н	
	200F			Horizontal RH &	LH Side 10 HF	Drive	G,H	
	10 HP FR 286T		•	.Motor			F	
	J80001	,		.Brake			F	
	HU-47797	O-FM		.Reducer			F	
	124F			.Drive Base			F	
	125F			.Jack Shaft			F	
	126F	'		.Coupling			F	
	127F	i		.Pillow Block			F	
	128F			.Reducer Drive	Sprocket		F	
	188F			.Chain Guard			F	
	132F	,		.Torque Limiter	Guard		F	
	133F	,		.Brake Adapter	Plate	i	F	
	134F			.Head Shaft Spa	cer		F	
			SIZE	CODE IDENT. NO.	DWG. N	Ο.	RE	V.
			A	07586	2-1026	DLA	C	
						SHEET	10	

CODE IDENT. NO.	DWG. NO.	REV.		DWG. TIT	LE		CAT	EGORY
	2-1026							
	135F			.Head Shaft End	l Cap	:	F	
	136F			.Jack Shaft Spa	icer		F	
	137F			.Jack Shaft End	l Cap		F	
	334F			.Motor Shaft Ad	laptor		F	
	335F			.Reducer Shaft	Adaptor		F	
	129F			.Head Shaft Dri	ve Sprock e t		F	
	323F			Adjusting Lug	Ī		F	
	324F			Adjusting Lug	ŗ		F	
	325F			Adjusting Bra	cket		F	
	326F			Hub			F	
	327F	A	•	Sprocket Base	:		F	
	328F			Washer			F	
' > I	329F		•	Sprocket			F	
	321F		•	.Torque Limiter	Assembly		F	
	130F		•	.Chain Take-Up		j	F	
	330F		•	Take-Up Brack	et		F	
	331F		•	Take-Up Slide			F	
	332F		•	Idler Sprocke	t		F	
	333F			.Pillow Block B	urn-Out		F	
	189F		•	.Drive Base			F	
	193F		•	.Adjusting Plat	e		F	
	191F			.Jack Shaft			F	
	259F		•	.Jack Shaft Dri	ve Sprocket		F	
	260F			.Jack Shaft Dri	ven Sprocket		F	
1			SIZE	CODE IDENT. NO.	DWG I			REV.
			A	07586	2-1026	DLA		B
					<u> </u>	SHEET	 \	
Form No. 177-8				<u> </u>		L	·	

L. 24.44

Late Steel

CODE IDENT. NO.	DWG. NO.	REV.		DWG.	TITLE	CAT	EGORY
	2-1026						
	197F			.Pillow Bloc	k	F	
	348F		.	.Pillow Block	k Burn-Out	F	
	350F	,		.Jack Shaft	End Cap	F	
	351F			.Jack Shaft	Spacer	F	
	352F			.Jack Shaft	Spacer	F	
	349F			.Reducer		F	
	354F			.Head Shaft	Drive Sprocket	F	
	357F			Hub		F	
	356F			Sprocket Ba	ase	F	
	355F			Sprocket		F	
	353F			.Adjusting So	crew	F	
	198F			.Chain Guard	, Upper	F	
	358F			.Chain Guard	, Lower	F	
	359F		•	.Pillow Block	k Spacer	F	
	360F		•	.Chain Take-	Jp	F	
	361F	i	•	Take-Up Bra	acket	F	
	362F		•	Take-Up Sl:	ıde	F	
	363F		•	Idler Take-	-Up Sprocket	F	
	340F		•	.Limit Switch	n Assembly	Г	
	369F		•	Mounting Br	racket	F	
	364F		•	Bracket		F	
	365F		•	Switch Actu	uator	F	
	366F		•	Mounting Pl	late	F	
	367F		•	Stud Bolt		F	
	368F		•	Spacer		F	
			SI7E	CODE IDENT. N	O. DWG. N	10.	REV.
			Α	07586	2-10261	DLA	
						SHEET : 2	L

	CODE IDENT. NO.	DWG. NO.	REV.		D	WG. TIT	LE		CATE	GORY
J		2-1026			-					
		141F			.Cleanout	Cover	•		F	, G
		143F			.Package (Guard			F	
		190F			.Serial P	late			D	
		270F			.Lube Char	rt			Н	
		284F			.Control s	Statio	on		В	, G
1		273F			Mounting	g Plat	:e		F	
		274F			Lock-Ou	t Cove	er		F	
		286F			Hinged	Cover			F	
		277F			.Mounting	Clip			F	
		278F			Lock Pla	ate			F	
		287F		•	Instruct	tion C	hart Intermed	iate	D	
		299F		•	.Warning	Plate			D	
		272F			Hinged 1	Plate			F	
		275F			Instruct	tion C	hart Master S	tation	D	
		276F			Spacer				F	
		279F		•	Instruct Station	tion C	hart Machine	Control	D	
	-	805-1400	066	D	oor Water	tight			F	,Н
				SIZE	CODE IDEN		DWG. 1 2-1026[REV.
								SHEET 1	 3	
L	orm No. 177-8				<u>\</u>					

		T		REVISIONS	·	
		REV.	DE	SCRIPTION	DATE	APPROVED
		B/C	GEN. REVISIO	V	5/20/77	
						<u> </u>
Α.	SUPPLEMENTING SHIP I	QUIPMENT	DRAWING:			
	EQU	JIPMENT		MFGR'S DRAWING NUM	EER	
	VERTICAL STOR					
В∙	APPLICABLE SPECIFICA	ATION				
C.	NAVY CCNTRACT					,
D.	MFGR.			ORDER NUMBER		
E.	MFGR'S. IDENTIFICATI					
	RATI	ENG:				
F.						
G.	SHIP IDENTIFICATION:					
Н.	NO. ITEMS PER SHIP					
I.	REFERENCE DRAWINGS:	DRAWING	LIST SHEETS	2 THROUGH 14		
J.	TECHNICAL MANUAL NO.	•				
K.	COMPONENT IDENTIFICA	ATION NO.	•	and the second distributed		
L.	NOTES:					
		<u> </u>		WODDIY		A 71004
				KORRY 400 HEATON ST + HAMILTON		
	PREPARE	D			AWING LIST	
	CHECKE			VERTICAL 100 LB. F TRUNK S	TYLE)r
	ENGINES	R	SIZE	TOP REAR LOADING CODE IDENT. NO.	TYPE B DRAWING	NO. REV.
! 			A	07586	2-1026 D LB	R
	i i					

SCALE

SHEET 1

OF 14

	CODE IDENT. NO.	DWG. NO.	REV.		DWG. TI	TLE		CAT	EGORY
ļ		2-1026							
		P21FB			eneral Arrangemop Rear Loading		:	А,В,	C,G
		347F (1 o 347F (2 o			lectrical Contro lectrical Contro			G G	
	!	P3-AF		Cr	coss Section			A	
		157F (1 o 157F (2 o			Trunk Assembly Trunk Assembly			A, A,	
		97F	ь		Head Frame			F	
		98F	A		Intermediate F	rame		F	
		99F	8		Tail Frame			F	
		100F	Α		Lower Frame			F	
		101F	Α		.Side Shield L	·i		F	
, }		102F	A		.Side Shield I	RH		F	
		114F	A		.Shield Support	Ė		F	
		106F	Α	• • •	.Single Cross B	Bar		F	
		107F	A	• •	.Side Shield L	ī	1	F	
		108F	Α	• •	.Side Shield R	Ĭ	}	F	
		301F		••	.Track Angle			F	
		306F			.Track Lower Fr	rame		F	
		307F		• •	.Track Lower Fr	ame	İ	F	
		308F		• •	.Track Lower Fr	came		F	
		309F			.Track Lower Fr	ame		F	
		310F			.Track Lower Fr	ame		F	
		311F			.Track Lower Fr	ame	1	F	
		85F DOUBLE CROSS BAR					F		
				SIZE A	CODE IDENT. NO. 07586	DWG. N 2-1026			REV.
							SHEET 2	<u>_</u>	
-	rm No. 177 8								

Form No. 1778

CODE IDENT. NO.	DWG. NO.	REV.		DWG. TIT	LE	CAT	EGORY
	2-1026						
	312F			.Track Lower Fr	ame	F	
	314F			.Track Lower Fr	ame	F	
	336F			.Track Tie Plat	e	F	
	337F			.Track Tie Plat	e	F	
	338F			.Joint Block		F	
	339F		••	.Support Block		F	
	304F		••	.LH Channel Sup	port	F	
	305F	[• •	.RH Channel Sup	port	F	
	302F		• •	.Joint Block		F	
	303F			.Support Block		F	
	74F	A		.Rod Holder	F		
	147F		.L	ubrication Acce	ss Head End	н	
			SIZE	CODE IDENT. NO.	DWG. NO	<u> </u>	REV.
			Α	07586	2-1026	DLB	B

SHEET 3

CODE		Γ			-				********************************
IDENT. NO.	DWG. NO.	REV.			DWG. TI	TLE		CATI	EGORY
	2-1026								
	104F	Α	.5	hield A	ssembly			Α,	В
	83F			Front Sl	nield E	ct.		F	
	113F	Α		Int. Fro	ont Shie	eld		F	
	140F	A		Int. Fro	ont Shie	eld		F	
	105F	Ą	••	Lower F	cont Sh	ield		F	
	81F	A		Head Rea	ar Shie	ld		F	
	77F	A		Int. Rea	ar Shie	ld		F	
	89F			Filler 1	Rear Sh	ield		F	
	109F	A	ļ	Lower R	ear Shi	eld		F	
	112F			Lower R	ear Shi	eld		F	
	111F	Α	••	Side Sh	ield Ta:	il Ext.		F	
	146F	A	• •	Lower F	ront Sh	ield		F	
	82F	A		Head Sid	de Shie	ld		F	
	115F	A	• •	Filler 1	Front Sl	nield		F	
	316F		• •	Angle C	lip			F	
	317F			Clip				F	
									•
•			SIZE	CODE ID		1	G. NO.		REV.
		į	A	075	86	2-1026	DLB		C
							SHEET		
m No. 177-8	·								

CODE	T	Γ					······
CODE IDENT. NO.	DWG. NO.	REV.	<u></u>	DWG. TIT	LE	CAT	EGORY
!	2-1026						
	117F		•	Door Frame Uppe	er	F	
	118F		•	Door Frame Inte	er. Square Corner	F	
	119F		•	Door Frame Inte	er. Round Corner	F	
Ì	148F			Door Frame Lowe	er	F	
	120F		• •	Side Plate		F	
	121F		•	Corner Plate		F	
	122F			Side Plate		F	
	138F			Bottom Plate		F	
	139F		• •	Top Plate		F	
	142F			Top Plate		F	
	144F			.Bottom Plate		F	
	P25F	E	.1	Head Unit Assemb	oly	A,	, B
	P23FA	Α		Head Cam Plate	LH	F	
	P23FB	Α		Head Cam Plate	RH	F	
	P24F	А		Head Shaft		F	
	87 F	A		Bearing Housing	(Head Shaft)	F	
	88F	A		Carrier Sprocke	et (Head)	F	
	116F	Α		Lubrication Mou	inting Assembly	н	
1	<u> </u>		SIZE	CODE IDENT. NO.	DWG. NO.		REV.
			A	07586	2-1026 DLE	3	B

SHEET 5

CODE IDENT. NO.	DWG. NO.	REV.			DWG. TITI	LE		CATE	ORY		
	2-1026										
	P22F	A	. Та	ail Unit	Assemb	ly		A,B			
	P8A	A		rail Cam	Plate	RH		F			
	P8B	A		rail Cam	Plate	TH		F			
	72F	A	:	Spring R	etainer			F			
	73F	A		Spring S	pacer			F			
	75 F	A	1	Bushing				F			
	78F		• • •	Adj. Rod				F			
								_			
	90F	A		Track Ri				F			
	91F	A		Track Ri				F			
	92F	A	••	Track Li	ft Fron	t		F			
	93F	Α	••	Track Li	ft Rear			F			
	94F	Α		Bearing	Retaine	r		F			
	95F	A	••	Tail Spr	ocket			F	ı		
	96F	A		End Cap				F			
	103F	A	 ••	Bushing				F			
	318F			Spring				F			
	:										
								<u> </u>			
			SIZE	CODE ID		DWG. N		a	REV.		
			A	075	000	2-1026	UL				
				_			SHEET	6			

CODE												
CODE IDENT. NO.	DWG. NO.	REV.			DWG. TIT	LE		CATE	GORY			
	2-1026											
	P20F	А	.Ca	arrier A	ssembly			A,G	,н			
	P26	C	(Carrier				F				
	P27	Α	(Guide Ar	m			F				
	P28	c	(Carrier	Shaft			F				
	41F	В		Chain Dr	awing			F				
	162F	A	• •	.Chain P	in			P				
	49F	Α	(Carrier	Link In	ner Assembly		F				
	45F	A	• •	.Carrier	Link I	nner		F				
	43F	A	• •	.Bushing				F				
<u> </u>	46F	A	(Cam Foll	ower			F				
	164F	A	(Cam Foll	ower Fl	anged		F				
' ት	47F	A		Cap				F				
	163F	A	• •	Spacer				F				
	48F	A	• •	Carrier	Link -	Outer Assembly	y	F				
	44F	A	••	.Carrier	Link -	Outer		F				
1	1	<u> </u>	SIZE	CODE ID	ENT. NO.	DWG.	NO.	l	REV.			
			A		86	2-1026		5	B			
				l			SHEET	7				
Form No. 127.9	·				X							

CODE IDENT. NO.	DWG. NO.	REV.		DWG. TIT	LE	CATE	GOR'		
	2-1026								
	PlOF (1 o: PlOF (2 o:			ader Unloader A ader Unloader A		F			
	P150F	Α	Loader Unloader Assembly						
	51F	A	P	latform		F			
	149F		Р	latform		F			
	52F	A	Bra	cket Assembly	RH	F			
	182F			Flanged Bushing		F			
	53F	Α	B	racket Assembly	LH	F			
	182F		• • • •	Flanged Bushing		F			
	55¥	A	c	levis Arm		F			
	56F	A	c	levis		F			
	57 F	A	c	levis Pin		F			
	58F	A	s	pring Rod		F			
	59F	A	c	onnecting Arm		F			
	60F	A	P	ivot Block		F			
	61F	A	s	hifter Arm		F			
	62F	A	G	uide Shaft		F			
	63F	Α	G	uide Plate		F			
	64F	А	P	ivot Stud		F			
	65F		s	plit Coupling		F			
	76F	,	s	pring		F			
	145F		s	leeve Bearing		F			
	161F	A	T	hrust Bearing		F			
	165F		T	hrust Bearing		F			
	300F		B	all Handle		F			
			SIZE	CODE IDENT. NO.	DWG. NO.		RE		
			Α	07586	2-1026 DLB		B		
					SHEE	T &			

CODE IDENT. NO.	DWG. NO.	REV.		DWG.	TITLE		CATE	GURY
	2-1026							
	151F		.To	op Rear Loade:	r Unloader Asser	nbly	Α,	В
	152F			op Loader Un	loader		F	
	153F		1	Mounting Brack	ket		F	
	154F			Load Bar			F	
	50 F	А	.Ja	am Limit Assen	nbly		Α,	В
	174F			Nounting Block			F	
	175F			founting Block			F	
	176F			Cable Guide A			F	
	177F			Counterweight	_		F	
	178F			able Assembly	,		F	
	228F			Cable Bracket			F	
,	179F			Counterweight	Bracket Assemb	Ly	F	
			SIZE	CODE IDENT. N	D. DWG. 2-1026			REV.
						SHEET	9	

CODE										
CODE IDENT. NO.	DWG. NO.	REV.		DWG. TIT	LE		CATE	GORY		
	2-1026									
	180F	A	.To	p Overtravel Li	mit Assy. Re	ear Loadir	g A,	3		
	181F		P	latform			F			
	169F		P	latform Mountir	g Bracket		F			
	183F		R	each Arm Assemb	ly		F			
	168F		s	pring Bracket A	ssembly		F			
	289F		1	Mounting Bracke	t		F			
	290F		• • • •	Spring Rod						
	291F			Yoke	F					
	292F		Pivot							
	293F	}		Channel			F			
	295F		M	ounting Bracket			F			
	170F		c	ontrol Arm Asse	mbly		F			
	171F		L	imit Switch Bra	cket		F			
	296F		•••]	B ase Plate			F			
	297F		1	Mounting Plate			F			
	298F			Control Arm Gui	de Plat e		F			
	173F		De	oor Arm			F			
	172F		G1	uide Plate			F			
	184F		c	ontrol Shaft			F			
	185F		D	eflector			:			
							F			
	320F		s	pring						
		-								
	SIZE CODE IDENT. NO. DWG. NO.				REV.					
			Α	07586	2-102	GDLB		C		
					<u> </u>	SHEET				
			<u> </u>			OHEET				

CODE IDENT. NO.	DWG. NO.	REV.	DWG. TITLE				CAT	EGORY
]	2-1026							
	P37F		.Ve	rtical Bac	k Mou	inted 10 HP Drive	G,	. Н
	200F		.Hc	rizontal R	H & I	.H Side 10 HP Dri	ve G,	Н
	10 HP Fr. 280T		M	lotor	F			
	J80001		B	rake			F	
	HU-477		R	Reducer				
	124F		D	rive Base	F			
	125F		J	ack Shaft	F			
	126F			oupling	F			
	127F		P	illow Bloc	F			
	128F		R	educer Dri	F			
	188F		c	Chain Guard				
	132F		T	orque Limi	ter G	uard	F	
	133F		B	rake Adapto	er Pl	ate	F	
	134F		H	ead Shaft	Space	r	F	
i	135F		Н	ead Shaft 1	End C	ap	F	
	136F		J	ack Shaft	Space	r	F	
	137F		J	ack Shaft 1	End C	ap	F	
	334F		M	otor Shaft	Adap	tor	F	
	335F	ļ	R	educer Shar	Et Ad	aptor	F	
	129F		Н	ead Shaft I	Orive	Sprocket	F	
	323F	j	• • •	Adjusting 1	Lug		F	
	324F		• • •	Adjusting Lug				
	325F		Adjusting Bracket				F	
			SIZE CODE IDENT. NO. DWG. NO.					REV.
			A	07586	5	2-10260	LB	B
						зн	EET //	

CODE IDENT. NO.	DWG. NO.	REV.		DWG. TIT	rle		CATE	GORY
	2-1026							
	326F		•••	Hub			F	
	327F	A	• • •	Sprocket Base			F	
	328F			Washer			F	
	329F		• • •	Sprocket	F			
	321F		Т	orque Limiter A	F			
	130F		c	hain Take-Up	F			
	330F		Take-Up Bracket					
	331F		Take-Up Slide					
	332F		Idler Sprocket					
	333F		Pillow Block Burn-Out					
	189F		D	rive Base			F	
	193F		Adjusting Plate				F	
1	191F		J	Jack Shaft				
	259F		ј	ack Shaft Drive	: Sprocket		F	
	260F		J	ack Shaft Drive	en Sprocket		F	
	197F		P	illow Block			F	
	348F		P	illow Block Bur	n-Out		F	
	350F			ack Shaft End (lap		F	
	351F		J	ack Shaft Space	er		F	
	352F		٠. ټ	ack Shaft Space	er		F	
	349F		R	educer			F	
	354F		Н	ead Shaft Drive	: Sprocket		F	
	357F		• • •	Hub			F	
	356F		Sprocket Base				F	
	355F		Sprocket					
			SIZE	O7586	DWG.1 2-1026			REV.
					<u> </u>	SHEET /	2	

CODE IDENT. NO.	DWG. NO.	REV.			DWG. TIT	LE		CATE	GORY
	2-1026								
	353F		A	djustin	g Screw			F	
	198F		c	hain Gu	ard, Upp	er		F	
	358F		c	hain Gu	ard, Low	er		F	
	359F		P	illow B	lock Spa	cer		F	
	360F		c	hain Tal	ke-Up			F	
	361F		• • •	Take-Up	Bracket	:		F	
	362F			Take-Up	Slide			F	
	363F		•••	Idler Ta	ake-Up S	procket		F	
	340F		L	imit Sw	itch Ass	embly		F	
	369F		•••	Mounting	g Bracke	t		F	
	364F		• • •	Bracket				F	
	365F		• • •	Switch A	Actuator			F	
1	366F		• • •	Mounting	g Plate			F	
	367F		• • •	Stud Bo	lt			F	
	368F		•••	Spacer				F	
	<u> </u>								
· ·	<u> </u>	1	SIZE	CODE ID	ENT. NO.	DWG.	NO.		REV.
			A	07	586	2-10261	DLB		
					<u> </u>		SHEET /	3	

	CODE DENT. NO.	DWG. NO.	REV.			DWG. TIT	LE		CATE	GORY
		2-1026								
		141F		c	leanout	Cover			F,G	;
		143F		P	ackage G	luard			F	
		190F		s	erial Pl	.ate			D	
		270F		L	ube Char	t			н	
		284F		c	ontrol S	tation			B,G	}
		273F		М	ounting	Plate			F	
		274F		•••	Lock-Out	Cover			F	
		286F		• • •	Hinged C	over			F	
		277F		М	ounting	Clip			F	
		278F		• • •	Lock Pla	te			F	
		28 7 F			Instruct Station	ion Cha	rt Intermedia	te	D	
		299F		W	arning P	late			D	
		27 2 F		•••	Hinged P	late			F	
		275F		•••	Instruct	ion Cha	rt Master Sta	tion	D	
		27 6 F		•••	Spacer				F	
		279F)	Instruct Station	ion Cha	rt Machine Co	ntrol	D	
		805 - 1400066		.Do	or Water	ti ght			F,H	
1 -				SIZE	CODE IDI		DWG. N			REV.
				A	075	86	12-10261	DLB		
								SHEET	14	

					REVISIONS		
		REV.		DE	SCRIPTION	DATE	APPROVED
•		в/с	GEN. REVI	SION		5/20/77	
			·				
A.	SUPPLEMENTING SH	HIP EQUIPME	IT DRAWING	}:			
					MFGR'S DRAWING NUM	BEP.	
3∙		STORES HA					
C•	NAVY CONTRACT						
D•							
E.							
F.							
G•	SHIP IDENTIFICAT	TION:	<u> </u>				
н.	NO. ITEMS PER SH	HIP	NO. S	SHIPS	INVOLVED		
I.	REFERENCE DRAWIN	NGS: DRAWI	NG LIST SI	HEETS	_ THRO GH 12		
J.	TECHNICAL MANUAL	L NO.					
К•	COMPONENT IDENT	FICATION N	0.				
L.	NOTES:						
		···			KORNY		
	PRE	PARED			DRAWING LI		
•		CKED			VERTICAL 100 LB. F	ACKAGE CONVEYO	OR
	 	NEER			TRUNK STYL		
				SIZE	CODE IDENT. NO.	DRAWING	NO. REV.
	-			<u> </u>	07586	2-1025DLC	В

SCALE

SHEET 1 OF 13

	CODE IDENT. NO.	DWG. NO.	REV.	DWG. TITLE	CATEGORY
,		2-1026			
		P21FC		General Arrangement Drawing Top Recessed Loading Style C	A,B,C,G
		347F (1 347F (2	of 2) of 2)	Electrical Controls Electrical Controls	G G
		P3-AF		Cross Section	A
		158F (1 158F (2	of 2) of 2)	.Trunk Assembly .Trunk Assembly	A,B A,B
		159F		Head Frame	F
		160F		Spreader	F
		98F	A	Intermediate Frame	F
		99F	۲.	Tail Frame	F
		100F	Α	Lower Frame	F
, 1		101F	A	Side Shield LH	F
		102F	A	Side Shield RH	F
		114F	A	Shield Support	F
		106F	Α	Single Cross Bar	F
		107F	A	Side Shield LH	F
		108F	A	Side Shield RH	F
		301F		Track Angle	F
		306F		Track Lower Frame	F
		307F	j	Track Lower Frame	F
		308F		Track Lower Frame	F
		309F		Track Lower Frame	F
		310F		Track Lower Frame	F
ļ		85F	ļ	Double Cross Bar	F
		·····		SIZE CODE IDENT. NO. DWG. NO. A 07586 2-1026 DL C	REV.
				SHEET	
	n No. 177-8			- John John John John John John John John	

CODE IDENT. NO.	DWG. NO.	REV.			DWG. TIT	LE			CATE	GORY
	2-1026						-			
	311F			Track	Lower F	'rame			F	
	312F			Track	Lower F	'rame			F	
	314F			Track	Lower F	'rame			F	
	336F			Track	Tie Pla	ite			F	
	337F			Track	Tie Pla	ite			F	
	3 3 8F			Joint	Block				F	
	339F			Suppor	t Block	:			F	
	304F			LH Cha	nnel Su	pport			F	
	305F			RH Cha	nnel Su	pport			F	
	302F			Joint	Block				F	
	303F			Suppor	t Block	:			F	
	7 4 F	A		Rod Ho	older				F	
	147F			Lubricat	ion Acc	ess Head	End		Н	
										!
		L	SIZE	CODE ID	ENT, NO.		DWG. I			REV.
			A	075	86	2-108	26	DLC		B
						<u> </u>		SHEET 3	l	L
								JITEET 3	, 	

CODE IDENT. NO.	DWG. NO.	REV.			DWG. TI	TLE			CATE	GORY
	2-1026			***************************************				·		
	104F (1 104F (2 104F (3			Shield Shield Shield	Assembl	y Y			Α,	B,G B,G B,G
	83F			Front	Shield	Ext.		!	F'	
	113F			Int. F	ront Sh	ield			F	
	140F			.Int. F	ront Sh	ield			F	
	105F			.Lower	Front S	hield			F	
	81F		<u> </u>	.Head R	ear Shi	eld			F	
	7 7 F			.Int. R	ear Shi	eld			F	
	89F			.Filler	Rear S	nield			F	
	109F			.Lower	Rear Sh	ield			F	
}	112F			.Lower	Rear Sh	ield			F	
	111F	· .	•	.Side S	hield Ta	ail Ext.			F	
1	146F			.Lower	Front Sl	nield			F	
	82F		•	.Head S	ide Shi	eld			F	
	115F		•	.Filler	Front S	Shield			F	
	316F			.Angle	Clip				F	
	317F		•	.Clip					F	
			SIZE	CODE ID	ENT. NO.	<u> </u>	DWG. I	NO.		REV.
			A	075	86	2-10	261	DL C		C
						<u> </u>		SHEET 4	<u>-</u>	
orm No. 127.8					X					

CODE		<u> </u>					1		
IDENT. NO.	DWG. NO.	REV.		DWG.	TITLE			CATE	GORY
	2-1026								
	117F			.Door Frame	Upper			F	
	118F			.Door Frame	Inter	. Square Co	rner	F	
	119F			.Door Frame	Inter	. Round Cor	ner	F	
	148F			.Door Frame	Lower			F	
	120F			Side Plate				F	
	121F			Corner Pla	te			F	
	122F			Side Plate				F	
	138F			Bottom Pla	te			F	
	139F	:		Top Plate				F	
	142F			Top Plate				F	
	144F			Bottom Pla	te			F	
	P25F			Head Unit As	sembl	У		Α,	В
	P23FA	. :		.Head Cam Pl	ate	LH		F	
	P23FB			.Head Cam Pl	ate	RH		F	
	P24F	į		.Head Shaft				F	
	87F			.Bearing Hou	sing	(Head Shaft)	F	
	88F			.Carrier Spr	ocket	(Head)		F	
	116F			.Lubrication	Moun	ting Assemb	ly	Н	
]							
• • • • • • • • • • • • • • • • • • •		<u> </u>	SIZE	CODE IDENT.	NO.	DWG. I	10.		REV.
			A	07586	2	-1026	DLC		В
							SHEET S	i 5	
			<u></u>						

CODE IDENT. NO.	DWG. NO.	REV.			DWG. TIT	TLE		CATI	GORY
	2-1026								
	P22F			Tail Un	it Asser	mbly		A,	В
	P8A			.Tail Ca	am Plate	e RH		F	
	P8B			.Tail Ca	am Plate	e LH		F	
	72F		•	.Spring	Retaine	er		F	
	73F		•	.Spring	Spacer			F	
	75F		•	.Bushing	J			F	
	78F		•	.Adj. Ro	od			F	
	90F		•	.Track H	Right Re	ear		F	
	91F		•	.Track H	Right Re	ear		F	
	92F		•	.Track I	Lift Fro	ont		F	
	93F		•	.Track I	Lift Rea	ar		F	
	94F		•	.Bearing	g Retair	ner		F	
	95F		•	.Tail Sp	procket			F	
	96F		•	.End Car			:	F	
	103F		•	.Bushing	3			F	
	318F		•	.Spring				F	
							ı		
_									
			SIZE		ENT. NO.				REV.
			A	075	86	2-1026	DLC		C
							SHEET	6	

是我们的时候,这个人是是一个人,我们就是我们的人,我们就是我们的人,我们就是我们的人,我们就是我们的人,我们就是我们的人,我们就是我们的人,我们就是我们的人,我 第二章

CODE IDENT. NO.	DWG. NO.	REV.		DWG. TIT	TLE	CAT	EGORY
	2-1026						
	P20F	A	,	.Carrier Assembl	Ly	Α,	G,H
	P26	C.		.Carrier		F	
	P27	A		Guide Arm		F	
	P28	c		.Carrier Shaft		F	
	41F	В		.Chain Drawing		F	
	162F	Α		Chain Pin		F	
	49F	Α		.Carrier Link 1	Inner Assembly	F	
	45F	A	•	Carrier Link	Inner	F	
	43F	A		Bushing		F	
	46F	A	•	.Cam Follower		F	
	164F	A	•	.Cam Follower F	langed	F	
	47F	A		.Cap	F		
	163F	Ą	•	.Spacer		F	
	48F	Α		.Carrier Link -	Outer Assembly	F	
	44F	Α	•	Carrier Link	- Outer	F	
		'					
			SIZE	CODE IDENT. NO.	DWG. NO.		REV.
			A	07586	2-1026 DLC		В

SHEET 7

CODE IDENT. NO.	DWG. NO.	REV.		DWG. TIT	LE		CATE	GORY
	2-1026				-			
	P10F (1	₽ pf 2)	.:	Loader Unloader			Α,	В
	P10F (2	of 2)	•:	Loader Unloader	Assembly		Α,	В
	P150F	A	• :	Loader Unloader	Assembly		Α,	В
	51F	A		.Platform			F	
	149F	 		.Platform			F	
	52F	A		.Bracket Assemb	oly RH		F	
	182F			Flanged Bushi	ng		F	
	53F	A		.Bracket Assemb	ly LH		F	
	182F			Flanged Bushi	ng		F	
	54F	Α		.Cross Shaft			F	
	55F	A		.Clevis Arm			F	
	56F	A		.Clevis			F	
	57F	A		.Clevis Pin			F	
	58F	A		.Spring Rod			F	
	59F	A	•	.Connecting Arm	1		F	
	60F	A		.Pivot Block			F	
	61F	A		.Shifter Arm			F	
	6?F	A		.Guide Shaft			F	
	63F	A		.Guide Plate			F	
	64F	A] .	.Pivot Stud			F	
	65F			.Split Coupling	1		F	
	76F			.Spring			F	
	145F			.Sleeve Bearing	J		F	
	161F			.Thrust Bearing	ı		F	
	165F	Ì	Į.	.Thrust Bearing	ı		F	
	300F	<u> </u>	SIZE	.Ball Handle CODE IDENT. NO.	DWG. N	1	F	REV
			_ '		1			
			A	07586	2-10260	, L C		В
					***************************************	SHEET 8		

CCDE IDENT. NO.	DWG. NO.	REV.			DWG. TIT	rLE		CATEGORY	
	2-1026								
	66F	A	.	Top From	nt Loade	er Unloader		A,B	
	69F	A	.	.Bracket	RH &	LH		F	
	70F	Α		.Mountir	ng Clip			F	
į	67F	A		.Roller	Assemb:	ly		F	
	68F	A	.	.Load Ba	ar			F	
		<u>.</u> :							
	156F	}		Top Over	travel	Limit Assemb	ly	A,B	
	167F			.Platfor	m			F	
	168F			.Spring	Bracket	Assembly		F	
!	289F			Mounti	ng Brad	cket		F	
	290F			Spring		F			
	291F		.	Yoke		F			
· H	292F			Pivot		F			
	293F		•	Channe		F			
	295F			.Mountin	ıg Brack	et		F	
	170F			.Control	. Arm			F	
	171F		•	.Limit S	witch E	Bracket	!	F	
	296F		•	Base P	late			F	
	297F			Mounti	ng Plat	:e		F	
	298F		•	Contro	1 Arm G	Guide Plate		F	
	320F		•	.Spring				F	
			SIZE	CODE IDI		DWG.		REV.	•
			Α	075	80	2-1026	DLC	C	
							SHEET S)	

....

C TANSTALL S.

CODE IDENT. I		G. NO.	REV.		DWG. T	TLE		CATE	GORY
1	2-	1026							
	50	F	A		Jam Limit Asse	embly		Α,	В
	17	4F			.Mounting Bloc	ek Top		F	
	17	5F			.Mounting Bloc	ek		F	
	17	6 F			.Cable Guide A	ssembly		F	
	17	7 F			.Counterweight	:		F	
	178	8F			.Cable Assembl	У		F	
	22	8F		•	Cable Bracke	t		F	
	179	9F			.Counterweight	Bracket Asse	mbly		
	P3	7 F		•	Vertical Back	Mounted 10 HP	Drive	G,	H
	200	OF			Horizontal RH	& LH Side 10	HP Drive	G,	н
1 1		HP 286T		•	.Motor			F	
	J80	0001		•	.Brake			F	
	HU-	-47797	C-FM	•	.Reducer			F	
	124	4F		•	.Drive Base			F	
	125	5F		•	.Jack Shaft			F	
	126	6F		•	.Coupling			F	
	127	7 F		•	.Pillow Block			F	
	128	3F		•	.Reducer Drive	Sprocket		F	
	188	3F		•	.Chain Guard			F	
	132	2F		•	.Torque Limite	r Guard	Í	F	
1	133	3F		•	.Brake Adapter	Plate		F	
	134	1F		•	.Head Shaft Sp	acer		F	
				SIZE	CODE IDENT. NO.	DWG.	NO.		REV.
				A	07586	2-1026	DLC		c
						<u> </u>	SHEET /	0	
Enrie Ha. 127-8	ti itti og ving mortendenski	The section of the se	و درو و مرود				<u> </u>		<u></u>

CODE	DWG. NO.	REV.			DWG. TIT	TI E			CATE	GORY
IDENT. NO.		1,50.	 		DITG. 11				UMIE	
	2-1026									
	135F			.Head Si	naft End	l Cap			F	
	136F			.Jack Sl	naft Spa	cer			F	
į	137F			.Jack Sl	naft End	l Cap			F	
	334F			.Motor	Shaft Ad	laptor			F	
	335F			.Reduce	Shaft	Adaptor			F	
	129F			.Head Sh	aft Dri	ve Sprod	ket		F	
	323F			Adjust	ing Lug	ſ			F	
	324F	ı		Adjust	ing Lug	ī			F	
	325F			Aljust	ing Bra	cket			F	
	326F		•	Hub					F	
	327F	A	•	Sprocl	et Base	.			F	
	328F		•	Washer	•				F	
	329F		•	SprocketTorque Limiter Assembly					F	
	321F		•						F	
	130F		•	.Chain 1	ake-Up				F	
	330 F		•	Take-	Ip Brack	et			F	
	331F		•	Take-t	Jp Slide	1			F	
	332F		•	Idler	Sprocke	t			F	
	333F	1	•	.Pillow	Block E	urn-Out			F	
	189F		•	.Drive E	ase				F	
	193F		•	.Adjusti	ng Plat	e			F	
	191F		•	.Jack Sh	aft				F	
	259F			.Jack Sh	aft Dri	ve Sproc	ket		F	
	260F		Jack Shaft Drive SprocketJack Shaft Driven Sprocket						F	
				··· -		• -				
			SIZE	CODE ID	ENT. NO.		DWG. N	o.		REV.
			A	075		2-10	26 D	LC		C
						<u> </u>		SHEET //		
m No. 177-8							<u></u>	SHEE! //		

CODE IDENT. NO.	DWG. NO.	REV.			DWG. TI	LLE	معالية والمارية والمارية		CATE	GORY
	2-1026									
	197F			.Pillow	Block				F	
	348F			.Pillow	Block I	Burn-Out			F	
	350F			.Jack Sh	aft End	d Cap			F	
	351F			.Jack Sh	aft Spa	acer			F	
	352F	1		.Jack Sh	aft Spa	acer			F	
	349F			.Reducer					F	
	354F			.Head Sh	aft Dri	ive Sprod	ket		F	
	357F		•	Hub					F	
	356F			Sprock	et Base	e			F	
	355F		•	Sprock	et				F	
	353F		•	.Adjusti	ng Scre	₽W		·	F	
	198F		•	.Chain G	uard, U	Jpper			F	
)	358F		•	.Chain G	uard, I	Lower			F	
	359F		•	.Pillow	Block S	Spacer			F	
	360F		•	.Chain T	ake-Up				F	
	361F		•	Take-U	p Brack	et			F	
	362F		•	Take-U	p Slide	•			F	
	363F		•	Idler	Take-Up	Sprocke	t		F	
	340F		•	.Limit S	witch A	ssembly			F	
	369F		•	Mounti	ng Brac	ket			F	
	364F		•	Bracke	t				F	
	365F	ļ	•	Switch	Actuat	or			F	
	366F		•	Mounti	ng Plat	:e			F	
	367F		•	Stud B	olt				F	
	368F		•	Spacer					F	
			SIZE	07 5		2-10	DWG. NO			REV.
		}								
Ponn No. 177-8								SHEET /	2	

CODE IDENT. NO.	DWG. NO.	REV.		DWG. T	ITLE		CATEGORY
	2-1026						
	141F			.Cleanout Cove	er		F,G
	143F			.Package Guard	a		F
	190F			.Serial Plate			D
	270F			.Lube Chart			Н
	284F			Control Stati	ion		B,G
	273F			Mounting Pla	ate		F
!	274F			Lock-Out Co	er/		F
	277F			.Mounting Clip	þ		F
	278F			Lock Plate			F
	287F		•	Instruction Station	Chart Intermed	diate	D
	299F			.Warning Plate	•		D
	272F			Hinged Plate	•		F
	275F			Instruction	Chart Master	Station	D
	276F			Spacer			F
	279F			Instruction Station	Chart Machine	Control	D
	2867		•	HINGED COV	ER		
	805-1400	066	ם	Door Watertight	:		F,H
j							
			SIZE	CODE IDENT. NO	. DWG.	NO.	REV.
			A	07586	2-1026	DLC	
						SHEET	3

Form No. 177-8

Section IV

Reliability and Maintainability Program Plan, Final

A. Reliability Program Plan

The following pages describe the Reliability Program Plan for the high-reliability vertical package conveyor developed for this contract. Goals are: 0.95 criteria for successful system mission; 20,000 hours average life under user conditions; minimuzed redundancy. The Failure Modes and Effects Analysis required by the Reliability Program Plan has been completed and submitted to Naval Ship Engineering Center on March 23, 1976 (see Item 8 of Section I of this Final Report).

B. Maintainability Program Plan

The pages immediately following the Reliability Program Plan outlined in Section A above, describe the Maintainability Plan for the high-reliability conveyor. Both the Reliability and Maintainability Program Plans were completed and submitted to Naval Ship Engineering Center as a "task element" of Phase II on February 4, 1975 (see Item 1 of Section I of this Final Report).

FINAL

RELIABILITY AND MAINTAINABILITY

PROGRAM PLANS

CDRL ITEM B001AA

USN CONTRACT NOO024-72-C-5500

JANUARY 28, 1975

R. A. Larson General Manager Systems Logistics

Kornylak Corporation, Hamilton, Ohio

RELIABILITY PROGRAM PLAN

FOR

VERTICAL PACKAGE CONVEYOR

JANUARY 28, 1975

USN CONTRACT N00024-72-C-5500

Kornylak Corporation, Hamilton, Ohio

FOREWORD

The Vertical Package Conveyor Reliability Program Plan describes the reliability work to be accomplished during Phase II - Detailed Design & Development, and Phase III Prototype Build Program, how they will be accomplished, responsibilities, and scheduling. Reference and support information is included in the appendices.

Requirements of MIL-STD-785 and Contract N00024-72-C-5500 are implemented as specified herein to provide for the most economical implementation of work tasks. This program assures that the reliability requirements are determined and satisfied throughout all phases of contract performance. It is planned to substitute MIL-I-45208 Inspection System Requirements in place of MIL-Q-9858 Quality Control Requirement.

TABLE OF CONTENTS

Paragraph		Page
	Foreword	ii
	Section 1 - Introduction	
1.1 1.2 1.3 1.3.1 1.3.2	Purpose Scope Objectives Reliability Program Goals Life	1-1 1-1 1-1 1-1 1-2
1.3.3 1.3.4	Design Philosophy Redundancy Requirements	1-2 1-2
	Section 2 - Management and Control	
2.1 2.2 2.3 2.4 2.5 2.5.1 2.5.2 2.6 2.6.1 2.6.2 2.6.3 2-6-4 2.6.5 2.6.6	General Organization Program Plan Program Revision Program Control Program Schedule Program Evaluation and Review Documentation Program Plan Progress Reports Milestone/Cost Reports Final Report Design Review Minutes FMEA Report Demonstration Test Plan Section 3 - Task Plan	2-1 2-1 2-1 2-3 2-3 2-3 2-3 2-3 2-3 2-5 2-5 2-5
3.1 3.2 3.2.1 3.2.2 3.3 3.3.2 3.4 3.4.1 3.4.2 3.5 3.5.1	General Reliability Analysis Allocation Prediction Parts Application Vendor Control Failure Mode, Effect Analysis Analysis Requirements Application Design Review Formal Continuing Review	3-1 3-1 3-1 3-2 3-2 3-2 3-2 3-3 3-3

TABLE OF CONTENTS (CONT'D)

Paragrapl	n.	Page
3.5.3	Engineering Design Changes	3-3
3.6	Reliability Demonstration	3-3
3.7	Component Controls	3-4
3.7.1	Reliability Assurance	3-4
3.8	Data Collection, Analysis and Corrective Action	3-4
3.8.1	Failure Documentation	3-4
3.8.2	Failure Analysis and Corrective Action	3-4
	APPENDICES	
• •	I Reliability Check List	1-1
Annondiv	II Definitions and Abbreviations	TT 1

Section 1 INTRODUCTION

1.1 PURPOSE

The Reliability Program Plan for the Vertical Package Conveyor (VPC) has been prepared and submitted in accordance with the Contract Data Requirements List, Sequence Number B001AA. This document is the master plan for implementing the Kornylak Corporation (KC) reliability program.

1.2 SCOPE

The Reliability Program Plan details the approach, procedures, schedules and management control that KC will use to achieve VPC reliability within requirements of the contract. This plan defines an organized approach to reliability which encompasses the total range of reliability effort from the initial conceptual phase and throughout the design, fabrication, assembly, and test of the VPC. The reliability program is based on the required elements of Contract N00024-72-C-5500 and Military Standard, Reliability Program for Systems and Equipment Development and Production, MIL-STD-785-A.

1.3 OBJECTIVES

A reliability program will be implemented at KC to assure that reliability requirements affecting VPC performance and operating success are identified and satisfied throughout all phases of the VPC contract. Maximum program effectiveness will be provided by interfacing with design personnel during the initial phases of the work and continuing throughout the fabrication and testing phases. Specific actions will be taken and controls instituted to meet reliability program goals as described in this plan.

1.3.1 RELIABILITY PROGRAM GOALS

The system mission or criteria for success is 0.95. Operational success is defined as the probability of successful operation of the VPC during typical ship use conditions. As a design objective KC shall attempt to minimize the occurrence of hardward failures and to prevent failures from occurring by prescribing preventative maintenance routines. In addition, KC shall strive to eliminate or minimize all single failure points.

1.3.2 LIFE

The VPC shall be designed to have an average life of 20,000 hours under user conditions.

1.3.3 DESIGN PHILOSOPHY

The design shall utilize, as far as practical, fully developed and proven parts and components. All equipment shall be designed for worst-case environmental and component tolerance parameters. Operational system success shall be the prime consideration and particular emphasis shall be placed on high availability rate and ease for performing maintenance functions. The mean time between failures (MTBF) will be considered during Phase II Engineering Studies, and Phase III Testing.

1.3.4 REDUNDANCY REQUIREMENTS

Redundancy shall be employed to the lowest practical level consistent with meeting reliability goals. The type redundancy to be utilized shall be selected after a full-failure mode analysis has been performed to determine the possible and most probable failure modes. The application of redundancy techniques shall not be used as justification for poor design practices or the use of equipment of marginal reliability.

Section 2

RELIABILITY PROGRAM MANAGEMENT AND CONTROL

2.1 GENERAL

This section describes the organization, responsibilities, program planning and control, and documentation that will be used to manage and control the reliability program.

In establishing and providing for a realistic and workable program management and control plan, the following was considered.

- Task Responsibility Each reliability task is identified with an organization responsible for its completion.
- Scheduling Each task is scheduled.
- Reporting Program progress and status of accomplishment is reported on a continuing basis.
- Monitoring The program is monitored and a record kept of all changes so that continuity to the plan is maintained.

2.2 ORGANIZATION

Functional responsibility for the reliability program lies within the Engineering Branch. Work tasks will be performed by personnel skilled in the reliability disciplines and familiar with the activities.

Figure 2-1 shows the responsibilities and tasks assignments by organization. The tasks were abstracted from the work statement requirements.

2.3 PROGRAM PLAN

The Program Plan was prepared in compliance with the VPC Program. This plan constitutes the scope of work of the reliability program.




Figure 2-1 Organizational Task Responsibility Chart

2.4 PROGRAM REVISION

Any change in the scope of work will be documented in subsequent revisions and in accordance with General Provisions: Changes, of the contract.

2.5 PROGRAM CONTROL

Program management and control is provided on a continuing basis by supervision and management personnel. This activity is exemplified by adherence to scheduled milestones and status reporting.

2.5.1 PROGRAM SCHEDULE

The functional areas of the reliability program and the schedule of important milestones are identified in Figure 2-2. Milestone dates are in agreement with the overall program plans. Management controls will be maintained in order to meet task milestones in a timely and effective manner.

2.5.2 PROGRAM EVALUATION AND REVIEW

The reliability program of KC is subject to evaluation, review, and inspection by customer designated representatives. Customer - contractor program milestone review points are identified on the schedule of Figure 2-2 for Phase I, II and III.

2.6 DOCUMENTATION

The reliability program is documented by the following reports. Figure 2-3 lists the documents and the contractor Data Requirement List Sequence Number.

2.6.1 PROGRAM PLAN

This Preliminary Program Plan is submitted as required by contract. The final Program Plan for Phase II and III will be submitted 45 days after Phase II work commences.

2.6.2 PROGRESS REPORTS

A reliability progress report is submitted as a part of the Progress Report and includes all accomplishments for the preceding quarter.

2.6.3 MILESTONE/COST REPORTS

Inputs will be furnished to the monthly milestone/cost reports.

1 2 3 4 5 6 7 8 9 10 11 12 13 14 15	PHASE I PHASE II PHASE III	○ ×	· • • • • • • • • • • • • • • • • • • •				Δ		
MONTHS AFTER PLAN APPROVAL	TASK	1 MANAGEMENT AND CONTROL Reliability Plan - Prelim & Final-Customer - Contractor Eeview Milestone/Cost Reports Progress Reports Final Reports		3 PARTS APPLICATION Vendor Control	Prelim & Final	5 DESIGN REVIEW - FORMAL Informal Design Thange Review	6 RELLABILLEY DEMONSTRATION TEST PLAN - Prelim & Final	COMPONENT CONTROL	B DATA COLLECTION, ANALYSIS AND CORRECTIVE ACTION

Contractual Documentation

Reliability Detail Task Schedule Ø 1 Figure 2

Do×

Scheduled Milestone Support to Documentation Delivery

TITLE	CONTRACTOR DATA REQUIREMENTS LIST	REMARKS
Program Plan	AOOLAA BOOLAA	Preliminary Final
Progress Reports	AOOlAE BOOLAF COOLAM	Input to support documentation delivery
Milestone/Cost Report	E002 (in all phases)	Input to support documentation delivery monthly
Final Report	AOOLAF BOOLAG COOLAU	Input to support documentation delivery
Design Review Minutes	AOOIAD BOOIAE COOIAC	15 days after each formal review
FMEA, Report	BOOLAH	Preliminary Final
Demonstration Test Plan	COOLAK COOLAK	Preliminary Final

2.6.4 FINAL REPORT

Inputs to the Final Report will be provided at the completion of Phase I, II and III.

2.6.5 DESIGN REVIEW MINUTES

Minutes of each design review will be prepared and submitted 15 days after each formal design review is completed.

2.6.6 FMEA REPORT

A preliminary and final FMEA Report will be furnished. This report identifies possible modes of failure, effect of the failure on system capability, and the criticality of the failure to system success.

2.6.7 DEMONSTRATION TEST PLAN

A Reliability Demonstration Test Plan will be submitted prior to the scheduled start of testing.

Section 3

TASK PLAN

3.1 GENERAL

Section 3 describes the tasks, their objectives, schedules, and methods of implementation. Figure 2-1 shows the overall reliability program by tasks, grouped in their corresponding categories.

3.2 RELIABILITY ANALYSIS

To satisfy the Reliability Program Goals, Kornylak Corporation will perform reliability analysis on critical components and parts based on the methods described in MIL-STD-785 Military Standard Reliability Program for systems and Equipment Development and Production. The purpose of these analysis is to systematically evaluate key elements of the system to insure that potentially unreliable hardward and critical failure modes are detected and corrected prior to the final design. The analysis will include a review of all critical part and component applications, system redundancy requirements, environmental profiles, and performance tolerances to identify reliability stress levels and opportunities for reliability trade-offs.

The major effort of this will include inputs to the parts application and design review tasks. Work effort continuity will be maintained throughout the program to assess the impact on system reliability which could influence VPC performance. This will be done by updating the reliability analysis as data becomes available from developmental testing and failure analysis results.

3.2.1 ALLOCATION

Reliability objectives will be allocated to the part level based on the methods described in MIL-STD-756A Military Standard Reliability Prediction. Allocated goals on critical hardward will be identified for implementation in specifications, procurement recommendations and design reviews.

3.2.2 PREDICTION

An analysis of all critical parts during Phase II will be performed to determine their probable failure modes and failure rates. This analysis is accomplished in part by preparation of component application sheets which define the component reliability design requirements. All applicable information including specifications, system applications, design characteristics, vendor data and test reports are analyzed and used. This information is prepared for selected components and the results documented.

A continuing review of all test and failure reports is to be maintained and the component reliability analysis is updated as new information becomes available. The results derived from this task will be utilized in making VPC reliability estimates.

A reliability prototype of the VPC will be prepared to show the functional relationships that are necessary for successful VPC operation. A prediction of the reliability for VPC will be made for the hardware configuration of Phase III.

3.3 PARTS APPLICATION

The design of the VPC will utilize proven parts and components as far as practical. Action will be taken during the design reviews to maximize the use of parts and components which have design factors to meet the performance, reliability and quality requirements as specified in the Contract and/or its specification.

Reliability personnel will work closely with the design engineer in order to implement reliability requirements. Feedback of information from previous experience with similar or related designs will be inputed into system development. The design will include application of preferred parts to the greatest extent possible. It shall be an objective during the design review to eliminate from the design parts known to be inadequate.

3.2.2 VENDOR CONTROL

Vendors if required will be chosen that have a proven record of reliability accomplishment. This will be determined based on the ability of the vendor to meet qualification, reliability and maintainability standards for military operations. Vendor surveys will be performed whenever products do not meet specification requirements or whenever functional failures are experienced. Vendor purchase orders for components will contain quantitative requirements for Repair and Maintenance as necessary to satisfy overall contract requirements.

3.4 FAILURE MODE, EFFECT ANALYSIS

A Failure Mode, Effect Analysis (FMEA) shall be performed as an integral part of the design process. This will provide a study of the system to determine possible modes of failure and their effects on system success. A list of critical items will also be furnished.

3.4.1 ANALYSIS REQUIREMENTS

A failure mode effect analysis will be performed to determine modes of system failure and the effect of each failure on operational capability. The FMEA report will be made starting at the system or function level and expanding downward to the part level in order to identify critical functions. Each potential failure will be considered in the light of probability of occurrence and be categorized as to the probable effect on system operating success and personnel safety. The final FMEA will be completed and delivered at the time the design for Phase III is finalized.

3.4.2 APPLICATION

The Reliability Engineer will utilize FMEA data as an input for reliability prediction and safety analysis. An important objective is to discover critical failure areas and to identify means of removing the failure susceptibility from the system. Reliability studies, as described in Section 3.2, will utilize FMEA data to aid the VPC design. Use of the FMEA will also be made to provide an input to the maintainability task and as a major consideration in design reviews.

3.5 DESIGN REVIEW

Engineering design reviews evaluate the design and ability of parts, components, and systems to perform their intended function. Both formal and informal design reviews will be conducted.

3.5.1 FORMAL REVIEW

Formal design reviews will be conducted at which time the designs and drawings will be reviewed and analyzed in detail to determine equipment deficiencies. Improvements to the design and operation will be identified that will increase system reliability, maintainability and safety.

A preliminary design review will be held prior to initial design release. Formal design reviews will be held for the Phase II, III and Phase IV configuration.

The following check lists are used in design review meetings to insure that all potential causes of failures or problems are considered:

a) Functional-Mechanical, b) Functional-Electrical, c) Environment,
d) Component Requirements, e) System Requirements, f) Reliability, g) Testing, and h) Human Factors/Maintainability Design Review. The Reliability Check List is shown in Appendix I.

3.5.2 INFORMAL CONTINUING REVIEW

Informal continuing reviews in the form of reliability analysis is maintained as a part of the reliability program, as previously described in Section 3.2. This work arrangement assures that the best features for inherently reliable designs are provided to the designers at the earliest possible date. This will help to insure that many reliability principles are incorporated into the design prior to the formal review.

3.5.3 ENGINEERING DESIGN CHANGES

Engineering design changes, after initial release, will be reviewed to determine their effect on system success, availability and safety. As part of the overall change activity, any design change which adds, deletes, or changes the operation of a functional component shall be documented as part of the engineering design change system and consideration given to its effect.

3.6 RELIABILITY DEMONSTRATION

A reliability demonstration test plan will be prepared during Phase III for use in Phase III. This plan will contain information regarding reliability test procedures. Definition of equipment failure, rules for continuation of testing, and failure analysis and corrective action guidelines will be furnished. Reliability demonstration of the VPC will be performed by Kornylak Corporation personnel.

3.7 COMPONENT CONTROLS

Controls will be applied on the VPC in order to provide added confidence that components will perform intended functions. Components whose successful performance is required for operating success, ease of maintenance, and safety will have been identified in the reliability analysis, FMEA, parts application and design review tasks. Continuity will be maintained during hardward manufacture and assembly to assure that reliability and quality is not degraded.

3.7.1 RELIABILITY ASSURANCE

Reliability engineering personnel who participated in the initial phases of the program will also have responsibility to assure that reliability is enhanced. This continuity will provide the basis for evaluation of progress and assurance of reliability. Records will be maintained and reviewed periodically for impact.

All life limited components affected by age or operational characteristics will be identified. Components with special characteristics, safety or reliability requirements will be determined and these requirements will be included in the applicable specification. Components with repetitive quality, test or failure history will be monitored and corrective measures will be implemented to reduce the incidence of recurring problems.

3.8 DATA COLLECTION, ANALYSIS AND CORRECTIVE ACTION

Failure analysis will be performed and corrective action taken on all functional failures. Data will be acquired to insure effective monitoring, information feedback and timely resolution of all problems encountered during the activities under this contract. Failures on critical components shall be assessed for potential impact on the system hardware and operational objectives.

3.8.1 FAILURE DOCUMENTATION

Failures and discrepancies are reported on Incoming Material, Inspection Sheets, Defective Material Notices and Interim Report-Test Problem/Malfunction. These documents identify and describe problems that occur during incoming inspection, in-plant processing, assembly operations and testing.

3.8.2 FAILURE ANALYSIS AND CORRECTIVE ACTION

All functional failures identified during production, and testing, are closed out by issuing Functional Failure Close-Out Sheets, and Reliability Engineering Test Close Outs. Status of all open functional failures is maintained so that analysis and corrective action and recommendations are made on a timely basis. Corrective action includes design improvements and verification.

APPENDIX I

RELIABILITY CHECK LIST

The following check list is used to ensure that as many potential failure causes as possible are considered.

- 1) Have corrosion-resistant materials or finishes been provided?
- 2) Are there dissimilar metals in contact?
- 3) Are all materials satisfactory for the temperature involved?
- 4) Is the possibility of flaking considered?
- 5) Has moisture protection been provided where necessary?
- 6) Are all materials fungus resistant or inert?
- 7) Are electrically conductive finishes provided where necessary?
- 8) Have cantilever mountings been eliminated where possible?
- 9) Is the trunk and frames sufficiently designed for the application?
- 10) What are the location and load ratings of mounting points?
- 11) Where are the heaviest parts located?
- 12) Have the center of gravity and acceleration been considered in the design.
- 13) In the case of terminal boards, are the critical components mounted at the edges rather than in the center and are they properly supported?
- 14) Has clearance been provided with due consideration for vibration, shock and noise stresses?
- 15) Can electrical instability be caused by vibration of mechanical parts?
- 16) Are stranded wires properly received close to solder points to prevent flexing?
- 17) Are proper screw lengths and locking provisions specified?
- 18) Is the design such that the components may be installed without heat or mechanical damage?
- 19) Is there adequate accessibility for repair?

- 20) Does the design eliminate the possibility of inserting the wrong plug or module into a receptacle?
- 21) Have provisions been made for properly leading cables and wiring around corners and sharp edges?
- 22) Are grommets provided where needed?
- 23) Is lacing properly specified and harness well routed and properly clamped?
- 24) Have cables and connectors been properly identified?
- 25) Does the system and components have a design life expectancy exceeding all test, checkout, and operational requirements?
- 26) What is the failure history of the item? Is this a critical item; i.e., would its failure cause system failure?
- 27) What is the expected or estimated numerical value of reliability of the item?
- 28) If the item is a newly developed design what are its critical weaknesses? What provision has been made in the design so that modifications can be made at the earliest possible time if these or other weaknesses show up during testing?

APPENDIX II

DEFINITIONS AND ABBREVIATIONS

DEFINITIONS:

COMPONENT A combination of

A combination of parts, subassemblies or assemblies, usually self-contained, which performs a distinctive function in the

operation of the overall equipment. "A black box."

FAILURE The inability of a system, subsystem, component, or part to

perform its intended function under defined conditions.

FAILURE MODE The physical description of the manner in which a failure

occurs, and the operating conditions of the equipment at the

time of failure.

FAILURE RATE At any point in the life of material, the incremental change

in the number of failures per associated incremental changes in the measure of life (cycles, time, miles, event, etc.,

as applicable).

GENERIC

FAILURE

RATES

That rate as defined above which would prevail when the part, component, or system is used at rated conditions under

ambient laboratory environments.

MAINTAINABILITY The quality of the combined features of equipment design and

installation which facilitates the accomplishment of inspection, test, checkout, servicing, repair, and overhaul with a minimum

of time, skill and resources in the planned maintenance

environments.

MODEL A program which uses functional logic expressions together

with babilistic values to determine system reliability.

MILESTONE Any significant event in the design and development of a system

or in the associated reliability program which is used as a control point for measurement of progress and effectiveness or for planning or re-directing future effort. Reliability program

milestones should be identified in the Reliability Program Plan.

PART One or more pieces joined together, and which are not normally

subject to disassembly without destruction. Generally a

constituent of a component.

QUALIFICATION Determination by a series of tests and examination of

documents and processes that a part. component, subsystem, cr

system is capable of meeting performance requirements

prescribed in the specification.

QUALIFICATION DATA

The complete body of data obtained in the qualification testing of a part, component, subsystem or system.

QUALIFICATION TEST

A test or series of tests conducted to determine if a part, component, sybsystem, or system meets qualification requirements.

REDUNDANCY (OF DESIGN) The use of more than one means of accomplishing a given task or function where all must fail before there is an over-all failure of the system.

RELIABILITY

The probability of a successful operation of the device in the manner and under the conditions of intended customer use.

RELIABILITY TEST Tests to establish a significant level of engineering confidence in the reliability of the hardware. These tests will be a continuation of qualification tests to verify the life expectancy with the addition of overstress tests as necessary to determine failure modes and safety margins.

SUPPLIER

A contractor, subcontractor or other source producing or providing articles or services required in connection with the prime contract.

SYSTEM

One of the principal functioning entities comprising the project hardware and related operational services within a project or flight mission. Ordinarily, a system is the first major subdivision of project work. Similarily, a subsystem may also be an organized and disciplined approach to accomplish a task, e.g., a failure reporting system.

FINAL

MAINTAINABILITY PROGRAM PLAN

FOR

VERTICAL PACKAGE CONVEYOR

JANUARY 28, 1975

USN CONTRACT N00024-72-C-5500

Kornylak Corporation, Hamilton, Ohio

FOREWORD

The Vertical Package Conveyor Maintainability Program Plan describes the maintainability work to be accomplished during design development and prototype phases. The plan defines and describes the tasks of the maintainability program, how they will be accomplished, responsibilities; and scheduling.

Requirements of MIL-STD-470, Maintainability Program Requirements and U.S. Navy Contract N00024-72-C-5500 are included in the program plan.

TABLE OF CONTENTS

Paragraph		Page
	Foreword	ii
	Section 1 - Introduction	
1.1	Purpose	1-1
1.2	Scope	1-1
1.3	Objectives	1-1
1.3.1	Maintainability Program Goals	1-1
1.3.2	Maintainability Philosophy	1-1
	Section 2 - Maintainability Program Management and Control	
2.1	General	2-1
2.2	Organization	2-1
2.3	Program Plan	2-1
2.4	Program Revision	2-1
2.5	Program Control	2-3
2.5.1	Program Schedule	2-3
2.6	Documentation	2-3
2.6.1	Program Plan	2-3
2.6.2	Progress Reports	2-3
2.6.3	Final Report	2-3
2.6.4	Demonstration Test Plan	2-3
2.7	Relation to Integrated Logistics Plan	2-3
2.8	Liaison Between Maintainability and Reliability	2-5
2.9	Program Reviews	2-5
2.10	Subcontractor Relations	2-5
	Section 3 - Task Plan	
3.1	General	3-1
3.2	Maintainability Analysis	3-1
3.2.1	Maintainability Allocation	3-1
3.2.2	Maintainability Prediction	3-1
3.3	Maintainability Demonstration	3-2
3.4	Human Factors Engineering	3-2
3.5	Maintainability Assurances	3-2
3.6	Maintenance Concept and Plan	3-2
3.7	Maintainability Reporting	3-2
	Attachment A - Maintainability Design	A-1

TABLE OF CONTENTS (CONT'D)

Paragraph		Page
	List of Illustrations	
2.1	Organizational Task Responsibility Chart	2-2
2.2	Maintainability Schedule	2-4
2.3	Maintainability Data Requirements	2-6
3.1	Maintainability/Human Factors Failure	3-3/
	Reporting Form	

Section 1

INTRODUCTION

1.1 PURPOSE

The Maintainability Program Plan for the Vertical Package Conveyor (VPC) has been prepared and submitted in accordance with the Contract Data Requirements List, Sequence Number B001AA. This document is the master plan for implementing the Kornylak Corporation (KC) maintainability program.

1.2 SCOPE

The Maintainability Program Plan details the approach, procedures, schedules and management control that KC will use to achieve VPC maintainability within the requirements of the contract. This plan defines an organized approach to maintainability which encompasses the total range of effort from the initial conceptual phase and throughout the design, fabrication, assembly, test, and delivery of the VPC. The program is based on the required elements of Contract N00024-72-C-5500 and Military Standard, Maintainability Program Requirements MIL-STD-470.

1.3 OBJECTIVES

A maintainability program will be implemented at Kornylak to assure that requirements affecting VPC performance and operating success are identified and satisfied throughout the VPC contract. Maximum program effectiveness will be provided by interfacing with design personnel during the initial phases of the work and continuing throughout the fabrication and testing phases. Specific actions will be taken and controls instituted to meet program goals as described in this plan.

1.3.1 MAINTAINABILITY PROGRAM GOALS

The goal for mean time to repair is: No more than 1 of 20 simulated preventative maintenance (P.M.) tasks shall exceed 2 hours, and no P.M. tasks shall exceed 4 hours. No more than 2 of 20 corrective maintenance tasks shall exceed 5 hours and the mean time to repair shall not exceed 3 hours.

1.3.2 MAINTAINABILITY PHILOSOPHY

The maintainability philosophy will be to utilize to the maximum extent possible those design practices which allow for ease and speed of both preventative and corrective maintenance. Requirements for special tools or test equipment will be held to a minimum. Tasks requiring special skills will be reviewed to determine that no practical alternative exists.

Section 2

MAINTAINABILITY PROGRAM MANAGEMENT AND CONTROL

2.1 GENERAL

This section describes the organization, responsibilities, program planning and control, and documentation that will be used to manage and control the program.

In establishing and providing for a realistic and workable program management and control plan, the following was considered.

Task Responsibility. Each task is identified with an organization responsible for its completion.

Scheduling. Each task is scheduled.

Reporting. Program progress and status of accomplishment is reported on a continuing basis.

Monitoring. The program is monitored and a record kept of all changes so that continuity is maintained.

2.2 ORGANIZATION

Functional responsibility for the maintainability program lies within the Engineering Branch. Work tasks will be performed by personnel skilled in the disciplines and familiar with the activities required.


Figure 2-1 shows the responsibilities and task assignments by component organization. The masks were abstracted from the work statement requirements.

2.3 PROGRAM PLAN

The Program Plan was prepared in compliance with the VPC Program requirements. This plan constitutes the scope of work of the maintainability program.

2.4 PROGRAM REVISION

Any change in the scope of work will be documented in subsequent revisions of the program plan.



: Figure 2-1 Organizational Task Reponsibility Chart

٠,

2.5 PROGRAM CONTROL

Program management and control is provided on a continuing basis by supervision and management personnel. This activity is exemplified by adherence to scheduled milestones, and status reporting.

2.5.1 PROGRAM SCHEDULE

The functional areas of the program and the schedule of important milestones are identified in Figure 2-2. Milestone dates are in agreement with the overall program plans. Management controls will be maintained in order to meet task milestones in a timely and effective manner.

2.6 DOCUMENTATION

The program is documented by the following reports. Figure 2-3 lists the documents and the contractor Data Requirement List Sequence Number.

2.6.1 PROGRAM PLAN

This Preliminary Program Plan is submitted as required by contract. The final Program Plan for Phase II and III will be submitted 45 days after Phase TT work commences.

2.6.2 PROGRESS REPORTS

A maintainability progress report is submitted as a part of the Progress Report and includes all accomplishments for the preceding quarter.

2.6.3 FINAL REPORT

Inputs ... the Final keport will be provided at the completion of Phase III.

2.6.4 DEMONSTRATION TEST YLAN

A Maintainability Demonstration Test Plan will be submitted prior to the scheduled start of testing.

2.7 RELATION TO INTEGRATED LOGISTICS PLAY

The integrated logistics p. an must consider: 1) the maintainability plans provision for periodic maintenance, 2) spares provisioning necessary to meet the MTBF for specific equipments, and 3) equipment utilization to meet the availability requirements. When the maintainability requirements are established, the logistics plan should be amended to assure adequate spares to meet the requirements of the overall system.

12 13 14 15 PHASE III			O	
5 6 7 8 9 10 11 PHASE IT	*** ** **		•	
1. 1. 2. 3. 4. PHASE I	* * *		Ve	
NONTHS AFFER PLAN APPROVAL. TASKS	Maragement and control. Customer Review Nilestone Costs Reports Progress Reports	Plan - Preliminary Plan - Final *Demonstration Plan - Preliminary & Final	Analysis, Allocation, Prediction Design Reviews Subcontractor Support and Control Data Reporting, Analysis, Corrective Action	Maintenance Inputs Maintainability Design Criteria Human Factors Engineering System Safety Engineering

Figure 2-2 Maintainability Schedule

- Contractual Documentation Delivery

Scheduled Milestones

X - Support to Documentation Delivery

2.8 LIAISON BETWEEN MAINTAINABILITY AND RELIABILITY

There will be constant interchange of collected data between the maintainability and the reliability functions.

2.9 PROGRAM REVIEWS

Informal design reviews will be made on a continuing basis as the system/ equipment design evolves. To assure the incorporation of maintainability requirements, these informal reviews will includ a current comparison of maintenance time predictions with downtime apper mionments. The design guidelines will be used as guides in evaluating Jesigns for qualitative maintainability features.

PDR's will be conducted during the design phase of the program to maintain close liaison with program personnel and to provide assistance in:

- a. Evaluating the relative maintainability merit of system configuration being considered.
- b. Evaluating the effect of proposed design changes on system maintainability.

2.10 SUBCONTRACTOR RELATIONS

Subcontractors will be required as necessary to provide maintainability plans and/or maintainability data. Currently, no equipment subcontractors are contemplated. However, in the event that a subcontractor is chosen to design and produce a portion of the system, the requirements of this paragraph and MIL-STD-470 will be imposed.

TITLE	CONTRACTOR DATA REQUIREMEN'TS LIST	REMARKS
Program Plan	AOOLAA BOOLAB	Preliminary Final
Progress Reports	AOOLAE	Input to support documentation delivery quarterly
Final Report	• ACOLAF BOOLAG COOLAU	Input to support documentation delivery
Demonstration Test Plan	COOLAJ	Preliminary Final

Figure 2-3. Maintainability Data Requirements

Section 3

en de la compacta del compacta de la compacta de la compacta de la compacta de la compacta del compacta de la compacta del la compacta del la compacta de la compacta de la compacta de la compacta de la compacta de la

TASK PLAM

3.1 GENERAL

Section 3 describes the tasks, their objectives, schedules, and methods of implementation. Figure 2-1 shows the overall maintainability program by tasks grouped in their corresponding categories.

3.2 MAINTAINABILITY ANALYSIS

In order to satisfy program goals, Kornylak Corporation will perform analysis on critical components and parts during basic research and development, to influence the design of the VPC. The maintainability analysis of the system shall identify the maintainability characteristics of the equipment and components of the system in terms of their contribution to the overall system maintainability. Factors considered shall include, but not be limited to, mean time between failure, mean time to repair, mean time for scheduled maintenance, operational requirements, skills, special equipment. levels and location of facilities, and mean down time.

The output of the maintainability analysis will be the quantitative and qualitative maintainability requirement, with a maintenance concept and maintenance plan.

3.2.1 MAINTAINABILITY ALLOCATION

As an aid to design and to achieve required maintainability goals, allocation of maintainability parameters will be developed early in the program. The allocation will be made by assigning corrective downtime goals to part levels based on fail relates and preventive maintenance requirements. Item with the highest frequency of failure or servicing will be assigned maintenance time allocations sufficiently low that the required downtime criteria can be set.

3.2.2 MAINTARNABILITY PREDICTION

The contractor will provide predictions of maintainability parameter values for the system. The prediction technique used will be as defined in MIL-HDEK-72. The prediction technique will estimate the quantitative maintainability system parameter values for the planued design configuration. The quantitative estimates will be used to judge the adequacy of the proposed design to meet the maintainability predicted requirements and identify design features requiring corrective action.

3.3 MAINTAINABILITY DEMONSTRATION

Maintainability Demonstration will be accomplished by the Kornylak Corporation in accordance with the Maintainability Demonstration Plan. This plan will be developed in accordance with MII-STD-471, Military Standard Maintainability Demonstration.

3.4 HUMAN FACTORS ENGINEERING

The human factors engineering will support the maintainability activity. Principles and procedures of Human Factors Engineering will be applied to decisions during the development, manufacturing, testing and operation of the system. MIL-STD-1472 and MIL-H-46855 will be the basic reference documents. The approval of drawings by Engineering will verify that the configuration and arrangement of equipment satisfy man/equipment performance requirements.

3.5 MAINTAINABILITY ASSURANCE

The contractor will establish and periodically up-date detailed maintains ability criteria determined from the repetitive system analysis. Appropriate consideration of maintainability criteria will be reflected in design concept reviews, item selection, design reviews and trade-offs.

3.6 MAINTENANCE CONCEPT AND PLAN

One output of the maintainability analysis is the maintenance concept for the Vertical Package Conveyor. Areas to be covered in the maintenance concept include preventive maintenance such as lubrication of reducers, inspection and test requirements such as checking the torque limiting device setting, corrective maintenance concepts such as the replacement of relays and periodic overhaul requirements such as replacement of bearings.

The maintainability analysis will develop the preliminary maintenance plan specifying levels and types of maintenance required.

3.7 MAINTAINABILITY REPORTING

Maintainability and Human Factors data will be collected on the data form shown as Figure 3-1. This form will be initiated by the test engineer/technician when failures or unsatisfactory conditions occur. Copies of these reports will be used for Kornylak Corporation Maintainability analysis.

MAINTAINABILITY/HUMAN FACTORS FAILURE REPORT

Contract Number	Form Number
Date of Failure	
Elapsed Time at Time of Failure	hours
Elapsed Cycles at Time of Failure	cycles
Failed Piece Part of Item (Name and Identifi	cation)
Primary	
Secondary	
Cause of Failure (Design, Workmanship, Human	, Unknown, Wear-Cut, Other; Explain)
No. of previous failures of same part in tes	ting period
First Indication of Malfunction (Did Anyone	Observe the Failure?)
Note of Operation When Failure Occurred	
Errect of Failure on Part	
Effect of Failure on System	
Detailed Failure Analysis	•
Repair Action (or Action Taken to Correct De	
Eliminate, Modify, Design, Modify Part, Othe	r; Describe Concisely the Action Taken)
Describe any change in maintenance requireme	nts as result of repair action

2.	Cost of Repair Parts (or Remedy)		
3 .	Skill Level Required to Repair Failed I	tem	
	Diagnostic Time to Isolate Trouble	hours	min.
	* Actual Time to Repair	hours	min.
	Man-Hours to Repair	hours	min.
	**Down Time	hours	min.
•	Scheduled (Preventive) Maintenance Association	ciated with Failed Part	·
15.	Scheduled (Preventive) Maintenance Associate		•

Figure 3-1. Maintainability/Human Factors Failure Reporting Form

^{**}Down Time is the length of time that the unit is not operational. It incluies such times as time away from repair due to meals, holidays, waiting for ordered parts and administrative delays.

Maintainability analysis of the reports will be performed and the results of the analysis will be provided to design the Maintainability Plan and prepare the Maintenance Engineering Technical Manuals. Follow-up will be maintained and status reported in the progress reports.

Section V

Failure Modes and Effects Analysis

A. FMEA Selection and Criteria Report

The following FMEA Selection and Criteria Report was prepared and submitted to Naval Ship Engineering Center April 14, 1975 (see Item 2 of Section I of this Final Report).

B. Failure Modes and Effects Analysis

The pages immediately following the FMEA Selection and Criteria Report comprize the Failure Modes and Effects Analysis completed and submitted by the Contractor to Naval Ship Engineering Center on March 23, 1976 (see Item 8 of Section I of this Final Report).

FMEA Selection and Criteria Report DD 1423 Item BOOLAB

(partial fulfillment of line item 004 re Contract No. N00024-72-C-5500)

Copies: 6

Reproducibles: 0

Submitted: Commander, Naval Ship

Engineering Center

Center Bldg. Prince Georg. Center Hyattsville, Md. 20782

Code 6164

Attention: Mr. Satterthwaite

Mr. Otto cc:

Note: Original enclosed copy of DD 250 should be signed at destination and distribution made including a signed copy to:

Kornylak Corporation

400 Heaton Street Hamilton, Ohio 45011 Attention: Mr. R.A. Larson

Submittal date: 10 April 1975

F M E A
Selection and Criteria Report
CDRL Item B001AB
USN Contract N00024-72-C-5500
April 10, 1975

R. A. Larson, General Manager

Kornylak Corporation Hamilton, Ohio

FAILURE MODES AND EFFECTS ANALYSIS SELECTION AND CRITERIA REPORT

- 1. SCOPE
- 1.1 The Failure Modes and Effects Analysis (FMEA) Selection and Criteria Report contains:
 - (a) A narrative functional description of the vertical stores conveyor.
 - (b) A functional block diagram.
 - (c) An indentured block diagram detailed down to the indentured level which will identify replaceable parts or components.
 - (d) A list of the items recommended for FMEA application.
 - (e) An outline of the depth to which FMEA will be applied within each assembly and subassembly.
 - (f) A description of the type of failure modes associated with each item selected for FMEA application.
 - (g) A description of the criteria to be used for identifying critical items (MIL-STD-1629 (Ships) will be used as applicable).
 - (h) The rational for selecting the items and associated failure modes for FMEA.
- 2. APPLICABLE DOCUMENTS
- 2.1 To the extent applicable the following documents will be used to prepare and support this report:

Standards:

MIL-STD-470 -- Maintainability Program Requirements

(for Systems and Equipment)

MIL-STD-785 -- Reliability Program for Systems and

Equipment Development and Production

MIL-STD-1629 -- Procedures for Performing a Failure (Ships)

Mode and Effect Analysis for Shipboard

Equipment

Reports:

"Reliability and Maintainability Program Plans - Final" (prepared by Kornylak Corporation and submitted

January 28, 1975 under CDRL Item B001AA of USN Contract

#N00024-72-C-5500).

"Reliability Studies Including Corrective Action Plan for Vertical Package Conveyor" (prepared by Kornylak Corporation and submitted August 10, 1972 under CDRL Item A001AG-1 of USN Contract #N00024-72-C-5500.

- 3. EQUIPMENT DESCRIPTION AND FUNCTIONAL BLOCK DIAGRAM
- Narrative functional description. The vertical stores conveyor is used to convey goods and stores from one ship's level to another. The conveyor is equipped with vertically moving trays to carry packages weighing up to 100 pounds in sizes up to 36 inches wide by 24 inches deep by 36 inches high. Each load station is equipped with platforms that can be positioned to mechanically eject packages at that load station; these devices can also be positioned as a load platform to position loads for pick-up during strike-up operation. Speed of operation can be selected at 8, 12 and 16 trays per minute. The machine is electrically motor-driven through a non-overhauling

reducer. An electrical brake is used to stop conveyor motion. The conveyor is controlled thru a series of push-button stations located at each load station. One of these stations is designated the "master control station" and has the additional function of turning power "on" and selecting conveyor speed. Safety devices are incorporated to protect the motor against overload and to sense incipient package jams stopping the conveyor. An audio signal warns the operator that the conveyor is about to start.

3.2 <u>Functional block diagram</u>. The following block diagram and block diagram sub-systems provide the structural data for the FMEA.

Number 100 - Vertical conveyor system

Number 10 - Drive system

Number 20 - Structure

Number 30 - Operating system

Number 40 - Control system

Number 50 - Safety devices

Number 60 - Load/unload devices

The functional interrelationships between these devices and sub-systems is shown on Figure No. 1.

3.2.1 Sub-System number-10 - Drive system

The drive system powers the conveyor thru a chain and sprocket system.

The drive sprocket and chain are considered part of the drive system. The rest of the system consists of:

Number 10.1 - Base plate

Number 10.2 - Motor

Number 10.3 - Torque limiter

Number 10.4 - Reducer

Number 10.5 - Brake

Number 10.6 - Jack shaft coupling

Number 10.7 - Jack Shaft

Number 10.8 - Pillow block bearing

Number 10.9 - Drive sprockets & keys

Number 10.10 - Drive chain

Number 10.11 - Drive chain take-up

The drive system may be back, left side or right side mounted - as selected by the procuring activity. The functional interrelationship between the components of the drive system is shown on Figure No. 2.

3.2.2 <u>Sub-System number 20 - Structure</u>

The structure consists of the conveyor trunk or frame, door frames and doors, and various internal shields. The trunk or frame is the basic supporting and mounting structure for the drive system and all operating elements. The door frame is fastened to the trunk (not the frame of frame types) and supports the door hinging and "dogging" mechanism. A variety of shields are included as "structure" although they do not contribute to conveyor support. These shields guard the package area and the operating mechanism. The structure consists of:

Number 20.1 - Trunk (or frame)

Number 20.2 - Door framing

Number 20.3 - Shields

3.2.2.1 The main structure or trunk of the conveyor is sized to adequately support the drive system, operating system, shields, door frames and operating loads. The trunk is also sized to withstand whatever water pressure head is specified by the procuring activity. The trunk is permanently welded to the ship's deck and becomes a part of the ship's structure. The trunk consists of welded plates forming a rectangular box of a length necessary to service the deck levels specified. The shields are formed sheet steel bolted or welded to the trunk by suitable supports and/or bracketry. Door frames are welded





FIGURE NO. 1 Second indenture level functional block diagram.



NOTE: All components are sized and rated as a function of conveyor loading.

FIGURE NO. 2 Third indentured level functional block diagram for drive system (Number 10)




FIGURE NO. 4 Third indentured level functional block diagram for the control system (Number 40).

to the outside of the trunk at the deck levels serviced. The Contractor is not planning to perform failure modes and effects analysis on the Structure Sub-system.

3.2.3 Sub-system Number 30 - Operating System

The operating system consists of those parts which lift and lower the loads. The loads are positioned on "carriers" attached to a "carrier chain" supported by head and tail sprockets. The carriers operate in tracks which guide the carriers and which tilt the carriers from the horizontal flat position for load carrying to the vertical position for return at the back of the conveyor. The load area is separated from the return area by back shields The operating system consists of:

Number 30.1 - Head cam plate

Number 30.2 - Head shaft

Number 30.3 - Head shaft bearings

Number 30.4 - Head bearing housing

Number 30.5 - Head shaft sprocket

Number 30.6 - Carrier chain section

Number 30.7 - Carrier link

Number 30.8 - Chain pin

Number 30.9 - Carrier shaft

Number 30.10 - Guide arm

Number 30.11 - Cuide arm cap

Number 30.12 - Cam follower - flanged

Number 30.13 - Cam follower

Number 30.14 - Carrier

Number 30.15 - Front track

Number 30.16 - Rear track

Number 30.17 - Tail cam plate

Number 30.18 - Tail carrier sprocket

Number 30.19 - Tail sprocket bearings

Number 30.20 - Chain take-up

Number 30.21 - Head driven sprocket

The functional interrelationship between the components of the operating system is shown on Figure No. 3.

3.2.4 Sub-system Number 40 - Control System

The control systems consists of the controller, the master station, the machinery area station and intermediate control stations located at each ship's level serviced by the conveyor. The controller passes ships power at 440 Volts, 3-phase, 60 hertz through relays to the conveyor motor and brake. The relays are operated by the master, machinery and intermediate stations to start or stop the conveyor. The master station selects which of the stations will be in control, the speed of the conveyor, and, the direction of motion - up or down. The machinery station is equipped with a jog switch allowing intermittent motion of the conveyor in either the up or down direction to facilitate maintenance and repair. Safety devices (see par. 3.2.5) operate to stop the conveyor by interrupting power to the motor and brake. The brake is "fail safe" in that the brake is "on" when the power is "off". Both the motor and the brake will be analyzed as part of the Drive System (Number 10); they are included here to complete the electrical circuitry diagram. Elements of the Control system are:

Number 40.1 - Controller

Number 40.2 - Master station

Number 40.3 - Machinery station

Number 40.4 - Intermediate station(s)

The functional interrelationship between the elements of the control system is shown in Figure No. 4.

THIS PAGE IS MISSING IN ORIGINAL DOCUMENT




FIGURE NO. 3 Third indentured level functional block diagram for operating system (Number 30)

3.2.4.1 Controller. The controller performs the function of housing the 3-speed motor reversing starter, the instant overload relay (IOL) and bypass timer, the thermal overload device, the emergency run button, the audio signal timer, three relays activated by the safety devices (Number 50, par. 3.2.5), and three relays activated by the speed selector switch (Number 40.2, par. 3.2.4). The controller receives ship's power and, at the command of the controlling stations and the safety devices, turns the motor on or off. The controller is usually mounted in a secure but accessible location either on the ship's bulkhead or on the trunk of the conveyor. All elements of the controller are replaceable. These elements consist of:

Number 40.1.1 - 3-speed reversing starter

Number 40.1.2 - Thermal overload device

Number 40.1.3 - Emergency run switch

Number 40.1.4 - Instant overload relay (IOL)

Number 40.1.5 - IOL by-pass timer

Number 40.1.6 - 440V to 110V transformer

Number 40.1.7 - 1st speed relay

Number 40.1.8 - 2nd speed relay

Number 40.1.9 - 3rd speed relay


Number 40.1.10 - Over-the-door jam sensing relay

Number 40.1.11 - Loader/unloader interlock and jam sensing relay

Number 40.1.12 - Door interlock relay

Number 40.1.13 - Audio signal timer

The functional interrelationships between these elements, the safety devices, and the control system is shown in Figure No. 5.



3.2.4.2 Number 40.2 - Master control station. The master control station performs the function of turning power on to power itself and all other stations. Power "on" is indicated by a green light. The master control station also selects one of three motor speeds, the direction of motion, and, which station will control the conveyor. All elements are replaceable. The master control station is usually mounted on the conveyor trunk, at the main deck level. Elements consist of:

Number 40.2.1 - Power on/off selector switch

Number 40.2.2 - Three position speed selector switch

Number 40.2.3 - Two position conveyor motion switch (up/down)

Number 40.2.4 - One or more three position station selector switches

3.2.4.3 Number 40.3 - Machinery station. The machinery station is located in the machinery area to enable maintenance and repair personnel to operate the conveyor. All elements are replaceable. This station is equipped with:

Number 40.3.1 - Green power - on light

Number 40.3.2 - Start button

Number 40.3.3 - Stop/run switch

Number 40.3.4 - Jog switch

3.2.4.4 <u>Number 40.4 - Intermediate stations.</u> All intermediate stations are identically equipped and are the same as the machinery station except they have no jog switch. Functions are to start and to stop the conveyor during strike-up operation or should an emergency arise. Any intermediate station can stop the conveyor; all stop/run switches must be in the run position for the conveyor to operate.

3.2.5 Sub-System number 50 - Safety devices

Safety devices may be considered in the following general categories:

1) motor protection
2) personnel protection
3) protection against conveyor damage due to jamming

Following is a brief description of each safety device identifying function and the category into which the safety device fits.

Number 50.1 - Instantaneous overload - motor protection - allows an initial amperage surge for start-up - cuts off power if following amperage surges exceed a pre-set value.

- Number 50.2 Thermal overload motor protection cuts off

 power if motor amperage develops sufficient

 heat to exceed a pre-set value.
- Number 50.3 Audio signal personnel protection sounds an audio signal at each level warning personnel that the conveyor is about to start operates automatically for 2 to 3 seconds after the start action has been initiated but before the conveyor actually runs.
- Number 50.4 Brake personnel protection stops the conveyor
 within narrow limits whenever power is cut-off.

 Prevents the conveyor from back-traveling even
 though the conveyor is equipped with a nonoverhauling reducer.

Number 50.5 - Bottom overtravel - conveyor protection
prevents packages passing through and jamming

at the bottom of the conveyor - senses

incipient jamming - operates during strike-down

only.

Number 50.6 - Loader/unloader interlock - conveyor protection
prevents strike-down operation should the loader/

unloader be in the horizontal load position

instead of the tilted, unload, position
operates during strike-down.

Number 50.7 - Loader/unloader jam sensing - conveyor protection stops the conveyor should a down coming tray strike
a package not completely ejected after the package
has depressed the loader/unloader a pre-set
distance - senses incipient jamming - operates
during strike-down.

Number 50.8 - Door interlock - conveyor protection - prevents strike-down operation unless the door at the unload station is fully open.

Number 50.9 - Top overtravel - conveyor protection prevents

packages passing through and jamming at the top

of the conveyor - senses incipient jamming
operates during strike-up only.

Number 50.10 - Over-the-door-jam sensing - conveyor protection stops the conveyor if disturbed by a misplaced
package - most effective in preventing package
jamming between the tray and the upper door
coaming-senses incipient jamming - operates during
strike-up and strike-down.




FIGURE NO. 6 - Third indentured level functional block diagram for safety devices (Number 50).

Number 50.11 - Torque limiter - conveyor protection - set to slip at 110 to 115% of total load - operates continuously - will prevent conveyor and motor damage should all other devices fail.

The functional interrelationships between the safety devices are shown on Figure No. 6.

3.2.6 Sub-System Number 60 - Load/unload devices

Load/unload devices are supplied to enable the operators to conveniently load and unload packages into and out-of the conveyor. They may be positioned in one of three ways:

Load - horizontal to enable operators to place packages on
the fingers of the load/unload device. The fingers
of the tray pass between the fingers of the load/unload
device and pick-up the package, carrying the package up.
A safety interlock (Figure 4, 50.6) prevents strikedown operation when the load/unload device is in the "load"
position. Usually simple wheel type conveying sections
are hooked-to the load/unload device so that packages
may be rapidly on-loaded.

Unload - tilted about 30° from the horizontal. Packages carried by the trays strike the fingers of the load/unload device and slide out of the load area of the conveyor.

Usually simple wheel type conveying sections are hooked-to the load/unload device so that packages may be rapidly removed from the door opening. A door interlock

(Figure 4, 50.8) is included at each serviced level to assure that the door is fully open at the unload station before the conveyor will operate in the

strike-down mode.

Stowed - vertical either up or down. When the load/unload device is in the stowed downward position, loads may be unloaded from that station during strike-up operation. At times it is preferable to stow the load/unload device in the upward position where it acts as a personnel guard. Stowing upward or downward is an option of the procuring activity.

The load/unload device incorporates two additional safety features:

one - the fingers of the load/unload device are spring loaded and are capable of being depressed should a downcoming tray strike and press against a package inadvertently not removed from the package area. As the fingers of the load/unload device depress a micro-switch is activated which immediately cuts-off conveyor power.

two - the load/unload device is arranged to "hinge" when the device is in the load or unload positions. Thus, in the event packages strike the bottom of the load/unload device, the device will hinge upward and toward the door opening, out of the way of the upcoming package.

The functional interrelationship between the elements of the load/unload device is shown in Figure No. 7. These elements consist of:

Number 60.1 - Platform

Number 60.2 - Mtg. and stowing bracket R.H.

Number 60.3 - Mtg. and stowing bracket L.H.

Number 60.4 - Platform depress mechanism L.H.

Number 60.5 - Platform depress mechanism R.H.

Number 60.6 - Cross shaft

Number 60.7 - Interlock microswitch

Number 60.8 - Jam sensing microswitch




FIGURE NO. 7 - Third level indentured functional block diagram for the load/unload device (Number 60).

4. FMEA LIST 4.1 The list of items recommended for FMEA application is composed of all items listed in the following paragraphs: Paragraph: 3.2.1 Paragraph: 3.2.3 Paragraph: 3.2.4.1 Paragraph: 3.2.4.2 Paragraph: 3.2.4.3 Paragraph: 3.2.5 Paragraph: 3.2.6 5. FMEA DEPTH 5.1 The FMEA analysis will be performed on each major assembly and sub-assembly of the functional systems identified in paragraph 3.2, to the depth necessary to identify replaceable parts and components composing the assemblies and sub-assemblies. 6. FAILURE MODES 6.1 The Contractor analyzed data supplied by the Navy's Maintenance Support Office (MSO) Material History Report, MSO No. 479052704.A07, Volumes 1 and 2. This data covered 10 manufacturers of vertical stores conveyors during the period between January 1, 1970 thru April 1972 (2-1/3 years). The data described failures which occurred on 132 vertical stores conveyors ranging in capacity from 85 to 4,000 pounds per tray. The Contractor's report provided a statistical interpretation of this data and included a "corrective action plan". The report titled, "Reliability Studies Including Corrective Action Plan for Vertical Package Conveyor" was submitted to NAVSEC August 10, 1972. To the Contractor's knowledge no more valid source of data identifying the failures occurring to parts and systems of vertical stores conveyors is anywhere else available. - 20 -

6.2 The report identified above provides a valid statistical base for the selecting failure modes. The FMEA alysis, which will be performed as required by CDRL item B001AH, will analyze each item, system, or sub-system, of paragraph 4.1 and will use the work sheet shown as Figure 2 of MIL-STD-1629 (Ships) as the basic analysis tool. Failure modes for each of the items selected for analysis will be provided in the FMEA report.

7. CRITERIA FOR IDENTIFYING CRITICAL ITEMS

- 7.1 Criticality of the effect of item failure will be established using the techniques outlined in MIL-STD-1629 (Ships), par. 5.11 and 5.11.1.
- Criticality is defined as the combination of probability of occurrence 7.1.1 and the level of severity. A criticality matrix will be used as the means of identifying and comparing each failure mode to all other failure modes with respect to the ship's mission and the items functional output and maintenance.
- 7.1.1.i Severity is classified as follows: (MIL-STD-1629 SHIPS, par. 5.9.1)
 - (a) Level 1, minor. Characterized by any one or combinations of the following conditions:
 - (1) No effect on ship's mission capability.
 - (2) Negligible effect on functional output of the item at the initial indenture level.
 - (3) Other indenture level item degradation that can be repaired by performing "adjustment type" maintenance.
 - (b) Level 2, major. Characterized by any one or combinations of the following conditions:
 - (1) Negligible effect on ship's mission capability.
 - (2) Degradation in functional output of the item at the initial indenture level.
 - (3) Other indenture level item failure that can be repaired immediately within the capability of organization level maintenance.

(c) Level 3, critical. Characterized by any one or combinations of the following conditions:
(1) Some degradation in ship's mission capability.
(2) Severe reduction in functional output of the item at the initial indenture level.
(3) Other indenture level item failure that cannot be repaired immediately within the capability of organizational

(shipboard) level maintenance.

- (d) <u>Level 4, catastrophic.</u> Characterized by any one or combinations of the following conditions:
 - (1) Severe reduction in ship's mission capability.
 - (2) Complete functional output loss of the item at the initial indenture level.
 - (3) Other indenture level item failure requiring tender or depot maintenance repair.

The level of severity selected shall be the highest level an item falls under, regardless of whether a lower classification is also applicable.

7.1.1.2 Failure probability shall be assessed in both quantitative and qualitative terms (MIL-STD-1629 (SHIPS), par. 5.10, 5.10.1, 5,10,2, 5.10.2.1 and 5.10.2.2).

Failure probability level guidlines.

Qualitative. The following sample guidelines are suggested for developing definitions for failure probability levels in qualitative terms:

- (a) Level 1 Failure mode probability very low. A negligible chance of occurrence during the item operating time interval.
- (b) Level 2 Failure mode probability low. An unlikely chance of occurrence during item operating time interval.
- (c) Level 3 Failure mode probability medium. A random fifty/fifty chance of occurrence during item operating time interval.

(d) Level 4 - Failure mode probability high. A likely change of occurrence during the item operating time interval. Quantitative. The following sample guidelines are suggested for developing definitions for failure probability levels in quantitative terms: (a) Level 1 (very low). Any single failure mode probability of occurrence which is less than 0.01 of the overall probability of failure during the item operating time interval. (b) Level 2 (low). Any single failure mode probability of occurrence which is more than 0.01 but less than 0.10 of the overall probability of failure during the item operating time interval. (c) Level 3 (medium). Any single failure mode probability of occurrence which is more than 0.10 but less than 0.20 of the overall probability of failure during the item operating time interval. (d) Level 4 (high). Any single failure mode probability of occurrence which is more than 0.20 of the overall probability of failure during the item operating time interval. These recommended definitions shall be modified or expanded as necessary, depending on the system or equipment being analyzed and the amount of failure data available for the type of hardware involved. - 23 -

8. FMEA ITEM SELECTION RATIONAL 8.1 The items selected for FMEA analysis were selected based on the following rational: (a) any item the failure of which would prevent conveyor operation, (b) any item the failure of which would affect the operation of another system or sub-system. Example: failure of the loader/ unloader micro-switch jam sensing switch would not prevent or interfere with conveyor operation. However, should a jam occur, the micro-switch would fail to operate and serious damage could result since motor current would continue until either - cut-off by the IOL, - cut-off by the thermal overload protection device Failure of these systems to function would eventually force the torque limiter to slip. (c) any item the failure of which should be repaired to continue efficient conveyor operation or to minimize the possibility of eventual damage or wear to other systems, sub-systems or components. Example: freeze-up of a guide arm cam follower. By itself this failure is not overly detrimental, however, the frozen bearing would slide instead of roll along the track causing eventual wear to the track and bottom and top cam plates. Additional power would be required. If enough cam followers failed, wear would be rapid and power would exceed the limits of the IOL or thermal overload causing these devices to cut motor current.

Failure Mode and Effects Analysis Report DD 1423 Item B001AH

(Partial Fulfillment of Line Item 004 Re Contract No. N00024-72-C-5500)

Copies: Six

Reproducibles: None

Submitted: Commander, Naval Ship

Engineering Center

Center Building Prince George Center

Hyattsville, Maryland 20782

Code 6164

ATTENTION: Mr. Satterthwaite

COPY TO: Mr. Otto

Submittal Date: March 24, 1976

Failure Modes and Effects Analysis Report

(CDRL Item B001AH)

March 24, 1976

R. A. Larson, Controller

Kornylak Corporation Hamilton, Ohio

Introduction

This Failure and Effects Analysis Report has been prepared by the Kornylak Corporation, 400 Heaton Street, Hamilton, Ohio 45211 as a response to Contractor Data Requirement List Item B001AH of USN Contract N00024-72-C-5500.

The report covers the modes and effects of potential failure of significant parts, components, sub-assemblies and assemblies designed for incorporation into a "hi-reliability" vertical stores conveyor per contractural specification Ships-C-5552. Specifically this report has been prepared in accord with paragraphs 3.2.5, 3.2.5.1 and 3.2.5.2 of Ships-C-5552. The format of the report relies on MIL-STD-1629 titled "Procedures for Performing a Failure and Effects Analysis for Shipboard Equipment" provided to the contractor by Naval Ships Engineering Center for this purpose.

TABLE OF CONTENTS

Title Page	i
Introduction	ii
Table of Contents	iii
List of Figures	v
1. Scope	1
2. Applicable Documents	1
3. Equipment Description and Functional Block Diagram	2
3.1 Narrative Functional Description	2
3.2 Functional Block Diagram	3
3.2.1 Sub-system Number 10	4
Drive System	4
3.2.2 Sub-system Number 20 - Structure	4
3.2.3 Sub-system Number 30	5
Operating System	5
3.2.4 Sub-system Number 40	6
Control System	6
3.2.5 Sub-system Number 50	9
Safety Devices	9
3.2.6 Sub-system Number 60	11
Load/Unload Devices	11
4. FMEA List	13
5. FMEA Depth	14
6. Failure Modes	14
7. Criteria for Identifying Critical Items	15
8. FMEA Item Selection Rationale	18
9. FMEA Analysis	10

TABLE OF CONTENTS (Cont'd)

Analysis of Drive System	•••••
9.2 Analysis of Structure	2
9.3 Analysis of Operating System	26
9.4 Analysis of Control System	3:
9.5 Analysis of Safety Devices	38
9.6 Analysis of Load/Unload Devices	3
10. Working Papers	4:
10.1 Working Papers for Drive System	4
10.2 Working Papers for Structure	5
10.3 Working Papers for Operating System	5.
10.4 Working Papers for Control System	7:
10.5 Working Papers for Safety Devices	8
10.6 Working Papers for Load/Unload Device	9
11. Conclusions and Recommendations	100

LIST OF FIGURES

Figure No.	1 - Second Indenture Level Functional Block Diagram	109
Figure No.	2 - Third Indenture Level Functional Diagram for Drive System (Number 10)	110
Figure No.	3 - Third Indenture Level Functional Block Diagram for Operating System (Number 30)	111
Figure No.	4 - Third Indenture Level Functional Block Diagram for Control System (Number 40)	112
Figure No.	5 - Fourth Indenture Level Functional Block Diagram of the Elements of the Controller (Number 40.1)	113
Figure No.	6 - Third Indenture Level Functional Block Diagram for Safety Devices (Number 50)	114
Figure No.	7 - Third Indenture Level Functional Block Diagram for the Load/Unloader Device (Number 60)	115
Figure No.	8 - Criticality Matrix - Drive System (Number 10)	116
Figure No.	8(a)Tabulation for Drive System (Number 10)	117
Figure No.	9 - Criticality Matrix - Conveyor Structure (Number 20)	118
Figure No.	9(a)Tabulation for Conveyor Structure (Number 20)	119
Figure No.	10 - Criticality Matrix - Operating System (Number 30)	120
Figure No.	10(a)Tabulation for Operating System (Number 30)	121
Figure No.	11 - Criticality Matrix - Control System (Number 40)	122
Figure No.	11(a)Tabulation for Control System (Number 40)	123
Figure No.	12 - Criticality Matrix - Safety Devices (Number 50)	124
Figure No.	12(a)Tabulation for Safety Devices (Number 50)	125
Figure No.	13 - Criticality Matrix - Load/Unload Device (Number 60)	126
Figure No.	13(a)Tabulation for Load/Unload Device (Number 60)	127
Figure No.	14 - Criticality Matrix - Overview of All Sections	128

Failure Modes and Effects Analysis Report 1. SCOPE 1.1 The Failure Modes and Effects Analysis (FMEA) Report contains: (a) A narrative functional description of the vertical stores conveyor.

- (b) A functional block diagram.
- (c) An indentured block diagram detailed down to the indentured level which will identify replaceable parts or components.
- (d) A list of the items recommended for FMEA application.
- (e) An outline of the depth of which FMEA will be applied within each assembly and sub-assembly.
- (f) A description of the type of failure modes associated with each item selected for FMEA application.
- (g) A description of the criteria to be used for identifying critical items (MIL-STD-1629 [Ships] will be used as applicable).
- (h) The rationale for selecting the items and associated failure modes for FMEA.
- (i) A complete FMEA of the vertical stores conveyor including analysis, working papers, criticality matrix and criticality tabulation.

2. APPLICABLE DOCUMENTS

2.1 To the extent applicable, the following documents will be used to prepare and support this report:

Standards:

MIL-STD-470 - Maintainability Program Requirements (for Systems and Equipment)

MIL-STD-785 - Reliability Program for Systems and Equipment Development and Production

MIL-STD-1629 - Procedures for Performing a Failure (Ships) Mode and Effect Analysis for Shipboard Equipment

Reports:

"Reliability and Maintainability Program Plans -Final" (prepared by Kornylak Corporation and submitted January 28, 1975 under CDRL Item B001AA of USN Contract NO0024-72-C-5500).

"Reliability Studies Including Corrective Action Plan for Vertical Package Conveyor" (prepared by Kornylak Corporation and submitted August 10, 1972 under CDRL Item A001AG-1 of USN Contract N00024-72-G-5500).

FMEA Selection and Criteria Report (prepared by Kornylak Corporation and submitted April 10, 1975 under CDRL Item B001AB of USN Contract N00024-72-C-5500).

3. EQUIPMENT DESCRIPTION AND FUNCTIONAL BLOCK DIAGRAM

3.1 Narrative Functional Description. The vertical stores conveyor is used to convey goods and stores from one ship's level to another. The conveyor is equipped with vertically moving trays to carry packages weighing up to 100 pounds in size and up to 36 inches wide by 24 inches deep by 36 inches high. Each load station is equipped with platforms that can be positioned to mechanically eject packages at that load station; these devices can also be positioned as a load platform to position loads for pick-up during strikeup operation. Speed of operatio.. can be selected at eight, 10.7 and 16 trays per minute. The machine is electrically motor-driven through a non-overhauling reducer. An electrical brake is used to stop conveyor motion. The conveyor is controlled through a series of push-button stations located at each load station. The function of turning power "on" and selecting conveyor speed is located at the "Controller" which also houses the starting relays, safety relays and other electrical equipment. Safety devices are incorporated to protect the motor against overload and which sense incipient package jams in order to stop the conveyor. An audio signal warns the operator that the conveyor is about to start.

3.2 <u>Functional Block Diagram</u>. The following block diagram and block diagram sub-systems provide the structural data for the FMEA.

Number	100	Vertical Conveyor System
Number	10	Drive System
Number	20	Structure
Number	30	Operating System
Number	40	Control System
Number	50	Safety Devices
Number	60	Load/Unload Devices

The functional interrelationships between these devices and sub-systems is shown on Figure No. 1.

3.2.1 <u>Sub-system Number 10 - Drive System</u>. The drive system powers the conveyor through a chain and sprocket system. The drive sprocket and chain are considered part of the drive system. the rest of the system consists of:

statistical property of the second contract of the second

ene energy proposition proposition proposition and the composition of the proposition and the composition of the

Number 10.1 Base Plate Number 10.2 Motor Number 10.3 Torque Limiter Number 10.4 Reducer Number 10.5 Brake Number 10.6 Jack Shaft Coupling Jack Shaft Number 10.7 Pillow Block Bearing Number 10.8 Number 10.9 Drive Sprockets and Keys Number 10.10 Drive Chain Drive Chain Take-up Number 10.11

The drive system may be mounted on the back, left side or right side - as selected by the procuring activity. The functional interrelationship between the components of the drive system is shown on Figure No. 2.

3.2.2 <u>Sub-system Number 20 - Structure</u>. The structure consists of the conveyor trunk or frame, door frames and doors, and various internal shields. The trunk or frame is the basic supporting and mounting structure for the drive system and all operating elements. The door frame is fastened to the trunk (not the frame of frame types) and supports the door hinging and "dogging" mechanism. A variety of shields are included as "structure" although they do not contribute to conveyor support. These shields guard the package area and the

operating mechanism. The structure consists of:

Number 20.1

Trunk (or Frame)

Number 20.2

Door Framing

Number 20.3

Shields

- 3.2.2.1 The main structure or trunk of the conveyor is sized to adequately support the drive system, operating system, shields, door frames and operating loads. The trunk is also sized to withstand whatever water pressure head is specified by the procuring activity. The trunk is permanently welded to the ship's deck and becomes a part of the ship's structure. The trunk consists of welded plates forming a rectangular box of a length necessary to service the deck levels specified. The shields are formed sheet steel bolted or welded to the trunk by suitable supports and/or bracketry. Door frames are welded to the outside of the trunk at the deck levels serviced. The Contractor is not planning to perform failure modes and effects analysis on the Structure Sub-system except in compliance with NAVSEC letter Ser. #367 dated 21 May 1975. paragraphs 1.b(2) and (3). (Note: paragraph 1-b(1) is a shippard installation problem beyond the Contractor's control).
 - 3.2.3 Sub-system Number 30 Operating System. The operating system consists of those parts which lift and lower the loads. The loads are positioned on "carriers" attached to a "carrier chain" supported by head and tail sprockets.

 The carriers operate in tracks which guide the carriers and which tilt the carriers from the horizontal flat

position for load carrying to the vertical position for return at the back of the conveyor. The load area is separated from the return area by back shields. The operating system consists of:

Number 30.1	Head Cam Plate
Number 30.2	Head Shaft
Number 30.3	Head Shaft Bearings
Number 30.4	Head Bearing Housing
Number 30.5	Head Shaft Sprocket
Number 30.6	Carrier Chain Section
Number 30.7	Carrier Link
Number 30.8	Chain Pin
Number 30.9	Carrier Shaft
Number 30.10	Guide Arm
Number 30.11	Guide Arm Cap
Number 30.12	Cam Follower - Flanged
Number 30.13	Cam Follower
Number 30.14	Carrier
Number 30.15	Front Track
Number 30.16	Rear Track
Number 30.17	Tail Cam Plate
Number 30.18	Tail Carrier Sprocket
Number 30.19	Tail Sprocket Bearings
Number 30.20	Chain Take-up
Number 30.21	Head Driven Sprocket

The functional interrelationship between the components of the operating system is shown on Figure No. 3.

3.2.4 <u>Sub-system Number 40 - Control System</u>. The control systems consist of the Controller and intermediate control stations

located at each ship's level serviced by the conveyor and in the machine area. The Controller passes ship's power at 440 Volts, three-phase, 60 hertz through relays to the motor and brake. The relays are operated by controls at the intermediate stations to start or stop the conveyor. Switches located in the Controller turn power on or off to the control stations and select the speed of the conveyor. Safety devices (see paragraph 3.2.5) operate to stop the conveyor by interrupting power to the motor and brake. The brake is "fail safe" in that the brake is "on" when the power is "off". Both the motor and the brake will be analyzed as part of the Drive System (Number 10); they are included here to complete the electrical circuitry diagram. Elements of the Control System are:

Number 40.1 Controller

Number 40.2 Controller Station

Number 40.3 Intermediate Station (s)

The functional interrelationship between the elements of the control system is shown in Figure No. 4.

on the entry of a transportation of the bose of a transportation of the property of the property of the appropriate of

3.2.4.1 Controller. The Controller performs the function of housing the three-speed motor reversing starter, the instant overload relay (IOL) and by-pass timer, three relays activated by the safety devices (Number 50, paragraph 3.2.5), and three relays activated by the speed selector switch (Number 40.2.2, paragraph 3.2.4.2). The Controller receives ship's power and, at the command of the controlling stations and the safety devices, turns the motor on or off. The Controller is usually mounted in a secure but accessible location either on the ship's

bulkhead or on the trunk of the conveyor. All elements of the Controller are replaceable. These elements consists of:

Number	40.1.1	Three-speed Reversing Starter
Number	40.1.2	Thermal Overload Device
Number	40.1.3	Instant Overload Relay (IOL)
Number	40.1.4	IOL By-pass Timer
Number	40.1.5	440 Volt to 110 Volt Transformer
Number	40.1.6	First Speed Relay
Number	40.1.7	Second Speed Relay
Number	40.1.8	Third Speed Relay
Number	40.1.9	Over-the-door Jam Sensing Relay
Number	40.1.10	Loader/Unloader Interlock and Jam
		Sensing Relay

Number 40.1.11 Audio Signal Timer

The functional interrrelationships between these elements, the safety devices, and the control system is shown in Figure No. 5.

3.2.4.2 Number 40.2 - Controller Station. The Controller station performs the function of turning power "on" to power all other stations. Power "on" is indicated by a red light. This station also houses the three-speed selector switch and the emergency run switch. All elements are replaceable. The emergency run switch by-passes the instantaneous overload and the thermal overload protecting the motor to allow emergency operation of the conveyor. Elements consist of:

Number 40.2.1 Power On/Off Selector Switch

Number 40.2.2 Three-position Speed Selector Switch

Number 40.2.3 Power "On" Light (Red)

Number 40.2.4 Emergency Run Switch

3.2.4.3 Number 40.3 - Intermediate Stations. All intermediate station stations are identically equipped; an intermediate station is located in the machinery area to enable maintenance personnel to operate the conveyor. The intermediate stations function to designate conveyor direction, up or down, and to stop the conveyor in the event of an emergency. Any intermediate station can stop the conveyor; all "stop/on" switches must be in the "on" position for the conveyor to operate.

Number 40.3.1 Power "On" Light (Green)

Number 40.3.2 Stop Push - On Pull (Red Light on Stop)

Number 40.3.3 Up Push Button

Number 40.3.4 Down Push Button

- 3.2.5 <u>Sub-system Number 50 Safety Devices</u>. Safety devices may be considered in the following general categories:
 - (1) Motor Protection
 - (2) Personnel Protection
 - (3) Protection Against Conveyor Damage Due
 To Jamming

Following is a brief description of each safety device identifying function and the category into which the safety device fits.

Number 50.1 - Instantaneous overload - motor protection allows an initial amperage surge for startup - cuts off power if following amperage
surges exceed a pre-set value.

- Number 50.2 Thermal overload motor protection
 cuts off power if motor amperage develops

 sufficient heat to exceed a pre-set value.
- Number 50.3 Audio signal personnel protection sounds an audio signal at each level
 warning personnel that the conveyor is
 about to start operates automatically
 for two to three seconds after the start
 action has been initiated but before the
 conveyor actually runs.
- Number 50.4 Brake personnel protection stops the conveyor within narrow limits whenever power is cut off. Prevents the conveyor from back-traveling even though the conveyor is equipped with a non-overhauling reducer.
- Number 50.5 Bottom overtravel conveyor protection
 prevents packages passing through and

 jamming at the bottom of the conveyor
 senses incipient jamming operates during

 strike-down only.
- Number 50.6 Loader/Unloader interlock conveyor

 protection prevents strike-down operation

 should the loader/unloader be in the horizontal

 load position instead of the tilted, unload,

 position operates during strike-down.
- Number 50.7 Loader/Unloader jam sensing conveyor

 protection stops the conveyor should a down

 coming tray strike a package not completely

ejected after the package has depressed the loader/unloader a pre-set distance senses incipient jamming - operates during strike-down.

Number 50.8 - Top overtravel - conveyor protection-prevents

packages passing through and jamming at the

top of the conveyor - senses incipient

jamming - operates during strike-up only.

Number 50.9 - Over-the-door-jam sensing - conveyor

protection - stops the conveyor if disturbed

by a misplaced package - most effective in

preventing package jamming between the tray

and the upper door coaming - senses

incipient jamming - operates during strike
up and strike-down.

Number 50.10 - Torque limiter - conveyor protection - set

to slip at 110 to 115% of total load
operates continuously - will prevent conveyor

and motor damage should all other devices fail.

The functional interrelationships between the safety devices are shown on Figure No. 6.

3.2.6 Sub-system Number 60 - Load/Unload Devices. Load/Unload devices are supplied to enable the operators to conveniently load and unload packages into and out of the conveyor. They may be positioned in one of three ways:

Load - horizontal to enable operators to place packages

on the fingers of the load/unload device. The

fingers of the tray pass between the fingers of the

load/unload device and pick up the package, carrying the package up. A safety interlock (Figure 6, 50.6) prevents strike-down operation when the load/unload device is in the "load" position. Usually simple wheel type conveying sections are hooked to the load/unload device so that packages may be rapidly on-loaded.

- Unload Tilted about 30 degrees from the horizontal.

 Packages carried by the trays strike the fingers

 of the load/unload device and slide out of the

 load area of the conveyor. Usually simple wheel

 type conveying sections are hooked to the load/unload

 device so that packages may be rapidly removed from

 the door opening.
- Stowed Vertical either up or down. When the load/unload device is in the stowed downward position, loads may be unloaded from that station during strike-up operation. At times it is preferable to stow the load/unload device in the upward position where it acts as a personnel guard. Stowing upward or downward is an option of the procuring activity.

The load/unload device incorporates two additional safety features:

One - The fingers of the load/unload device are spring

loaded and are capable of being depressed should a

downcoming tray strike and press against a package

inadvertently not removed from the package area. As

the fingers of the load/unload device depress a micro-switch is activated which immediately cuts off conveyor power.

Two - The load/unload device is arranged to "hinge" when the device is in the load or unload positions.

Thus, in the event packages strike the bottom of the load/unload device, the device will hinge upward and toward the door opening, out of the way of the upcoming package.

The functional interrelationship between the elements of the load/unload device is shown in Figure No. 7. These elements consist of:

Number 60.1	Platform
Number 60.2	Mtg. and Stowing Bracket R.H.
Number 60.3	Mtg. and Stowing Bracket L.H.
Number 60.4	Platform Depress Mechanism L.H.
Number 60.5	Platform Depress Mechanism R.H.
Number 60.6	Cross Shaft
Number 60.7	Interlock Microswitch
Number 60.8	Jam Sensing Microswitch

4. FMEA LIST

4.1 The list of items recommended for FMEA application is composed of all items listed in the following paragraphs:

Paragraph: 3.2.1

Paragraph: 3.2.2

Paragraph: 3.2.3

Paragraph: 3.2.4.1

Paragraph: 3.2.4.2

Paragraph: 3.2.4.3

Paragraph: 3.2.5

Paragraph 3.2.6

5. FMEA DEPTH

5.1 The FMEA analysis will be performed on each major assembly and sub-assembly of the functional systems identified in Paragraph 3.2, to the depth necessary to identify replaceable parts and components composing the assemblies and sub-assemblies.

6. FAILURE MODES

- Support Office (MSO) Material History Report, MSO No. 479052704.A07, Volumes 1 and 2. This data covered 10 manufacturers of vertical stores conveyors during the period between January 1, 1970 through April, 1972 (2-1/3 years). The data described failures which occurred on 132 vertical stores conveyors ranging in capacity from 85 to 4,000 pounds per tray. The Contractor's report provided a statistical interpretation of this data and included a "corrective action plan". The report titled, "Reliability Studies Including Corrective Action Plan for Vertical Package Conveyor" was submitted to NAVSEC August 10, 1972. To the Contractor's knowledge no more valid source of data identifying the failures occurring to parts and systems of vertical stores conveyors is anywhere else available.
- 6.2 The report identified above provides a valid statistical base for the selecting failure modes. The FMEA analysis, which will be performed as required by CDRL Item B001AH, will analyze each item, system, or sub-system, of paragraph 4.1 and will use the work sheet shown as Figure 2 of MIL-STD-1629 (Ships) as the

basic analysis tool. Failure modes for each of the items selected for analysis will be provided in the FMEA report.

7. CRITERIA FOR IDENTIFYING CRITICAL ITEMS

- 7.1 Criticality of the effect of item failure will be established using the techniques outlined in MIL-STD-1629 (Ships), paragraph 5.11 and 5.11.1.
- 7.1.1 Criticality is defined as the combination of probability of occurrence and the level of severity. A criticality matrix will be used as the means of identifying and comparing each failure mode to all other failure modes with respect to the ship's mission and the items functional output and maintenance.
- 7.1.1.1 Severity is classified as follows: (MIL-STD-1629 SHIPS, paragraph 5.9.1)
 - (a) <u>Level 1, Minor</u>. Characterized by any one or combinations of the following conditions:
 - (1) No effect on ship's mission capability.
 - (2) Negligible effect on functional output of the item at the initial indenture level.
 - (3) Other indenture level item degradation that can be repaired by performing "adjustment type" maintenance.
 - (b) <u>Level 2, Major</u>. Characterized by any one or combination of the following conditions:
 - (1) Negligible effect on ship's mission capability.
 - (2) Degradation in functional output of the item at the initial indenture level.
 - (3) Other indenture level item failure that can be repaired immediately within the capability

of organization level maintenance.

- (c) <u>Level 3, Critical</u>. Characterized by any one or combination of the following conditions:
 - (1) Some degradation in ship's mission capability.
 - (2) Severe reduction in functional output of the item at the initial indenture level.
 - (3) Other indenture level item failure that cannot be repaired immediately within the capability of organizational (shipboard) level maintenance.
- (d) <u>Level 4, Catastrophic</u>. Characterized by any one or combination of the following conditions:
 - (1) Severe reduction in ship's mission capability.
 - (2) Complete functional output loss of the item at the initial indenture level.
 - (3) Other indenture level item failure requiring tender or depot maintenance repair.

The level of severity selected shall be the highest level an item falls under, regardless of whether a lower classification is also applicable.

7.1.1.2 Failure probability shall be assessed in both quantitative and qualitative terms (MIL-STD-1629 [SHIPS], paragraphs 5.10, 5.10.1, 5.10.2, 5.10.2.1 and 5.10.2.2).

Failure Probability Level Guidlines

Qualitative. The following sample guidelines are suggested for developing definitions for failure probability levels in qualitative terms:

(a) Level 1 - Failure mode probability very low.
A negligible chance of occurrence during the item operating time interval.

- (b) Level 2 Failure mode probability low. An unlikely chance of occurrence during item operating time interval.
- (c) Level 3 Failure mode probability medium. A random fifty/fifty chance of occurrence during item operating time interval.
- (d) Level 4 Failure mode probability high. A likely chance of occurrence during the item operating time interval.

Quantitative. The following sample guidelines are suggested for developing definitions for failure probability levels in quantitative terms:

- (a) Level 1 Very low. Any single failure mode probability of occurrence which is less than 0.01 of the overall probability of failure during the item operating time interval.
- (b) Level 2 Low. Any single failure mode probability of occurrence which is more than 0.01 but less than 0.10 of the overall probability of failure during the item operating time interval.
- (c) Level 3 Medium. Any single failure mode probability of occurrence which is more than 0.10 but less than 0.20 of the overall probability of failure during the item operating time interval.
- (d) Level 4 High. Any single failure mode probability

of occurrence which is more than 0.20 of the overall probability of failure during the item operating time interval.

These recommended definitions shall be modified or expanded as necessary, depending on the system or equipment being analyzed and the amount of failure data available for the type of hardware involved.

8. FMEA ITEM SELECTION RATIONALE

- 8.1 The items selected for FMEA analysis were selected based on the following rationale:
 - (a) any item the failure of which would prevent conveyor operation,
 - (b) any item the failure of which would affect the operation of another system or sub-system. Example: failure of the loader/unloader microswitch jam sensing switch would not prevent or interfere with conveyor operation. However, should a jam occur, the microswitch would fail to operate and serious damage could result since motor current would continue until either
 - cut-off by the IOL,
 - cut-off by the thermal overload protection device.

 Failure of these systems to function would eventually force
 the torque limiter to slip,
 - (c) any item the failure of which should be repaired to continue efficient conveyor operation or to minimize the possibility of eventual damage or wear to other systems, sub-systems or components. Example: freeze-up of a guide arm cam follower. By itself this failure is not overly

detrimental, however, the frozen bearing would slide instead of roll along the track causing eventual wear to the track and bottom and top cam plates. Additional power would be required. If enough cam followers failed, wear would be rapid and power would exceed the limits of the IOL or thermal overload causing these devices to cut motor current.

9. ANALYSIS

The following sub-system analyses will cover only those failures which result in a frequency or severity level of three or four. In each case the recommended corrective action, effect on personnel safety and a discussion of the actual probability of failure, during an average operating cycle of 5,000 hours between overhauls will be provided. Each failure mode at the three and four levels will be separately discussed.

9.1 Analysis of Drive System - Refer to Figures 8 and 8(a) and the FMEA working papers regarding the Drive System.

9.1.1 Motor (10.2)

9.1.1.1 Failure Mode 10.2.01 - No RPM - This failure is generally caused by failure of the motor windings.

The probability factor is extremely low, however, failure of the motor winding will cause the conveyor to be completely inoperative. There is no significant personnel safety hazard connected with failure of the motor. Corrective action is limited to replacing the motor or removing the motor and repairing the windings.

en indominationaliseera, de Catalanda, elemento de Maleira Machine en Comban

9.1.1.2 Failure Mode 10.2.04 - Runs Rough. This failure is

generally caused by bad bearings. If allowed to continue the armature will eventually bind and fail the motor, causing loss of conveyor operation. No personnel safety hazard is involved and the actual probability of occurrence is extremely low. Corrective action is to remove and repair the motor immediately upon noting the condition.

9.1.1.3 Failure Mode 10.2.05 - On-Off Operation. This type of failure can be caused by partially shorted windings or by bad bearings which allow the armature to bind intermittently. Probability of failure is extremely low - no particular personnel safety hazard involved. Corrective action is limited to replacing the motor or removing the motor for repair.

9.1.2 Reducer (10.4)

- 9.1.2.1 Failure Mode 10.4.01 No RPM. This failure mode can be the result of a broken worm gear, stripped worm or gear teeth, failed or frozen bearings, broken input shaft, broken or sheared keys, etc. These failures are mechanical and will result in conveyor stoppage. There is some personnel hazard involved if the non-overhauling properties of the Reducer are jeopardized. With proper lubrication and adequate inspection, the probability of this type of failure is low. Corrective action consists of removing and repairing the Reducer.
- 9.1.2.2 Failure Mode 10.4.04 Load Trays Tilt Drive Chains
 Out of Synchronization. This type of failure, wherein

the load trays cock significantly increases the chance of tray jamming as the trays transition through the tail and head cam plates. With the single side control principle embodied in the new conveyor design, the probability of this type of failure has been significantly reduced due to the forgiving nature of the new design. However, tray cocking must be corrected whenever noted or a jam will eventually occur which, in addition to causing loss of conveyor operation, may do substantial damage to the cam plates, the track, package shields, trays and tray mounting devices. Little or no personnel hazard. Corrective action should be taken immediately and will usually consist of reworking keyways and replacing keys.

- 9.1.2.3 Failure Mode 10.4.02 Runs Rough Runs Noisy.

 This type of failure must be corrected when noted by replacing the bad bearings. If allowed to continue the bearing could fail resulting in damage to the Reducer Worm Gear and/or the Reducer Ring Gear; failure of the Reducer will cause loss of conveyor operation. Probability of failure is low but is enhanced by negligent maintenance practices. Little or no safety hazard to personnel except for possible loss of the non-overhauling feature of the Reducer.
- 9.1.2.4 <u>Failure Mode 10.4.03 Reducer Runs Hot May Be</u>

 Noisy Input Shaft Hard to Turn. These symptoms

 indicate that the Reducer lubricant has been lost, is

contaminated, has been improperly applied, etc.

Damage may be significant when noted. The Reducer should be removed, opened, and checked for worm and gear wear, for bearing wear, for adequate seals. No personnel safety hazard unless ignored. This type of failure is preventable by good periodic maintenance and adequate inspection. The Contractor has noted instances of total Reducer neglect, which, unless disciplined, will lead to loss of conveyor operation and expensive Reducer damage.

9.1.3 <u>Coupling (10.6)</u>

- 9.1.3.1 Failure Mode 10.6.02 Torsional Stress Failure.

 This type of failure is extremely remote unless the coupling material is seriously defective. Failure will result if tray cocking with associated incipient jams at the head or tail cam plates and incipient damage to conveyor parts and loss of conveyor operation.

 Little or no personnel hazard involved. Condition must be corrected immediately by coupling replacement.
- 9.1.3.2 Failure Mode 10.6.03 Stress Failure of Key (s).

 The key stress is very low under full jam conditions which indicates that this type of failure is very remote. The same conditions apply as in paragraph 9.1.3.1. Immediate corrective action is necessary requiring replacement of the sheared or damaged keys.

 Careful inspection of the coupling and shaft keyways is necessary to assure that the replacement key will fit correctly.

9.1.3.3 Failure Mode 10.6.01 - Worn or Distorted Keys
and/or Keyways. This type of failure usually
preceeds failure mode 10.6.03 discussed in
paragraph 9.1.3.2. Once wear is noted the key (s)
should be replaced immediately and the keyways
inspected for possible damage. As stated in the
preceding paragraphs, worn or defective keys and/or
keyway may allow the trays to cock increasing the
propensity for tray jams as the trays translate
through the cam plates.

9.1.4 Jack Shaft (10.7)

9.1.4.1 Failure Mode 10.7.02 - Torsional Stress Failure. This failure mode is highly improbable unless the jack shaft material is seriously defective. Should a jack shaft fail the results will depend on whether the Reducer is a double or single shaft output type. In the case of a double shaft output Reducer, failure of a jack shaft will cause loss of tray control on the failed side. Jamming will occur with associated damage and loss of conveyor operation. In the case of a single shaft output Reducer, failure of the jack shaft will cause total loss of conveyor operation. If loads are on the conveyor trays the conveyor will backtravel and jam. Hazard to personnel limited under most conditions however, the non-overhauling properties of the Reducer as well as the brake stopping torque will be ineffective and there would be no way to apply torque to the lifting chains until the failed shaft is replaced.

- 9.1.4.2 Failure Mode 10.7.03 Coupling or Sprocket Key

 Stress Failure. Failure mode highly improbable since
 the keys are under low stress during jam conditions.

 Failure results are identical to those described
 under Failure Mode 10.7.02 (paragraph 9.1.4.1)
- 9.1.4.3 Failure Mode 10.7.01 Worn or Distorted Keyways

 and/or Keys at Coupling and/or Sprockets. Worn or

 distorted keys and/or keyways may allow trays to

 cock with increased propensity to jam as the tray

 transition through the cam plates. This type of

 failure is highly improbable due to the low key

 stress. No particular hazard to personnel. Worn

 or distorted keys and/or keyway can be detected by

 inspection and must be repaired when noted.

9.1.5 Bearing (10.8)

9.1.5.1 Failure Mode 10.8.01 - Frozen Bearing. This type of failure is highly improbable since the pillow block bearings have been sized generously and since inspection and periodic maintenance procedures should detect and prevent occurrence. Failure will result in the loss of conveyor operation and will be immediately detectible. The motor is protected by the IOL and the thermal overload device. No personnel hazard since the conveyor will not move.

Usual cause is corrosion contamination caused by negligent periodic maintenance. Bearing must be replaced - bearing repair is not recommended.

9.1.6 Drive Sprocket (10.9)

- 9.1.6.1 Failure Mode 10.9.02 Sprocket Key Stress Failure.

 Failure highly improbable because of the low stress in the key. Should a key fail the results will be identical to those described under Coupling Failures (paragraphs 9.1.3.1, 9.1.3.2 and 9.1.3.3) and Jack Shaft Failures (paragraphs 9.1.4.1, 9.1.4.2 and 9.1.4.3).
- 9.1.6.2 Failure Mode 10.9.01 Worn or Distorted Keyways

 and/or Keys at Sprockets. This type of failure

 produces the same results as that described under

 Jack Shaft's Failure Mode 10.7.01 (paragraph 9.1.4.3).

9.1.7 Drive Chain (10.10)

- 9.1.7.1 Failure Mode 10.10.01 Stretched or Distorted Chain.

 Stretched chain can cause cocking of the carrier trays increasing the propensity of the trays to jam at the head and tail cam plates. This condition has been previously discussed. The chains operate at a factor of safety of not less than 10 to one, reducing the probability of this type of failure significantly. Stretched chain, when detected by inspection, should be replaced immediately. No particular personnel hazard.
- 9.2 Analysis of Conveyor Structure Refer to Figures 9 and 9 (a)
 and the FMEA Working Paper Regarding the Conveyor Structure
 9.2.1 Trunk (20.1)
 - 9.2.1.1 (a) It is possible to introduce stresses into the trunk at installation if installation procedures are not followed by the installation mechanics.

The base plate, usually furnished by the shipbuilders must be flat and square across corners. W. Jing must be done carefully to minimize the effects of weld shrinkage at the deck openings. There are no Level Three or Four catagories to consider.

- (b) The Contractor is recommending that the trunk be welded to the deck collar using a "Z" configured filler weld plate to achieve flexibility. This design avoids the problem of weld shrinkage and minimizes shear loads at the deck openings.
- 9.3 Analysis of Operating System Refer to Figures 10 and 10 (a) and the FMEA Working Papers Regarding the Operating System.

9.3.1 <u>Head Cam Plate (30.1)</u>

9.3.1.1 Failure Mode 30.1.02 - Tracks Broken. Jamming at the head cam plate historically has occurred as a result of tray cocking caused by worn keys, keyways, improper tensioning of the drive chains and packages left on trays. This cam plate design controls the tray transition from vertical to horizontal or horizontal to vertical from one side of cam plate -- never is control on both sides simultaneously as in previous designs. This results in a much more forgiving design capable of tolerating significant amounts of tray cocking without jamming. Thus the propensity for jamming at the head cam plate is greatly reduced.

Broken tracks will cause jams and should be repaired immediately. Should a jam occur at the head cam plate, both left and right cam plates must be

inspected and damage repaired before continuing operation. Personnel hazard is slight but resultant damage to trays and tray mounting devices could be extensive.

9.3.2 Head Shaft (30.2)

- 9.3.2.1 Failure Mode 30.2.02 Torsional Stress Failure.

 The torsional stresses in the head shaft are well within design limits even under the worst jam conditions. Therefore, the probability of torsional failure is remote unless the material is faulty. A complete separation would dump all loads with associated resultant damage and possibility of loads striking operating personnel -- a head shaft separation has never been experienced.

 Proper inspection and checking all reasons for tray cocking should reveal incipient failure and the stressed shaft replaced.
- 9.3.2.2 Failure Mode 30.2.03 Sprocket Key Stress Failure.

 Complete stress failure of the driven sprocket or carrier sprocket keys will allow the failed side to spin free creating tray cocking and imposing stresses on the holding side. Jams will occur at the head and tail cam plates. The key stresses are low; therefore, the probability of failure is remote.

 Personnel hazard is minimal. A completely failed key is immediately detectible and must be replaced.
- 9.3.2.3 Failure Mode 30.2.01 Worn or Distorted Keyways or

 Keys at the Driven Sprocket. This type of failure
 results in tray cocking with associated possibility

of jamming at the head and tail cam plates. Disciplined inspection to detect worn or distorted keys or keyways will enable replacement before cocking becomes intolerable for the cam plates to handle. Hazard to personnel is minimal. This condition results from repeated pounding of the keys and keyways usually caused by jams. Since the conveyor is protected against jams by a variety of safety devices (see Safety Devices No. 50) the possibility of jams has been significantly reduced.

9.3.3 Head Shaft Bearing (30.3)

9.3.3.1 Failure Mode 30.3.01 - Frozen Bearings. Failure results in loss of conveyor operation. Primary cause is corrosion contamination. Proper maintenance will do much to preclude failure occurring. No personnel hazard. Failed bearing must be removed and replaced.

9.3.4 Head Shaft Bearing Housing (30.4)

9.3.4.1 Failure Mode 30.4.01 - Housing Cracked or Broken

Failure can cause bearing to seize, stopping conveyor operation. Probability extremely remote and has never been experienced by Contractor. Minimal personnel hazard. Depending on type, location and severity of cracks or breaks, trays can cock with associated danger of jamming. Minor cracks are difficult to detect unless associated with symptoms noted herein. Faulty housing must be replaced.

9.3.5 Head Shaft Sprocket (30.5)

9.3.5.1 Failure Mode 30.5.02 - Sprocket Key Stress Failure

Same as Failure Mode 30.2.03 (see paragraph 9.3.2.2).

9.3.6 Carrier Chain (30.6)

9.3.6.1 Failure Mode 30.6.01 - Stretched or Distorted Carrier Chain. The new conveyor design is equipped with a chain tensioning device which pre-sets chain tension to a value selected to match the load capacity of the conveyor. In addition the factor of safety of the chain ranges from a low of 14 to one for the longest conveyor to 99 to one for the shortest conveyor. Accordingly, chain stretch is almost eliminated as a problem. Chain distortion or chain stretch could happen if one side of the system became disengaged as with a head shaft separation; or, should a bolt, nut, or other foreign material force the chain out of it's normal sprocket engagement. Most frequent symptom would be tray cocking, which if noted, should be checked immediately and corrective action taken. (Note - other causes of tray cocking have been noted and discussed in this Analysis Section).

9.3.7 Carrier Link (30.7)

9.3.7.1 Failure Mode 30.7.01 - Stretched or Distorted Link.

The probability of this type of failure occurring is extremely remote due to the low stresses in the chain link under the most severe jam conditions. Failure would visualize as a cocked tray. Corrective action would be to replace the offending link; personnel hazard is minimal.

9.3.8 Chain Pin (30.8)

9.3.8.1 Failure Mode 30.8.01 - Disengagement of Chain Pin.

Paragraph 9.3.6.1 identifies the factor of safety applicable to the chain. The chain pin has been designed to keep stresses low in concert with the chain factor of safety. However, chain pins can disengage if not properly installed. This is a human factor and therefore, probability is impossible to determine. Should a chain pin totally disengage, the chain would separate, dropping all loads. Damage could be extensive; personnel could be struck by loads tumbling through doors. Checking chain pin engagement during periodic inspection and maintenance assures that this type of failure is avoided.

9.3.9 Carrier Shaft (30.9)

9.3.9.1 Failure Mode 30.9.01 - Excessive Torsional Stress

Causing Shaft to be Bent or Broken. The combined torsional and bending stresses in the carrier shaft are within allowable limits under the worst jam conditions. Probability of torsional failure is low. Should failure occur, the trays would twist, exposing the conveyor to jams at the head and tail cam plates. Hazard to personnel is low; however, damage may be extensive to trays and tracks.

9.3.10 Guide Arm (30.10)

9.3.10.1 Failure Mode 30.10.01 - Key Shear Limit Exceeded.

The key shear stress is low; therefore, the probability of this type of failure occurring is remote. Should the key fail the tray would be stabilized by the opposite side. However, during transition through

the cam plates control of tray movement is passed from one side to the other and jams are likely.

A sheared key can occur only during jam. When clearing a jam, the keys must be inspected and replaced if damaged. No hazard to personnel.

9.3.11 Guide Arm Cap (30.11)

9.3.11.1 Failure Mode 30.11.01 - Cap Shear Limit Exceeded.

This type of failure will produce identical results to those identified under Failure Mode 30.10.01 (paragraph 9.3.10.1). Inspection of guide arm keys and caps after severe jam, i.e. fully loaded conveyor in strike-down operation is mandatory.

9.3.12 Front Track (30.15)

9.3.12.1 Failure Mode 30.15.02 - Tracks Broken. The front track will be treated as the track guiding the center-line mounted flanged cam follower; the rear track will be treated as the tray guiding the 45 degree arm mounted roller. Calculations show that the tray will pivot at the jam point under the force exerted by the chain pull. The worst possible jam condition will be a jam at a lower door coaming with a fully-loaded conveyor of 40 total trays, 20 loaded to 100 pounds each. Under these conditions, there is little or no load on the "front track". The resisting moment is provided by the 45 degree guide arm acting on the "rear track". The highest stress occurs therefore, in the single section "rear track". This stress exceeds the allowable stress of extruded

aluminum by 16 percent (allowable stress 70 percent of tensile yield). However, the tensile yield is not exceeded and the design is safe and should not break or deform under the worst jam conditions. A minor design modification will bring the design into the "allowable stress range". Broken or deformed track must be replaced when noted. Broken or deformed track presents no personnel hazard but may lead to interrupted conveyor operation and serious damage should a guide roller escape track confinement.

9.3.13 Rear Track (30.16)

9.3.13.1 Failure Mode 30.16.02 - Tracks Broken. The analysis of paragraph 9.3.12.1 applies to this failure mode.

9.3.14 Tail Cam Plate (30.17)

9.3.14.1 Failure Mode 30.17.02 - Cam Tracks Broken. The analysis of paragraph 9.3.1.1 applies to this failure mode.

9.3.15 Tail Shaft Bearings (30.19)

9.3.15.1 Failure Mode 30.19.01 - Frozen Bearings. The analysis of paragraph 9.3.3.1 applies to this failure mode.

9.3.16 Head Driven Sprocket (30.21)

- 9.3.16.1 Failure Mode 30.21.02 Sprocket Key Stress Failure.

 The analysis of paragraph 9.3.2.2 applies to this failure mode.
- 9.3.16.2 Failure Mode 30.21.01 Worn or Distorted Keyways and/or

 Keys at Sprockets. The analysis of paragraph 9.3.2.3

 applies to this failure mode.

9.4 Analysis of Control System - Refer to Figures 11 and 11 (a) and the FMEA Working Papers Regarding the Control System

9.4.1 Thermal Overload (40.1.2)

9.4.1.1 Failure Mode 40.1.2.1 - One or More Heater Elements Inoperative. In a three-phase circuit a thermal overload heater coil is inserted in each phase. One of the phases contains the current sensing coil for the instantaneous overload device. If a thermal overload heater coil fails in a phase not containing the IOL, the IOL will sense the increase in current and shut off power to the motor windings. If the thermal overload heater coil fails in the phase containing the IOL sensing coil, the IOL coil will not sense the increased current draw and the motor windings will overheat and eventually burn. The failure visualizes as refusal of the motor to start. Loss of a thermal overload heater coil means the conveyor will not run. Because of the damage which may occur if the operator continues to apply current to the motor under the conditions outlined above, the contractor recommends immediate corrective action should the motor not start when the circuit is energized. The contractor has not experienced a starter coil failure, therefore must conclude that the probability of failure is low. No personnel safety hazard invisioned even though failure could occur while operating with a fully-loaded conveyor since the non-overhauling properties of the Redr er will prevent run-away loads.

9.4.2 Instantaneous Overload (40.1.3)

9.4.2.1 Failure Mode 40.1.3.1 - Burned or Interrupted Coil.

The relationship of the thermal overload heater coils to the instantaneous overload sensing coil is described in paragraph 9.4.1.1. Should the IOL sensing coil fail, the motor will single phase causing increased current draw to heat and activate the thermal overload.

Conveyor operation is lost until the IOL coil is replaced. No personnel hazard -- probability of failure low -- the contractor has not experienced a loss of a properly sized IOL coil.

9.4.3 Instantaneous Overload By-pass Timer (40.1.4)

- 9.4.3.1 Failure Mode 40.1.4.1 Burned or Interrupted Coil.

 This type of failure prevents motor operation because the initial surge of current at motor start will be sensed by the IOL sensing coil which will trip the IOL and de-activate the circuit. Conveyor may be operated using the Emergency Run Switch. Normal continuous conveyor operation is lost until the IOL coil is replaced. Probability of failure is low with a properly sized coil -- no personnel safety hazard.
- 9.4.3.2 Failure Mode 40.1.4.2 Cracked or Broken Bellows.

 This type of failure has the same effect as Failure Mode 40.1.4.1 (paragraph 9.4.3.1). Essentially the IOL has no by-pass and, therefore, the IOL prevents motor operation. Conveyor operation is lost until the failure is repaired. No personnel safety involved.
- 9.4.3.3 Failure Mode 40.1.4.3 Air Hole in Bellows Plugged.

This type of failure allows the IOL to by-pass current continuously effectively eliminating the IOL as a safety device. This failure is difficult to diagnose since the conveyor operates normally. However, should a jam occur or other circumstances arise which causes current surge, the IOL being inoperative, will not function and will allow current to continue to the motor with potential damage to the conveyor beyond that which would have occurred had the IOL been operative. Probability of this type of failure is low. No unusual personnel safety hazard.

9.4.4 Over-the-door Jam Sensing Relay (40.1.9)

9.4.4.1 Failure Mode 40.1.9.1 - Burned or Shorted Coil.

De-activation of the over-the-door jam sensing relay prevents activation of the intermediate stations.

The conveyor cannot be run except through the Emergency Run circuit until the relay is replaced. Low failure probability. No personnel hazard. (See para. 11.3)

9.4.5 Load/Unload Jam Sensing Relay (40.1.10)

9.4.5.1 Failure Mode 40.1.10.1 - Burned or Shorted Coil.

De-activation of the load/unload jam sensing relay

de-activates the "down" circuit. Conveyor will run in

the strike-up mode only. Probability of failure low.

No personnel hazard.

9.4.6 Power "On-Off" Selector Switch (40.2.1)

9.4.6.1 Failure Mode 40.2.1.1 - Burned or Worn Contacts.

Failure cf the selector switch to make contact results in no power to the control circuit. Conveyor does not

run until the switch is replaced -- the emergency circuit is also inactive. Low probability - easy to diagnose - no personnel safety hazard.

9.4.7 Three-position Speed Selector Switch (40.2.2)

9.4.7.1 Failure Mode 40.2.2.3 - Burned or Worn Contacts in all Positions. Failure of the three-position switch to make contact in all positions results in no power to the motor -- conveyor does not run in normal or emergency run modes, until failure is corrected. No personnel safety hazard -- low probability of all three positions failing at same time.

9.4.8 "Stop - Push, On - Pull" Switch (40.3.2)

- 9.4.8.1 Failure Mode 40.3.2.1 Burned or Worn Contacts.

 With this type of failure contact is not made when the switch is set in the "On Pull" position. The conveyor will not run when the UP or DOWN push buttons are activated at any station until the failure is diagnosed and corrected. No safety hazard to personnel and very low probability of failure.
- 9.4.8.2 Failure Mode 40.3.2.2 Contacts Welded Together. This is a more serious failure than Failure Mode 40.3.2.1 and results in continued conveyor operation when the switch is pushed to the STOP position. If allowed to run, the conveyor may jam with associated mechanical damage. The conveyor can be stopped by interrupting the circuit by utilizing the over-the-door jam sensing device or by turning off power at the Controller. Potential safety hazard if operator is surprized by the lack of

conveyor response when "Push - Pull" switch depressed to STOP position and conveyor continues to run -- may cause operator to lose control of load in strike-up mode of conveyor operation. Probability of failure is low. Failure is immediately evident. "Push - Pull" switch should be replaced before operation is continued in spite of the fact that operation can be controlled by utilizing locally handy over-the-door safety device.

9.4.9 Up - Push Button (40.3.3)

- 9.4.9.1 Failure Mode 40.3.3.1 Burned or Worn Contacts.

 Circuit will not be energized when the Up Push button is pressed in the UP direction. Conveyor operation limited to down direction only. Failure immediately evident. Failed switch must be replaced to operate in UP direction at the subject station. Little or no personnel hazard -- probability of failure low.
- 9.4.9.2 Failure Mode 40.3.3.2 Contacts Welded Together.

 With this type of failure the conveyor will operate immediately when the control circuit is energized.

 May surprize operator and represents a serious failure which must be corrected immediately upon noting.

 Conveyor can be stopped by depressing "Push Pull" switch or by utilizing the locally handy over-the-door jam sensing safety device. Probability of failure is low.

9.4.10 Down - Push Button (40.3.4)

9.4.10.1 Failure Mode 40.3.4.1 - Burned or Worn Contacts.

Same type of failure as described under Failure Mode

- 40.3.3.1 (see paragraph 9.4.9.1).
- 9.4.10.2 <u>Failure Mode 40.3.4.2 Contacts Welded Together</u>.

 Same type of failure as described under Failure

 Mode 40.3.3.2 (see paragraph 9.4.9.2).
- 9.5 Analysis of Safety Devices Refer to Figures 12 and 12 (a) and the FMEA Working Papers Regarding the Safety Devices.
 - 9.5.1 Bottom Overtravel Limit Switch (50.5)
 - 9.5.1.1 Failure Mode 50.5.01 Bottom Overtravel Limit

 Switch Locked Open. Failure in this mode means that
 the conveyor is inoperative in the down direction.

 Switch must be replaced. This type of failure is
 usually mechanical in nature and rare among commercial
 micro-switches. No hazard to personnel.
 - 9.5.2 Failure Mode 50.6.01 Loader/Unloader Interlock Switch is

 Locked Open. Identical to Failure Mode 50.5.01 (see para. 9.5.1.1).
 - 9.5.3 Failure Mode 50.7.01 Loader/Unloader Jam Sensing Switch is

 Locked Open. Identical to Failure Mode 50.5.01 (see paragraph 9.5.1.1).
 - 9.5.4 Failure Mode 50.8.01 Top Overtravel Switch Locked Open.

 Failure in this mode means that the conveyor is inoperative in the up direction. Switch must be replaced. This type of failure is usually mechanical in nature and rare among commercial micro-switches. No hazard to personnel.
 - 9.5.5 Failure Mode 50.9.01 Over-the-door Jam Sensing Switch Locked

 Open. This type of failure means that the conveyor is inoperative in both up and down directions. The failed switch must be located and replaced. This type of failure is usually mechanical in nature and rare among commercial micro-switches.

 No hazard to personnel.

- 9.6 Analysis of Load/Unload Device Refer to Figures 13 and 13 (a) and to the FMEA Working Papers Regarding the Load/Unload Device
 9.6.1 Mounting and Stowing Bracket R.H. (60.3).
 - 9.6.1.1 Failure Mode 60.2.01 Bent Bracket. Bent or distorted mounting brackets may make it difficult or impossible to place the load/unloader in the load, unload or stowed positions. Inability to seat the load/unloader in the unload or stowed positions properly will not allow the down circuitry to be completed, resulting in loss of conveyor operation in the down direction. Inability to seat the load/unloader in the load position properly may allow the down direction circuitry to remain completed allowing strikedown operation normally prevented by the load/ unloader interlock switches. These failures are easily detectible allowing immediate corrective action. Probability is low -- personnel hazard is minimal.
 - 9.6.2 Mounting and Stowing Bracket L.H. (60.4)
 - 9.6.2.1 Failure Mode 60.3.01 Bent Bracket. This failure mode is identical to Failure Mode 60.2.01 (see paragraph 9.6.1.1).
 - 9.6.3 Platform Depress Mechanism L.H. (60.4)
 - 9.6.3.1 Failure Mode 60.4.01 Binding of Guide Shaft in

 Guide Plate Slide. If the guide shaft binds in

 the guide plate slide, the platform will not depress
 in the event of a jam. Protection against strike-

down jam is lost at the subject station. Also, binding will make it impossible to position the load/unload device from the load position to the unload position, or, from the unload position to the load position dependant on which position the load/unload device was in when the binding occurred. Failure is easily detectible and must be corrected when noted. Failure probability is low. Personnel hazard minimal.

- 9.6.3.2 Failure Mode 60.4.02 Binding in the Guide

 Plate Slide. This type of failure produces

 identical results as Failure Mode 60.4.01 (see

 paragraph 9.6.3.1).
- Arms. If the pins work out of the connecting arms, the loader/unloader spring tension will be lost, making it impossible to position the load/ unloader in the unload position. Conveyor operation in the down position will be lost. Failure is easily detectible and must be corrected immediately. Probability is low -- minimal personnel hazard.

9.6.3.4 Failure Mode 60.4.06 - Broken Spring. Failure of the load/unloader spring will make it impossible to place the load/unloader in the unload position resulting in loss of downward conveyor operation.

Failure is easily detectible and must be corrected immediately. Probability is low. Personnel hazard is minimal.

9.6.4 Platform Depress Mechanism R.H. (60.5)

- 9.6.4.1 Failure Mode 60.5.01 Binding of Guide Shaft

 in Guide Plate Slide. Failure identical to Failure

 Mode 60.4.01 (see paragraph 9.6.3.1).
- 9.6.4.2 <u>Failure Mode 60.5.02 Binding in Guide Plate Slide.</u>

 Failure is identical to Failure Mode 60.4.02

 (see paragraph 9.6.3.2).
- 9.6.4.3 <u>Failure Mode 60.5.03 Pins Work Out of Connecting</u>

 <u>Arms. Failure is identical to Failure Mode 60.4.03</u>

 (see paragraph 9.6.3.3).
- 9.6.4.4 <u>Failure Mode 60.5.06 Broken Spring</u>. Failure is identical to Failure Mode 60.4.06 (see paragraph 9.6.3.4).

9.6.5 Cross Shaft (60.6)

9.6.5.1 Failure Mode 60.6.01 - Loose Coupling. Loose couplings would make it difficult or impossible to position the loader/unloader in the unload position.

Conveyor operation in the strike-down mode would be lost. Loader/unloader may cock or tilt. Failure easily detectible and must be corrected when noted. Probability is low -- minimal personnel hazard.

Indenture Level No. 1	VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2	Drive System
Indenture Level No. 3	Motor
ndenture Level No. 4	Commercial Part

Output specification	Failure Mode			Symptoms-	Effect of Failure			
functional description	SN	Description	Possible causes	detectability Local Effect		End Effect	End Effect	
10.2 Motor (1800, 1200 & 900 RPM)	10.2.01	No RPM	Burned Winding	s High Current	Current Interrupt	Conveyor Inoperative		
			Insulation Breakdown	High Current	Current Interrupt	Conveyor Inoperative		
			Bearing Failure	High Current	Current Interrupt	Conveyor Inoperative		
Powers Conveyor and allows a selection of 3-speeds; 8, 10.7 and 16 trays perminute		Will not run at 1200 RPM	1200 RPM Winding Burned Out	Speed Selectio Limited to 1800 and 900	n Same as Symptom	Conveyor Operation Limited to 16 and 8 trays per minute		
	10.2.03	Will not run at 1800 and 900 RPM	1800 and 900 RPM Windings Burned Out	Speed selection limited to 1200 RPM	ı Same as Symptom	Conveyor Operation limited to 10.7 trays per minute		
	10.2.04	Runs Rough	Bad Bearings(s	Vibration	Vibration Indicating Eminent Bearing Failure - Temperature Rise	Eminent Loss of Conveyor Operation		
					Eminent Bearing Failure - Temperature	Conveyor		

Contract No.	N00024-72-C-5500
Organization	KORNYLAK CORPORATION
	GINEERING DEPT., KURNYLAK CORP.

APPROVED: _ DATE: Effect of Failure Existina Level Failure Symptomscompensating of Remarks and Recommendations probdetectability **Local Effect End Effect** provision Severity ability ndings High Current Current Conveyor None 4 1 Protected by IOL and Fuses Interrupt Inoperative High Current Current Conveyor None 4 1 Protected by IOL and Fuses Interrupt Inoperative High Current Current Conveyor 4 None Protected by IOL and Fuses 1 Interrupt Inoperative Speed Selection Same as Conveyor None 1 1 Protected by IOL and Fuses urned Limited to Symptom Operation 1800 and 900 Limited to 16 and 8 trays per minute

900 Speed selection Same as Conveyor 2 None 1 Protected by IOL and Fuses ngs limited to Symptom Operation 1200 RPM limited to 10.7 trays per minute ngs(s|Vibration Vibration Eminent None 3 1 Thermal Overload Indicating Loss of Eminent Conveyor Bearing Operation Failure -Temperature Rise

Page - 42 -

Indenture Level No. 1 <u>VERTICAL CONVEYOR SYSTEM</u>
Indenture Level No. 2 <u>Drive System</u>
Indenture Level No. 3 <u>Motor (Page -2-)</u>

Indenture Level No. 4
Drawing
One Commercial Part

		Failure Mode			Effect of	En	
Output specification functional description			Possible causes	Symptoms- detectability			comp
	SN	Description		detectability	Local Effect	End Effect	pr
10.2 Motor	10.2.05	On - Off Operation	Partially Shorted Windings	Motor Shuts Down - High Current	Temperature Rise	Intermitten Conveyor Operation	-
			Bad Bearing	Motor Shuts Down - High Current	Temperature Rise	Intermitten Conveyor Operation	No

Contract No. N00024-72-C-5500
Organization KORNYLAK CORPORATION
By ENGINEERING DEPT., KORNYLAK CORP.

APPROVED:	 DATE:	

D C	detectability Motor Shuts Down - High Current Motor Shuts Down - High	Rise	End Effect Intermitten Conveyor Operation	compensating provision None	of Severity 3	prob- ability 1	Remarks and Recommendations Protected by IOL and Thermal Overload
D C	Down - High Current Motor Shuts	Rise	Conveyor	None	3	1	
D D		Temperature					
	Current	Rise	Intermitten Conveyor Operation	None	3	1	Protected by IOL and Thermal Overload
							Page - 43 -

Form No 216 6

Indenture Level No. 1	VERTICAL CONVEYOR SYSTEM Drive System
Indenture Level No. 2	Drive System
	Torque Limiter
indenture Level No. 4	•
	Commercial Part

Output specification	Failure Mode SN Description			Symptoms-	Effect of		
functional description			Pussible causes	detectability	Local Effect	End Effect	ce
10.3 Torque Limiter	10.3.01	Friction Disc worn, glazed fractured	- Improper adjustment -overheating -system overloaded	Conveyor does not react full speed	Motor connection to system slips	Drive syster is sluggish	
-The Torque Limiter provides conveyor protection -Is set at 110%	10.3.02	Bellwood spring is defective	-weak spring -corroded spring	Torque Limiter will not Cransmit load	Motor connection to system slips	Drive system is sluggish	Se a management and place
to 115% of total load -It operates continuously -Prevents conveyor and	10.3.03	Bearing failure	-fractured raceway -broken or missing roller	Torque Limiter connection runs rough	Same as end effect	Drive system vibrates	e programme and supplied to the second
	10.3.04	Pressure nut loosens	-improper adjustment -set screws not locked tight	Conveyor does not reach full speed	Moto: connection to system slips	Drive system sluggis ¹	1 cghti
	10.3.05	Key failure	Adjustment set to tight System over- loaded	Conveyor will not run	Same as end effect	Conveyor inoperative	er et state en en en en en en en en en en en en en
							A Seesing 1985

ont	ract No.	N00024-72	2-C-5500		
) r g a	nization	KORNYLAN	CORPOR	RATION	
By	EN	GINEERING	DEPT.,	KORNYLAI	CORP.

						APPRO	VED: DATE:
	Symptoms-	Effect of Failure		Existing compensating	Level	Failure prob-	Remarks and Recommendations
	detectability	Local Effect	End Effect	provisien	Severity	ability	Lights and Licentifications
ng	Conveyor dues not reach full speed	Motor connection to system slips	Prive syster is sluggish	ı None	1	2	Disassemble Torque Limiter Replace friction disc (s) in Torque Limiter. Adjust per instruction in manual.
ng	Torque Limiter will not transmit load	Motor connection to system slips	Drive system is sluggish		1	2	Disassemble Torque Limiter Replace Bellwood spring Adjust per instruction in manual
ller	Torque Limiter connection runs rough	Same as end effest	Drive system vibrates	Kone	2	î	Disassemble Torque Limiter Replace faulty bearing Adjust per instruction in manual
3,	Conveyor does not reach full speed	Notor connection to system slips	Drive system sluggish	Tighten pressure nut	1	1	Adjust Torque Limiter in accordance with instructions in manual
set	Conveyor will not run	Same as end cffect	Conveyo: inoperative	None	2	1	Remove Torque Limiter Rework Keways - replace key (s

Page - 44-

Indenture Level No. 1 Indenture Level No. 2	VERTICAL CONVEYOR SYSTEM Drive System
	Reducer
Indenture Level No. 4	
n	Commercial Park

Output specification	Failure Mode		D	Symptoms-	Effect	of Failure	Exi
functional description	SN	Description	Possible causes	detectability	Local Effect	End Effect	com pe pr o v
10.4 Reducer Reduces speed from 1800, 1200 and 900 RPM to 36, 24 and 18 RPM. Reducer is non-overhaul- ing to prevent reverse conveyor operation under load.	10.4.01	No output RPM	-broken worm -stripped worm teeth -broken gear -stripped gear teeth -failed or frozen bearing -broken in-put shaft -broken in-put shaft key		Same	Conveyor inoperative	Nor
	10.4.02	Runs rough - runs noisy	Bad bearing	Vibration, noise	Incipient loss of reducer	Incipient loss of conveyor operation	Not
	10.4.03	Reducer runs hot - may be noisy - in-put shaft hard to turn	Loss or deterioration of lubricants -bad seals -cracked housing -no make-up lubricant added -wrong make-up lubricant added	-runs hot -visible evi- dence of lubricant on base plate -high motor current	Incipient loss of reducer	Incipient loss of conveyor operation	No
							2

Contract No. NOO024-72-C-5500
Organization KORNYLAK CORPORATION
By ENGINEERING DEPT., KORNYLAK CORP.

APPROVED:	 DATE:	

detectability	Local Effect	Effect of Failure		Level of	Failure prob-	Remarks and Recommendations
	Local Ellect	End Effect	compensating provision	Severity	ability	nenjarks and necommendations
o output RPM	Same	Conveyor inoperative	None	4	1	Replace Reducer
ibration, oise	Incipient loss of reducer	Incipient loss of conveyor operation	None	3	1	Replace bearing
runs hot visible evi- ence of ubricant on ase plate high motor urrent	Incipient loss of reducer	Incipient loss of conveyor operation	None	3	1	Service manual requires periodic inspection of oil level and specifies type and grade of make-up lubricant
						Page - 45 ~
h	igh motor	igh motor	igh motor	igh motor	igh motor rrent	igh motor rrent

Indenture Level No. 1 VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2 Drive System
Indenture Level No. 3 Reducer (Page -2-)
Indenture Level No. 4
Drawing
Commercial Part

Output specification	tput specification ctional description SN Description		Symptoms-	Effect of	Failure	com	
functional description			Possible causes	detectability	Local Effect	End Effect	(0
10.4 Reducer	10.4.04	Load trays tilt-drive chains out of synchronization	-lubricant contaminated -one or both out-put shaft keys or keyways distorted or broken	Trays tilted -one side of tray driving the other	Incipient jam at head or bottom cam plates	Incipient loss of conveyor operation	N

Contract No. N00024-72-C-5500
Organization KORNYLAK CORPORATION
By ENGINEERING DEPT., KORNYLAK CORP.

APPROVED:	DATE:	
APPRUVPII:	UAIT:	

	Symptoms.	Effect of	Failure			Failure prob-	Remarks and Recommendations
)565 	detectability	Local Effect	End Effect	provision	Severity	ability	veliging and veconimendations
t ted oth haft	Trays tilted -one side of tray driving the other	Incipient jam at head or bottom cam plates	Incipient loss of conveyor operation	None	4	1	Service manual requires periodic check for condition of keys and keyways and check of drive chain synchronization.
or							
A comment of the both with the color							
ع تعلق جعما (م بادون دور							
والمراجع والمراجع المراجع المر							
Kataman Sandang, ph							
المستقدم والمستقد المستقد المستقد المستقدم والمستقدم وال							
e de de la desta de la desta de la desta de la desta de la desta de la desta de la desta de la desta de la dest							
and American State of the State				7			Page - 46 -

Form No. 276 6

Indenture Level No. 2 Drive System

Indenture Level No. 3 10.5 Brake

Indenture Level No. 4

CAGI IAN' A	
Drawing	Commercial Part

Output specification functional description	Failure Mode		Possible causes	Symptoms-	Effect of	Exis	
	SN	Description	Possible causes	dstectability	Local Effect	End Effect	compar previ
10.5 Brake Assures that conveyor will not reverse	10.5.01	Coil Burnout	-weak insula- tion -wrong hookup	Brake will not disengage	IOL or thermal overload trips	Conveyor will not run	Non
Assures that conveyor will	10.5.02	Engaging spring failure	-weak spring -corroded spring	Brake will not engage	Conveyor coasts to stop	Trays will not position properly	Non
stop and properly position trays at door openings.	10.5.03	Friction lining worn out	-improper gap adjustment -normal wear and tear	Brake will not engage properly	Conveyor coasts to a stop	Trays will not position properly	Non
Assures that conveyor will stop in the event of power	10.5.04	Brake to reducer key failure	-weak material -wear and tear	Brake will not engage	Conveyor coasts to stop	Trays will not position properly	Non
failure.	10.5.05	Pressure plate mechanism failure	-weak materia! -wear and tear -corrosion	1	Convayor coasts to stop	Trays will not position properly	Nor
	10.5.06	Jerky stops Slow to stop Brake slips	-grease or oil on friction discs ard/or pressure plate -improper gap adjustment	descript ion	Same as description	Trays may not position properly	Nor
							(3)

C-)t	tract No.	N0002	24-72-0	C-5500)			
Org	enization	KORNY	LAK (ORPO	RATION			
By	EN	GINEER	ING D	EPT.	KORNY	LAK (ORP.	

APPROVED: _____ DATE: ____

i i de Bio	Symptoms-	Effect of Failure		Existing Level	Failure			
G.	detectability	Local Effect	Local Effect compensating Security Secu		of Severity	prob- ability	Remarks and Recommendations	
i- Ip	Brake will not disengage	IOL or thermal overload trips	Conveyor will not run	None	2	1	Remove brake and replace coil.	
	Brake will not engage	Conveyor coasts to stop	Trays will not position properly	None	1	1	Remove brake and replace spring	
ıp	Brake will not engage properly	Conveyor coasts to a stop	Trays will not position properly	None	1	1	Remove brake and replace friction lining.	
al ar	Brake will not engaye	Conveyor coasts to stop	Trays will not position properly	None	1	1	Remove brake - replace key - re-work keyways.	
-1	Brake will not engage Same as	Conveyor coasts to stop	Trays will not position properly	None	1	1	Remove brake - repair or replace failed parts.	
il te p	Same as description	Same as description	Trays may not positica properly	None	1	1	Remove brake - clean pressure plate - clean or replace friction discs.	
							Page - 47 -	

Indenture Level No. 1	VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2	Drive System
Indenture Level No. 3	Coupling
!- denture Level No. 4	

Output specification	Failure Mode SN Description			Symptoms-	Effect o	f Failure	Exi
functional description			Possible causes	detectability	Local Effect	End Effect	compe
10.6 Coupling Connects Reducer Drive Shaft (s) to Jack Shafts	10.6.01	Worn or distorted keys and/or keyways	-repeated jams	Trays may tilt or cock	Incipient jams at head or tail cams	Incipient loss of conveyor operation	Not
	10.6.02	Torsional stress failure	-repeated jams -weak material	Trays tilt or cock	Jams at head or tail cams	Loss of conveyor operation	Maximum stress i psi undi conditio
	10.6.03	Stress failure of key (s)	-repeated jams -weak material	Trays tilt or cock	Jams at head or tuil cams	Loss of conveyor operation	Maximum stress i psi und conditio
2							

Contract No. N00024-72-C-5500
Organization KURNYLAK CORPORATION
By ENGINEERING DEPT., KORNYLAK CORP.

APPROVED:	 DATE:	

Market Barrie	Symptoms-	Effect of Failure		Existing compensating	Level of	Failure prob-	Remarks and Recommendations	
	detectability	Local Effect	End Effect	provision	Severity	ability	nemaliks and necommendations	
am S	Trays may tilt or cock	Incipient jams at head or tail cams	Incipient loss of conveyor operation	None	3	1	Replace couplings and keys or remove couplings and re-work keyways.	
ial	Trays tilt or cock	Jams at head or tail cams	Loss of conveyor operation	Maximum torsiona stress is 307 psi under jam conditions	1 4	1	Reprace coupling.	
	Trays tilt or cock	Jams at head or tail cams	loss of conveyor operation	Maximum key stress is 5112 psi under jam conditions	4	1	Replace keys.	
							Page - 48 -	

Indenture Level No. 1	VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2	Drive System
Indenture Level No. 3	Jack Shaft (s)
Indenture Level No. 4	
Drawing	

Output specification	Failure Mode		Possible causes	Symptoms-	Effect o	Exist	
functional description	SN	Qescription	Possible causes	detectability	Local Effect	End Effect	compens provid
10.7 Jack Shaft (s) Connects the Reducer Drive Shafts to the	0.7.01	Worn or distorted key- ways and/or keys at coupling and/or sprockess		Trays may tilt or cock	Incipient jams at head or tail cams	Incipient loss of conveyor operation	Non e
Drive Sprockets	0.7.02	Torsional stress	-rypeated jams -weak material		Jams at head or tail cams	Loss of conveyor operation	Shaft sed maximum torsional of 4046 p jam condi
	10.7.03	Coupling or sprocket key stress failure	-repeated jams -weak material	Tilted or cocked trays	Jam at head or tail cams	Loss of conveyor operation	Keys see maximum of 8058 i under jam condition
							The street of th

Contract No.	N00024-72-C-5500
Organization	KORNYLAK CORPORATION
By EN	GINEERING DEPT., KORNYLAK CORP.

APPROVED:	NATE.	
ATTRUVEU.	UNIE:	

الافحان	Symptoms-	Effect of Failure		Existing Level compensating of		Failure prob-	Remarks and Recommendations
القريفات	detectability	Local Effect End Effect		provision	Severity ability		Hemorks and Heconomic inations
	Trays may tilt or cock	jams at head or tail	Incipient loss of conveyor operation	None	3	1	Replace shafts and keys or remove shafts and re-work keyways.
	Tilted or cocked trays	head or	conveyor operation	Shaft sees a maximum torsional stress of 4046 psi unde jam conditions	4	1	Replace shaft.
lal	Tilted or cocked trays	Jam at head or tail cams	Loss of conveyor operation	Keys see a maximum stress of 8058 psi under jam conditions	4	1	Replace keys.
							Page - 49 -

Form No. 276-6

Indenture Level No. 1	VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2	Drive System
Indenture Level No. 3	Bearing
indenture Level No. 4	
Drawing	Commercial Part

Output specification		Failure Mode		Symptoms-	Effect		
functional description	SN	Description	Possible causes	detectability	Local Effect	End Effect	con
10.8 Bearing Supports Jack Shaft at sprocket end	10.8.01	Frozen bearing	-lack of propelubrication -contaminated -improper alignment	-high current -conveyor will not run	No jack shaft rotation	Conveyor inoperative	
	10.8.02	Dynamic failure	-normal wear and tear -overload	-high current -erratic operation	Trays may rock	Incipient jams at cam track plates	Bearin sized life o hours averag 140,00

Contract No. NOOD24-72-C-5500
Organization KORNYLAK CORPORATION
By ENGINEERING DEPT., KORNYLAK CORP.

alter all free land						APPRO	VEO: DATE:
nes	Symptoms-	Effect of Failure		Existing compensating	Level	Failure prok	Remarks and Recommendations
	detectability	Local Effect	End Effect	provision	Severity		
prope on ated	-high current -conveyor will not run	No jack shaft rotation	Conveyor inoperative	None	4	1	Service manual requires periodic inspection and lubrication of the pillow block bearings
	-high current -erratic operation	Trays may rock	Incipient jams at cam track plates	Bearings are sized for a bio life of 28,000 hours and an average life of 140,000 hours	2	1	Replace Fillow block bearing
A de la companya de l			<i>z</i> .				Page - 50 -

Fam No 7/6

Indenture Level No. 1	VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2	Drive System
	Drive Sprocket
Indenture Level No. 4	
Drawing	Commercial Part

Output specification	Failure Mode		Possible causes	Symptoms-	Effect a	Existia		
functional description	SN	Description	Lassinis canses	detectability	Local Effect	End Effect	compensa provisie	
10.9 Drive Sprocket Connects the Jack Shaft or Reducer Output to the Head Shaft Sprocket	10.9.01	Worn or distorted key- ways and/or keys at sprockets	Repeated jams	Trays may tilt or cock	Incipient jams at head or tail cams	Incipient loss of conveyor operation	Nones	
Shart Sprocket	10.9.02	Sprocket key stress failure	-repeated jams -weak material		Jams at head or tail cams	Loss of conveyor operation	Keys see maximum sof 8058 pi under jam condition	

Contract No. N00024-72-C-5500

Organization KORNYLAK CORPORATION
By ENGINEERING DEPT., KORNYLAK CORP.

APPROVED: _____ DATE: ____

Salva Sureci	Symptoms-	Effect of Failure		Existing compensating	Level of	Failure prob-	Remarks and Recommendations	
Company.	detectability	Local Effect End Effect		provision	Severity	ability	erating to and eracontinetinations	
er de la maria de la maria de la maria de la maria de la maria de la maria de la maria de la maria de la maria	Trays may tilt or cock	Incipient jams at head or tail cams	Incipient loss of conveyor operation	Non e	3	1	Replace sprocket and keys. Remove sprocket and re-work keys and keyways.	
	Tilted or cocked trays	Jams at head or tail cams	Loss of conveyor operation	Keys see a maximum stress of 8058 psi under jam conditions	4	1	Replace worn or distorted keys. Page - 51 -	

(2)

Form No. 276-6

Indenture Level No. 1	VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2	Drive System
Indenture Level No. 3	Drive Chain
Indenture Level No. 4	
0	Commercial Part

Output specification	Failure Mode		Possible causes	Symptoms.	Effect a	f Failure	con
functional description	SN	Description	Possible causes	detectability	Local Effect	End Effect	CON
10.10 Drive Chain Transmits power from the Jack Shaft to the Head Shaft	10.10.01	Stretched or distorted chain	-repeated or excessive jams -faulty material	Tilted or cocked trays	Jams at head or tail cams	Loss of conveyor operation	Chains never more t ultima streng

Contract No NOO024-72-C-5500
Organization KORNYLAK CORPORATION
By ENGINEERING DEPT., KORNYLAK CORP.

APPROVED _____ DATE: ____

150 5	Symptoms-	Symptoms- Effect of Failure			Level of	Failure prob-	Remarks and Recon mendations
1962	detectability	Local Effect	End Effect	compensating provision	Severity	ability	Tienterna una riccon institutioni
or jams	Tilted or	Jams at head or tail cams	Loss of conveyor operation	Chains are never loaded to more than 10% of ultimate strength	4	1	This condition is highly improbable due to design. Replace faulty chain.
							Page - 52 -

Farm No. 276 6

Indenture Level No. 1	VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2	Drive System
Indenture Level No. 3	Chain Take-up
Indenture Level No. 4	
Drawing	

Output specification functional description	Failure Mode		Possible causes	Symptoms-	Effect of	Failure	Exis
	SN	Description	Possible causes	detectability	Local Effect	End Effect	compe
10.11 Chain Take-up Removes slack from Drive	10.11.01	Bearing failure	No lubrication -faulty material	Trays tilt or cock out of square	Incipient jams at head or tai cams	Incipient loss of conveyor operation	Non
Chains. Keeps both side of Carrier Chain alined, by equalizing tension.	10.11.02	Faulty or poor adjustment	Repeated jams	Trays tilt or cock out of square	Incipient jams at head or tail cams	Incipient loss of conveyor operation	Non
	10.11.03	Broken adjust- ing screw -troken bracket -bent bracket	Repeated jams ~mechanical damage	Trays tilt or cock out of square	Incipient jams at head or tail cams	Incipient loss of conveyor operation	Non

Contract No. N00024-72-C-5500
Organization KORNYLAK CORPORATION
By ENGINEERING DEPT., KORNYLAK CORP.

APPROVED: _____ DATE: ____

Sayate	Symptoms-	Effect of	Failure	Existing compensating	Level of		Remarks and Recommendations
أوستنف	detectability	Local Effect	End Effect	provision	O: Severity		nemarks and necommendations
ion	Trays tilt or cock out of square	Incipient jams at head or tai cams	Incipient loss of conveyor operation	None	2	1	Replace take-up bearing.
on Company of the second	Trays tilt or cock out of square	Incipienc jams at heed or tail cams	Incipient loss of conveyor operation	None	1	1	Correct adjustment. Synchronize and re-align conveyor
D. D. A. A. A. A. A. A. A. A. A. A. A. A. A.	Trays tilt or cock out of square	Incipient jams at head or tail cams	Incipient loss of conveyor operation	None	2	1	Replace adjusting screw. Replace broken or bent bracket. Synchronize and re-align conveyor.
tion and statement in the statement of t							Page - 53 -

Form No 276 6

Indenture Level No. 1 Indenture Level No. 2	VERTICAL CONVEYOR SYSTEM Structure
Indenture Level No. 3	
Indenture Level No. 4	
fleaning	

functional description SN Description Column detectability Local Effect End Effect Column detectability Local Effect End Effect Column detectability Local Effect Column detectability Local Effect Column detectability Local Effect Column detectability Local Effect Column detectability Local Effect Column detectability Local Effect Column detectability	Output specification functional description	Failure Mode		Partible sauce Symptoms-	Effect of	E		
Provides support for conveyor mechanism Troubles a water tight enclosure 1		SN	Description	Possible causes		Local Effect	End Effect	CO IM
tion at deck -rubbing -noise stalls openings -high current Weld shrinkbinding trays -excess wear conveyor age at decks, -rubbing -noise stalls base and trunk -high current	Provides support for conveyor mechanism Provides a watertight		tight	-deterioration of door seal(s -improper adjustment of door dogs -misalignment of foundation base -material	water or Vair under	penetrate trunk from surrounding compartment -or- surrounding compart- ments from	local effect	N
age at decks, -rubbing -noise stalls base and trunk -high current		20.1.02		at deck	-rubbing			N
				age at decks, base and trunk	-rubbing			N

Contract No. NO0024-72-C-5500
Organization KORNYLAK CORPORATION
By ENGINEERING DEPT., KORNYLAK CORP.

APPROVED: _____ DATE: __

1.00	Symptoms-	Effect of Failure Local Effect End Effect		Existing			
	detectability			compensating provision	of Severity	prob- ability	Remarks and Recommendations
tion	Will not hold water or Vair under	Water can penetrate trunk from	Same as local effect	None	1	1 2	Find and repair cracked welds Replace door seals
of	pressure	surrounding compartment			1	2	Adjust dogs - replace if out of adjustability
ent ion		surrounding compart- ments from			1	1	Installation problems - check drawings and service manual for proper installation procedures.
		trunk			1	2	Conveyor drains must be kept open - check trunk frequently for rust. Chip and repaint when necessary.
S. Significant despendents	-binding trays -rubbing -high current	-excess wea -noise	conveyor stalls	None	j	1	Transmission of shear loads minimized by use of semi-flexible method of supporting conveyor at deck openings.
ks, runk	-binding trays -rubbing -high current	-excess wea	stalls	None	1	1	Exercise care during installation, especially in welding techniques
			:	_			Page - 54 -
				(g)	L		Form No. 276 6

Indenture Level No. 1	VERTICAL CONVEYOR SYSTEM Operating System
Indenture Level No. 2	
Indenture Level No. 3	Head Cam Plate
Indenture Level No. 4	
Drawing	

Output specification	Failure Mode		S/mptoms-		Effect o	6	
tonctional description	SN	Description	Possible causes	detectability	Local Effect	End Effect	COM PI
30.1 Head Cam Plate The Head Cam Plate causes the carrier tray to make the horizontal to vertical	30.01	Cam Tracks worn or distorted	Repeated sams	Conveyor runs rough	Same as symptom	-possible high current -possible nuisance IOL cut out -excessive slippage of torque limiter	Torque can al shock come 1
transition as the carrier trays move front to back	30.1.02	Cam tracks broken	Repeated jams	Conveyor jams at broken track	High current IOL cuts out	Pending loss of conveyor operation cam roll jams in broken cam track plate	Torque slips
				l			,

Contract No. MU0024-72-C-5500
Organization KORNYLAK CORPORATION
By ENGINEERING DEPT., KORNYLAK CORP.

APPROVED:	 DATE:	

والمعاور والمعالمة والمعارض والمعارض والمعارض والمعارض والمعارض والمعارض والمعارض والمعارض والمعارض والمعارض و	Symptoms- detectability	Effect of Failure		Existing compensating	Level of	Failure prob·	Remarks and Recommendations	
		Local Fifect	End Effect	pravision	Severity	ability	nemarks and necommendations	
O	Conveyor runs rough		-possible high current -possible nuisance IOL cut out -excessive slippage of torque limiter	Torque Limiter can absorb some shock or over- come roughness	2	2	Straighten and/or remove rough spots in cam track. Remove and replace faulty cam plate	
O	Conveyor jams at broken track	High current IOL cuts out	Pending loss of conveyor operation cam roll jams in broken cam track plate	Torque Limiter slips	4	2	Remove and repair cam plate or remove and replace faulty cam plate.	
							Page - 55 -	

Form No. 276 6

Indenture Level No. 1	VERTICAL CONVEYOR SYSTEM Operating System
Indenture Level No. 2	Operating System
Indenture Level No. 3	
Indenture Level No. 4	
Drawina	

Output specification	Failure Moule		_	Symptoms-	Effect of Failure		Ex
functional description	SN	Description	Possible causes	detectability	Local Effect	End Effect	compi pro
30.2 Head Shaft The head shaft	30.2.01	Worn or dis- torted keyways or keys at the driven sprocket	Repeated jams	Trays tilt or cock	Incipient jams at head cam	Incipient loss of conveyor operation	No
is the principal shaft which transfers the power to the tray system. The entire	30.2.02	Torsional stres failure	s Repeated jams faulty mater- ial	Tilted or cocked trays	Jams at head or tail cams	Loss of conveyor operation	Shaft maximum nal str 5054 pa jam com
weight of the tray system and load are on this shaft	30.2.03	Sprocket key stress failure	Repeated jams weak material	Tilted or cocked trays	Jams at head or tai cams	Loss of conveyor operation	Keys semaximum of 9134 at jam conditi
	30.2.04	Bent head shaft	Extremely heavy jam	Carrier sprocket wobbles as it revolves	Same as symptom	-stretched chain -tray flexure	No (see re column

Contract No.	N00024-72-C-5500
Drganiz a tion	KORNYLAK CORPORATION
	GINEERING DEPT., KORNYLAK CORP.

APPROVED:	 DATE:	
	Unic.	

د بودا	Symptoms-	Effect of Failure		Existing Level compensating of	Failure prob-	Remarks and Recommendations	
che se e	detectability	Local Effect	End Effect	provision	Severity	ability	nemalks and necommendations
ams	Trays tilt or cock	Incipient jams at head cam	Incipient loss of conveyor operation	None	3	1	Replace head shaft (s) and keys or remove shafts and rework keyways and keys
jams te r-	Tilted or cocked trays	Jams at head or tail cams	Loss of conveyor operation	Shaft sees a maximum torsio- nal stress of 5054 psi under jam conditions	4	1	Replace head shaft (s)
ams ial	Tilted or cocked trays	Jams at head or tai cams	Loss of conveyor operation	Keys see a maximum stress of 9134 psi at jam condition	4	1	Replace keys
	Carrier sprocket wobbles as it revolves	Same as symptom	-stretched chain -tray flexure	None (see remarks column)	2	1	Replace head shaft. Note: In the new design this shaft has been increased from 1.75" to 2.937" giving in excess of 4.7 times the previous strength.
							Page - 56 -

Indenture Level No. 1 VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2 Operating System
Indenture Level No. 3 Head Shaft Bearing (s)
Indenture Level No. 4

Drawing

Commercial Part

[<u> </u>	5 12 AA A					
Output specification		Failure Mode	Possible causes	Symptoms-	Effect o	f Failure	Exi com pa
functional description	SN	Description	a orginie conses		Local Effect	End Effect	prov
30.3 Head Shaft Bearing (s) Supports the head shaft at	30.3.01	Frozen bearings	Lack of proper lubrication -contamination -improper alignment	-conveyor will	No head shaft rotation	Conveyor inoperative	No
both the inboard and outboard end of the head shaft	30.3.02	Dynamic failure	-normal wear and tear -overload	-high current -erratic operation	Trays may rock	Incipient jams at cam track plates	Bearing sized for the size of

Contrac	t No.	N:0002	4-77	2-C-556	10			
Drenniza	tios	KOAN	LAN	CORP	DRAT	ION		_
Bv	EN	GINEER	ING	DEPT.	KOR	INYLAK	CORP.	

APPROVEO: _____ DATE: ____

والمراش والم	Symptoms-	Effect of Failure		Existing	Level Failure		Remarks and Recommendations
شيهاته ورايعة	detectability	Local Effect	End Effect	compensating provision	Severity ability		nemarks and necommensations
on	-high current -conveyor will not run		Conveyor inoperative	None	4	1	Service manual requires periodic inspection and lubrication of head shaft bearings
	-high current -erratic operation	Trays may rock	Incipient jams at cam track plates	Bearings are sized for a B-10 life of 30,000 hours and an average life of 150,000 hours	2	1	Replace head shaft bearings
							Page - 57 -

Indenture Level No. 1	VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2	Operating System
Indenture Level No. 3	Head Bearing Housing
Indenture Level No. 4	

Drawing .

Output specification Failure Mode	Symptoms-	Effect of	Failure	£
functional description SN Description Possible causes	detectability	Local Effect	End Effect	co m
	igh current conveyor will ot run	-no head shaft rotation -trays tilt or cock	Incipient loss of conveyor operation	N. Company of the state of the

Contract No. N00024-72-C-5500 Organization KORNYLAK CORPORATION By ENGINEERING DEPT., KORNYLAK CORP.

APPROVED:	 DATE:	**************************************
/// / // / / C / C C .	D/11 ~ .	the second secon

	Symptoms-					Failure prob-	Rer rks and Recommendations
	detectability	Local Effect	End Effect	provision	Severity		us: : k2 and usCommendation2
ting	High current -conveyor will not run	-no head shaft rotation -trays tilt or cock	Incipient loss of conveyor operation	None	4	1	Replace head shaft bearing housing. This contractor has never experienced a failure in this part after having produced vertical conveyor systems for over 20 years and over 400 units produced.
in the second se				<i>A</i>			Page - 58 -

Indenture Level No. 1
Indenture Level No. 2
Indenture Level No. 3
Indenture Level No. 4

VERTICAL CONVEYOR SYSTEM
Operating System
Head Shaft Sprocket

Drawing _

Output specification	Failure Mode	0	Symptoms-	Effect o	Exi		
functional description	SN	Description	Possible causes	detectability	Local Effect	End Effect	compe pre
30.5 Head Shaft Sprocket This item is	30.5.01	Worn head shaft sprocket	-misalignment -abnormal jams -abnormal loading	-polished teeth -ridges in teeth	Same as symptom	Rough conveyor operation	No
the sprocket which becomes the driver and load support for the carrier trays	30.5.02	Sprocket key stress failure	-repeated jams -weak or faulty materia	Tilted or cocked trays	Jam at head or tail cams	Loss of conveyor operation	Keys semaximum of 9134 jam con
							ې اوانام جولان سالمان مېداد سالون چولان داد او داد او داد او داد او داد او داد او داد او داد او داد او داد او داد

Contract No	NA0024-72-C-5	500	
Organization	KORNYLAK COR	PORATION	
By El	NGINEERING DEPT	r., KORNYLAK	CORP.

APPROVED:	 DATE:	

V. Messaga P. S. Sansa	Symptoms-	Effect of Failure Local Effect End Effect		Existing compensating	Level of	Failure prob-	Remarks and Recommendations
ا را معاملات	detectability			provision	Severity	ability	Velial ky alia Lierollilliandations
± S	~ridges in	Same as symptom	Rough conveyor operation	None	2	1	Replace head shaft sprocket
The state of the s	Tilted or cocked trays	Jam at head or tail cams	Loss of conveyor operation	Keys see a maximum stress of 9134 psi at jam condition	4	1	Rework key seat and replace keys
State of the Company							
ed in the Reading of				,	<u> </u>		Page - 59 -

Indenture Level No. 1 VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2 Operating System
Carrier Chain Section
Indenture Level No. 4
Drawing
Commercial Part

0

Output specification		Failure Mode	Describbe	Symptoms-	Effect		
functional description	SN	Description	Possible causes	detectability	Local Effect	End Effect	601
30.6 Carrier Chain Section The carrier chain section is the connecting link between each of the trays and the drive system.		Stretched or distorted carrier chain	-repeated or excessive jams -faulty material	Tilted or cocked trays	Jams at head or tail cams	Loss of conveyor operation	Chain never more of ulstren

Contract No.	N00024-72-C-550	10	
Organization	KORNYLAK CORP	DRATION	
By EN	GINEERING DEPT.	, KORNYLAK CO	ORP.

Symptomsdetectability

| Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensating | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensation | Compensat

ipes .	A			compensating	of	prob-	Remarks and Recommendations
ices	detectability	Local Effect	End Effect	provision	Severity	ability	
or	Tilted or cocked trays	Jams at head or tail cams	Loss of conveyor operation	Chains are never loaded to more than 10% of ultimate strength	4	1	Replace faulty chain. Note: This condition is highly improbable due to design loading of chain.
T. V. Karakan and K.							

							Page - 60 -

Indenture Level No. 1	VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2	Operating System
Indenture Level No. 3	Carrier Link
Indenture Level No. 4	
Orandona	

Output specification functional description	ļ	<u> </u>	Possible causes				com		
tunctional description	SN	Description		detectability	Local Effect				
30.7 Carrier Link The carrier link provides the	30.7.01	Stretched or distorted link	-repeated or excessive jams -faulty material	Tilted or cocked trays	Jams at head or tail cams	Impending loss of conveyor operation	N		
bearing and the linkage to connect the chain sections from tray to tray.	30.7.02	Worn sleeve in link	-faulty material -long use -lack of lubrication	-conveyor runs rough -conveyor is noisey	Same as end effect	Impending need to overhaul system	N		

Contract No.	N00G24-72-C-5500	
Organization	KORNYLAK CORPORATION	_
By EN	GINEERING DEPT., KORNYLAK CORP.	_

APPROVED:	DATE:	

2	Symptoms-			Existing compensating			Remarks and Recommendations	
ie.	detectability	Local Effect	End Effect	provision	Severity		Henry and Heconinensations	
r ams	Tilted or cocked trays	Jams at head or tail cams	Impending loss of conveyor operation	None	3	1	Replace carrier link and associated chain parts.	
	-conveyor runs rough -conveyor is noisey	Same as end effect	Impending need to overhaul system	None	2	1	Replace carrier link. Examine and replace any associated worn chain parts.	
·				•			Page - 61 -	

Indenture Level No. 1	VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2	Operating System
Indenture Level No. 3	Chain Pin
Indenture Level No. 4	
Drawina	

Output specification functional description SN Description Conterpin not pin allowing chain pin to connects the chain to the carrier link Output specification SN Description Possible causes Cotter pin not bent sufficibent sufficible suffic			Failure Mode			Effect of	Failure	
pin allowing chain pin to slide out of connects the chain to the carrier link pin allowing chent sufficiently to keep of proper chain or on chain pin engaged. With or loss of chain or on chain or on carrier link pin allowing chent sufficiently to keep of proper engagement with sprocket link pin allowing chent sufficiently to keep of proper engagement with sprocket link assembly or	Output specification functional description			Possible causes	Symptoms- detectability			con
	30.8 Chain Pin The chain pin connects the chain to the carrier link	30.8.01	pin allowing chain pin to slide out of	bent suffici- ently to keep chain pin engaged. -incomplete assembly or	with or loss of proper engagement	plates on chain or on carrier	loss of linkage in	

Contract No. N00024-72-C-5500
Organization KORNYLAK CORPORATION
By ENGINEERING DEPT., KORNYLAK CORP.

APPROVED:	DATE:	

bes	Symptoms-	Effect of Failure		Existing Level compensating of	Failure prob-	Remarks and Recommendations	
	detectability	Local Effect	End Effect	provision	Severity	ability	nemark) and decommendations
notici- teep	Difficulty with or loss of proper engagement with sprocket	Bent side plates on chain or on carrier link	Impending loss of linkage in system	None	4	1	Replace associated damaged parts. Note: This can only occur if proper repair or assembly procedures are not followed.
e gangin sa							
							Page - 62 -

(F)

Indenture Level No. 1 VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2 Operating System
Carrier Shaft
Indenture Level No. 4

Drawing

2-1026-P28

Output specification	Failure Mode		Pussible causes	Symptoms-	Effect of	Ex	
functional description	SN	Description	Possible Causes	detectability	Local Effect	End Effect	pro
30.9 Carrier Shaft	30.9.01	Excessive torsional stress causing shaft to be bent or broken	Jammed under full force of maximum reducer output	of carrier	Jam may occur in tail or head cam plates or in vertical track	Probable loss of conveyor operation	System protection which protection by cauto slf
						7	

Contract No.	N00024-72-C-5500
Organization	KORNYLAK CORPORATION
By EN	GINEERING DEPT., KORNYLAK CORP.

APPROVED:	 DATE:	

	Symptoms-	Effect of Failure		Existing Level	Failure	December 1 December 1	
	detectability	Local Effect	End Effect	compensating provision	of Severity	prob- ability	Remarks and Recommendations
r of put	-visible misalignment of carrier tray -loose carrier tray	Jam may occur in tail or head cam plates or in vertical track	Probable loss of conveyor operation	System is protected by torque limiter which should protect conveyo by causing driv to slip		2	Replace carrier shaft and associated parts. May need to replace tray if damaged.

Indenture Level No. 1 VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2 Operating System
Indenture Level No. 3 Guide Arm and Guide Arm Cap

Indenture Level No. 4

Drawing 2-1026-P-27 and 2-1026 47F

Output specification		Failure Mode	Possible causes	Symptoms-	Effect o	f Failure	Ei
functional description	SN	Description	Possible causes	detectability	Local Effect	End Effect	bu com
The guide arm and guide arm cap control the attitude of the tray from horizontal to vertical as the tray travels around the tray path	30.10.01 30.11.01	Description Key and cap shear limit exceeded	Jammed under a full force of maximum chain pull		Tray running	. Incipient jams cau occur in head or	System protector que which cause convey cease
							والحظالها والمباشعين والمحالية والأمريجين في مظالها والمناسعة ومستعداته فرعمة أن

Contract No.	N00024-72-C-5500
Organization	KURNYLAK CORPORATION
By EN	GINEERING DEPT., KORNYLAK CORP.

APPROVED: _____ DATE: ____

Jes .	Symptoms- detectability			Existing Level compensating of		Failure prob-	Remarks and Recommendations	
		Local Effect	End Effect	provision	Severity	ability	riemas as ann riecommendarions	
of ain	Guide arm loose on shaft -guide arm cap distorted	Tray running out of horizontal position -tray loose in track guides	jams can occur in head or	System is protected torque limiter which should cause the conveyor to cease operation	4	1	Replace guide arm and guide arm cap and associated damaged parts. Page - 64 -	

Form No. 27

Indenture Level No. 1 Indenture Level No. 2	Operating System Cam Follower Flanged/Cam Follower
Indenture Level No. 4	

Output specification	Failure Mode			Symptoms-	Effect of	Existi	
functional description	SN	Description	Possible causes	detectability	Local Effect	End Effect	comp ent provis
30.12 Cam Follower Flanged 30.13 Cam Follower				~ ~ ~		•••	***************************************
These cam followers guide the tray through its manuevers on the tray path							

Contract No.	N00024-72-C-5500
Organization	KORNYLAK CORPORATION
By EN	GINEERING DEPT., KORNYLAK CORP.

APPROVED:	 DATE	

يتماري والمتكافئة بالمتاريخ فيدرين	Symptoms-	Effect of Failure		Existing	Level	Failure	
	detectability	Local Effect	End Effect	compensating provision	of Severity	prob- ability	Remarks and Recommendations
							There are no discernable means of failure evident by our calculations
							Page - 65 -

Indenture Level No. 1	VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2	Operating Systems
Indenture Level No. 3	Carrier
Indenture Level No. 4	
Drawing	

Output specification		Failure Mode		Symptoms-	Effect (of Failure	Exi	
functional description	SN	Description	Possible causes	detectability	Local Effect	End Effect	com pe pr ov	
30.14 Carrier		Description Excessive torsional stres	Jammed under full chain load at tip of tray finger	Visible bolt farlure. Carrier tray	Same as symptom	Carrier tray may jam in any position	Carrier held in using should be setting	

Contract No. NOOO24-72-C-5500
Organization KORNYLAK CORPORATION
By ENGINEERING DEPT., KORNYLAK CORP.

APPROVED:		DATE:	
711110 FED.	the same of the sa	Drite	The second secon

	Symptoms-	Effect of Failure		Existing compensating	Level of	Failure	Remarks and Recommendations
	detectability	Local Effect	End Effect	provision	Severity	prob- ability	Hemarks and Hecoinmendations
p nger	Visible bolt failure. Carrier tray not in normal position	Same as symptom	tray may	Carrier tray held in position using shear bolt which shear above IOL setting		2	Drive out shear bolt stubs. Re-position carrier. Replace shear bolts with exact replacement. Reset IOL.
							Page - 66 -

Indenture Level No. 1	VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2	VERTICAL CONVEYOR SYSTEM Operating System Front Track and Rear Track
Indenture Level No. 3	Front Track and Rear Track
'ndenture Level No. 4	

Output specification		Failure Mode	Symptoms-	Effect	٤		
functional description	SN	Description	Possible causes	detectability	Local Effect	End Effect	con
30.15 Front Track 30.16 Rear Track	30.15.01 30.16.01	Tracks worn or distorted	Repeated jams	Conveyor runs rough	Same as symptom	-possible high current -possible nuisance IOL cut out	same s
The track system controls the attitude of the tray from horizontal to vertical in the front to rear travel of the carrier	30.15.02 30.16.02	Tracks broken	Repeated jams	Conveyor jams at broken track	High current IOL cuts out	Pending loss of conveyor operation cam roll jams in broken track	Torque slips

Cont	ract No.	N0002	4-72-0	-550	0	
Organ	nization	KORNY	LAKC	ORPC	RATION	
By .					KORNY	ORP.

APPROVED: _____ DATE: ____

3	Symptums-	Effect of Failure				Failure prob-	Remarks and Recommendations	
	detectability	Local Effect	End Effect	provision	Severity	ability	nemaixs and neconstrictivations	
am s	Conveyor runs rough	Same as symptom	-possible high current -possible nuisance IOL cut out	Torque Limiter can absorb same shock or overcome roughness	2	2	Straighten and/or remove rough spots in track. Remove and replace faulty track section	
ams	Conveyor jams at broken track	High current IOL cuts out	Pending loss of conveyor operation cam roll jams in broken track	Torque Limiter slips	4	2	Remove and replace faulty track section	

Indenture Level No. 1	VERTICAL CONVEYOR SYSTEM	
Indenture Level No. 2	Operating System	
	Tail Cam Plate	
Indenture Level No. 4		_
D		

Output specification		Failure Mode		Symptoms-	Effect o	f Failure	E
functional description	SN	Description	Possible causes	detectability	Local Effect	End Elfect	(Pr
30.17 Tail Cam Plate The Tail Cam Plate causes the carrier tray to make horizontal to vertical transition as	30.17.01	Cam tracks worn or distorted	Repeated jams	Conveyor runs rough	Same as symptom	-possible high current -possible nuisance IOL cut out -excessive slippage of Torque Limiter	Torque can ab shock (come r
the carrier trays move front to back	30.17.02	Gam tracks broken	Repeated jams	Cenveyor jams at broken track	High current JOL cuts out	Pending loss of conveyor operation cam roll jams in broken track	Torque slips

Contract No. NOO024-72-C-5500
Organization KORNYLAK CORPORATION
By ENGINEERING DEPT., KORNYLAK CORP.

APPROVED: _____ DATE: ____

es es	Symptoms-	Effect o	f Failure	Existing compensating	Level of	Failure prob-	Remarks and Recommendations
	detectability	Local Effect	End Effect	provision	Severity	ability	nemorks and necommendations
am s	Conveyor runs rough	Same as symptom	-possible high current -possible nuisance 101, cut out -excessive slippage of Torque Limiter	Torque Limiter can absorb some shock or over- come roughness	2	2	Straighten and/or remove rough spots in cam track. Remove and replace faulty cam plate
	Genveyor jams at broken track	High current IOL cuts out	Pending loss of conveyor operation cam roll jams in broken track	Torque Limiter slips	4	2	Remove and repair cam plate or replace faulty cam plate Page - 68 -
Sing Market and the state of th							Page - 68 -

Indenture Level No. 1 VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2 Operating System
Indenture Level No. 3 Tail Shaft Sprocket
Indenture Level No. 4

Drawing

Output specification		Failure Mode	Possible causes	Symptoms-	Effect o	Ex com p	
functional description	SN	Description	Lossible canses	detectability	Local Effect	End Effect	comp
30.18 Tail Shaft Sprocket This item becomes the main support and take-up for the carrier chain and guides the guide arms through the tail cam plate		Worn shaft sprocket	-misalignment -abnormal jams -abnormal loading	-polished teeth -ridges in teeth	Same as symptom	Rough conveyor operation	The second secon

Contract No.	N00024-72-C-5500	
Organization	KORNYLAK CORPORATION	
By EN	IGINEERING DEPT., KORNYLAK CORP.	

						APPRO	VED: DATE:
5	Symptoms- detectability	Effect of Local Effect	of Failure End Effect	Existing compensating provision	Level of Severity	Failure prob- ability	Remarks and Recommendations
ent	-polished teeth -ridges in teeth	Same as symptom	Rough conveyor operation	None	2	1	Replace tail shaft sprocket
							Page - 69 -

Indenture Level No. 1 VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2 Operating System
Indenture Level No. 3 Tail Shaft Bearings (s)
Indenture Level No. 4

Orawing Commercial Part

Output specification	Failure Mode			Symptoms-	Effect o	E		
functional description	SN	Description	Possible causes	detectability	Local Effect	End Effect	pri comi	
30.19 Tail Shaft Bearing (s) Supports the	30.19.01	Frozen bearing	-lack of prope lubrication -contamination -improper alignment	-conveyor will	No tail sprocket rotation	Conveyor Inoperative		
tail shaft (s) at both the inboard and outboard end of the tail shaft.	30.19.02	Dynamic failure	-normal wear and tear -overload	-high current -erratic operation	Trays may rock	Incipient jams at cam track plates	Bearin sized B-10 1 30,000 and an life of	

Contract No. N00024-72-C-5500
Organization KORNYLAK CORPORATION
By ENGINEERING DEPT., KORNYLAK CORP.

APPROVED:	 DATE:	

es	Symptoms-	Effect of	Failure	Existing compensating	Level of	Failure prob·	Remarks and Recommendations
	detectability	Local Effect	End Effect	provision	Severity		mental wy and meconimendations
n	r-ligh current -conveyor will not run	No tail sprocket rotation	Conveyor Inoperative	None	4	1	Service manual requires periodic inspection and lubrication of tail shaft bearings
T. Consideration and the constant of the cons	-high current -erratic operation	Trays may rock	Incipient jams at cam track plates	Bearings are sized for a B-10 life of 30,000 hours and an average life of 150,000 hours	2	1	Replace head shaft bearings
obs days and business upthough a file for							Page - 70 -

(1)

Indenture Level No. 1	VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2	Operating System
Indenture Level No. 3	Chain Take-up
'-denture Level No. 4	
Drawina.	

Output specification	Failure Mode		- Possible causes	Symptoms-	Effect of Failure		
functional description	SN	Description	- LOssible canses	detectability	Local Effect End Effect		CO
30.20 Chain Take-up	30.20.01	Loose lock bolts Loose jack screws Broken jack screw	-vibration -improper adjustment -repeated jams	-loose carrier chain -trays rock or tilt	Incipient jams at head or tail cam plates	-same as local effectpossible loss of conveyor operation	
				is			

Contract No. NOOD24-72-C-5500
Organization KORNYLAK CORPORATION
By ENGINEERING DEPT., KORNYLAK CORP.

APPROVED: _____ DATF: ____

	Symptoms-	Effect of Failure		Existing compensating	Level of	Failure prob-	Remarks and Recommendations
ses	detectability	Local Effect	End Effect	prevision	Severity		DESIGN NO SHE SECONSHIEMS (CAR)
The second state of the se	-loose carrier chain -trays rock or tilt	Incipient jams at head or tail cam plates	-same as local effec -possible loss of conveyor operation	None	2	1	Repair or replace broken parts - correct take-up adjustment
الحمطيفيين							Page - 71 -

Indenture Level No.: VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2 Operating System
Indenture Level No. 3 Head Driven Sprocket

Indenture Level No. 4

Drawing Commercial Part

	 		<u> </u>	<u> </u>	<u> </u>		
Output specification	Failure Mode		Possible causes	Symptoms-	Effect of	Exi	
functional description	SN	Description		detectability	Local Effect	End Effect	pre
30.21 Head Driven Sprocket Connects the	30.21.01	Worn or distorted keyways and/or keys at sprockets	Repeated jams	Trays may tilt or cock	Incipient jams at head or tai cams	Incipient loss of conveyor operation	N
jack shaft or reducer output sprocket to the head shaft sprocket	30.21.02		-repeated jams -weak material	Tilted or cocked trays	Jams at head or tail cams	loss of conveyor operation	Keys s maximum under condit

Contract No.	N00024-72-C-5500
Organiz a tion	KORNYLAK CORPORATION
By EN	GINEERING DEPT., KORNYLAK CORP.

APPROVED:	 DATE:	

ises	Symptoms- detectability	Effect of Failure		Existing compensating	Level of	Failure prob-	Remarks and Recommendations	
ā		Local Effect	End Effect	provision	Severity		ivemarks and necommendations	
ams	Trays may tilt or cock	Incipient jams at head or tai cams	Incipient loss of conveyor operation	None	3	1	Replace sprocket and keys. Remove sprocket and rework keys and keyways.	
de distribution of the contract of the contrac	Tilted or cocked trays	Jams at head or tail cams	Loss of conveyor operation	Keys see a maximum stress under jam conditions	4	3	Replace worn or distorted keys	
							Page - 72 -	

Indenture Level No. 1 VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2 Gontrol System
Controller
Indenture Level No. 4 Reversing Starter
Drawing Commercial Part

Output specification functional description	Failure Mode			Symptoms-	Effect of Failure		Exist comp er
	SN	Description	Possible causes	detectability	Local Effect	End Effect	provi
40.1.1 Three-speed Reversing Starter The three-speed reversing start- er is provided	40.1.1.1	Starter will not operate motor at 1800 RPM in either up or down direction	Burned out coi or burned or worn contacts on 1800 RPM starter	Conveyor will run okay in 900 and 1200 RPM mode but not in up or down at 1800 RPM	Conveyor does not run in one or more directions at 1800 RPM	Conveyor not fully operative in all speeds	Use spe e which ar operati v
to give up/down directions and speed selection of 8, 10.7, or 16 trays per minute		Starter will no operate motor at 1200 RPM in one or both directions	Burned out coi or burned or worn contacts in 1200 RPM starter	Conveyor will run at 900 and 1800 RPM but not in up or down mode at 1200 RPM	Conveyor does not run in up or down mode at 1200 RPM	Conveyor not fully operative in all speeds	Use sp ee which ar operativ
	40.1.1.3	Starter will not operate motor at 900 RPM in one or both directions	Burned out coi or burned or worn contacts in 900 RPM starter	Conveyor will run at 1200 and 1800 RPM but not in up or down mode at 900 RPM	Conveyor does not run in up or down mode at 900 RPM	Conveyor not fully operative in all speeds	Use spee which ar operativ

Contract (No. N00024-72-C-5500
Organizat	ON KORNYLAK CORPORATION
By	ENGINEERING DEPT., KORNYLAK CORP.

APPROVED: _____ DATE: ____

The state of	Symptoms-	Effect of Failure		Existing compensating	Level of	Failure prob-	Remarks and Recommendations		
de la composition	detectability	Local Effect	End Effect	provision	Severity	ability	Using K2 and Decommennations		
S CO	Conveyor will run okay in 900 and 1200 RPM mode but not in up or down at 1800 RPM	Conveyor does not run in one or more directions at 1800 RPM	Conveyor not fully operative in all speeds	Use speeds which are operative	1	1	Repair or replace coils or contacts or entire 1800 RPM starter		
coi r ts	Conveyor will run at 900 and 1800 RPM but not in up or down mode at 1200 RPM	Conveyor does not run in up or down mode at 1200 RPM	Conveyor not fully operative in all speeds	Use speeds which are operative	1	1	Repair or replace coils or contacts or entire 1200 RPM starter		
O T L	Conveyor will run at 1200 and 1800 RPM but not in up or down mode at 900 RPM	Conveyor does not run in up or down mode at 900 RPM	Conveyor not fully operative in all speeds	Use speeds which are operative	1	1	Repair or replace coils or contacts or entire 900 RPM starter		
							Page - 73 -		

Indenture Level No. 1 VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2 Control System
Controller
Indenture Level No. 4
Drawing Commercial Part

Output specification functional description	Failure Mode		Possible causes	Symptoms-	Effect of Failure		Exist
	SN	Description	Fossible causes	detectability	Local Effect	End Effect	comp en provin
40.1.2 Thermal Overload Protects the motor against high current overloads in	40.1.2.1	One or more heater element inoperative	Burned out or interrupted heater coils	-motor may "single-phase" -motor may not run and may overheat		Conveyor inoperative	Emergency switch
all of the three phases	40.1.2.2	One or more bi- metallic strips melted or broken		-none under normal opera- tion - frequen cutting-out of IOL if phase with IOL is lost and overloads -high current -motor over heats if lost phase not in same phase with IOL		overheat if phase	Non

Contract No. NOO024-72-C-5500
Organization KORNYLAK CORPORATION
By ENGINEERING DEPT., KORNYLAK CORP.

APPROVED: _____ DATE: ____

C. Talanda	Symptoms-	Effect of Failure		Existing Level compensating of		Failure prob-	Remarks and Recommendations
	detectability	Local Effect	End Effect	provision	Severity		Heliai ka ana Heegininenaatigiis
or	-motor may "single-phase" -motor may not run and may overheat		Conveyor inoperative	Emergency run switch	4	1	Rest of thermal overloads would open - if failure not in IOL phase, IOL would open.
	-none under normal opera- tion - frequen cutting-out of IOL if phase with IOL is lost and overloads -high current -motor over heats if lost phase not in same phase with IOL		e overheat if phase	None	2	1	Perform checks of safety devices to assure operational capability per technical manual. Repair or replace faulty thermal overload controls Page - 74 -

Form No 276 6

Indenture Level No. 2 VERTICAL CONVEYOR SYSTEM
Control System

Controller Indenture Level No. 3 ...

Indenture Level No. 4 Instant Overload Relay (IOL)

Drawing _

Output specification	Failure Mode			Symptoms-	Effect (of Failure	Exi	
functional description	SN	Description	Possible causes	detectability	Local Effect End Effect		com pe pr ov	
40.1.3 Instant Overload Relay (10L) This element protects the motor against a high current condition. It is set to cut out at 115% of normal load current.	40.1.3.1	-burned or interrupted coil	-faulty or aged material	-motor will single phase -motor will hum and may overheat -high current -motor may burn out windings not in IOL circuit	No motor RPM	Conveyor inoperative	Emergenceswitch	

on	tract No.	N0002	24-72-	C-5500)			
)raa	nization	KORNY	LAK	CORPO	RATIO	N		
Ιν	EN	GINEER	ING D	EPT.,	KORN	YLAK	CORP.	
•								_

APPROVED: _____ DATE: ____

	Symptoms-	Effect o	f Failure	Existing compensating	Level	Failure prob-	Remarks and Recommendations
ال ترمانساس	detectability	Local Effect	End Effect	provision	Severity		TIGHT KI BILL TICCUMINICALIANONS
	-motor will single phase -motor will hum and may overheat -high current -motor may burn out windings not in IOL circuit	No motor RPM	Conveyor inoperative	Emergency run switch	3	1	Thermal overloads would open due to single phasing of motor circuits. Repair or replace faulty instantaneous overload control.

Indenture Level No. 1 VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2 Control System
Controller
Indenture Level No. 4 TOL By-pass Timer
Drawing

Output specification	Failure Mode SN Description		Pussible causes	Symptoms-	Effect o	f Failure	Exi
functional description			Pussible causes	detectability	Local Effect	End Effect	com pe pr ov
40.1.4 IOL By- pass Timer Timer allows three to five seconds for high	40.1.4.1	Burned or interrupted coil	-solenoid sticking -worn linkage -insulation breakdown -burned contac	Motor starts but stops when IOL kicks out	Motor will not run continuousl	Conveyor inoperative	Emergen c switch
	40.1.4.2	Gracked or broken bellows	Worn or aged material	Motor starts but stops when IOL kicks out	Motor will not run continuousl	Conveyor inoperative /	Emergend switch
IOI	40.1.4.3	Air bleed hold has stopped up in bellows	-mechanical damage -dirty atmosphere	None under normal operation	No protection from IOL	Motor may overheat if system gets jammed or overloaded	Conveyorun but with IO protecti
							A STANS THE SECOND STANSFER SECOND SE

Contract No.	N00024-72-C-550	
Organization	KORNYLAK CORPO	PRATION
By EN	GINEERING DEPT.	KORNYLAK CORP.

APPROVED:	 DATE:	
711110 TED.	 DAIR.	

To the last of the	Symptoms-	Effect of Failure		Existing Level compensating of		Failure prob-	Remarks and Recommendations
	detectability	Local Effect	End Effect	provision	Severity	ability	ricilial k3 4/III Ticcolliniicilua(IVII)
ge	Motor starts but stops when IOL kicks out	Motor will not run continuousl	Conveyor inoperative	Emergency run switch	3	1	Thermal overload will open due to high motor current. Repair or replace faulty IOL by-pass timer
tac	s						
d	Motor starts but stops when IOL kicks out	Motor will not run continuousl	Conveyor inoperative	Emergency run switch	3	1	Thermal overload will open due to high motor current. Repair or replace faulty IOL by-pass timer
en de maria de la composiçõe de la compo	None under normal operation	No protection from IOL	Motor may overheat if system gets janumed or overloaded	Conveyor will run but not with IOL protection	3	1	Thermal overload will handle if high current. But mechanical damage may result before thermal overload can protect system.
							Page - 76 -

Form No. 2/6 6

Indenture Level No. 1 VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2 Control System
Controller Indenture Level No. 3 _ 110 Volt Transformer Indenture Level No. 4 ... Commercial Part

Drawing ...

Output specification		Failure Mode	Possible causes	Symptoms-	Effect of	Failure	Existi comp en
functional description	SN	Description	detectability		Local Effect	End Effect	provid
40.1.5 440V to 110V Transformer This 110V transformer supplies the power to operate all control circuits		Burned out or shorted winding	-faulty or overage material -mechanical damage	Relays and starters will not operate	No power to control part of system	Conveyor inoperative	Non-

Contract No.	N00024-72-C-5500	
Organization	KORNYLAK CORPORATION	_
By EN	GINEERING DEPT., KORNYLAK CORP.	

APPROVED: _____ DATE: ____

	Symptoms-	Effect of Failure		Existing compensating	Level of	Failure prob·	Remarks and Recommendations
	detectability	Local Effect	End Effect	provision	Severity	ability	Tiellar X. and Tielenmenter.
	Relays and starters will not operate	No power to control part of system	Conveyor	None	2	1	Rewind or replace faulty transformer.
e a Political de Calendario de La Calendario de Calendario							Page - 77 -

Form No. 276 6

(4)

Indenture Level No. 1 VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2 Control System
Indenture Level No. 3 Controller
Indenture Level No. 4 Speed Relays
Orawing Commercial

Output specification	Failure Mode		Possible causes	Symptoms-	Effect o	Failure	Exis
functional description	SN Description		Possible causes	detectability	Local Effect	End Effect	com pei pr ovi
40.1.6 First Speed Relay 40.1.7 Second Speed Relay 40.1.8 Third Speed Relay	40.1.6.1	Burned out coil	-faulty or overage material -mechanical damage to coil.	Speed selection limited to two remaining speed relays.	Same as end effect	Conveyor limited to two speeds	Use oper speeds remainin
These speed relays are provided so as to make proper selection of speeds from the Controller, they are interlocked in the circuit so that only one can operate at any one time.		Burned or welded contacts	-mechanical damage -overheating of contacts	Speed selec- tion limited to one speed- same as locked in relay	Same as end effect	Conveyor limited to single speed	Use at organism of the speed of

Contract No. N00024-72-C-5500
Organization KORNYLAK CORPORATION
By ENGINEERING DEPT., KORNYLAK CORP.

APPROVED: _____ DATE: ____

	Symptoms-	Effect of	Failure	Existing compensating	Level of	Failure prob-	Remarks and Recommendations
·	detectability	Local Effect	End Effect				usiners and necommendations
	Speed selection limited to two remaining speed relays.	Same as end effect	Conveyor limited to two speeds	Use operable speeds remaining	1	1	keplace coil.
90	Speed selec- tion limited to one speed- same as locked in relay	Same as end effect	Conveyor limited to single speed	Use at one speed only	1	1	Replace contacts or replace relay
A control of the cont							
Commence of the Commence of th							
							Page - 78 -

Form No. 276 6

Indenture Level No. 1 VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2 Control System
Controller
Over-the-door Jam Sensing Relay
Commercial Part

Output specification		Failure Mode	Desible	Symptoms-	Effect o	Effect of Failure	
functional description	SN	Description	Possible causes	detectability	Local Effect	End Effect	pr ov
40.1.7 Over- the-door Jam Sensing Relay The over-the- door Jam Sensing	40.1.9.1	Burned or shorted coil	-mechanical damage -faulty or overage material	No current to motor	Same as end effect	Conveyor inoperative	Nor
Relay is provided to protect the conveyor if a package is out of position such that it would jam between the tray and the door in a strike-up mode.	40.1.9.2	Contacts welded together	-high current -faulty material	None	None	Conveyor operative but does not have over-the- door protection	Torque will tal at 115% full lo torque

Contract No.	N00024-72-C-5500
Organization	KORNYLAK CORPORATION
By EN	GINEERING DEPT., KORNYLAK CORP.

APPROVED: _____ DATE: ____

	Symptoms-	Effect of	Failure	Existing compensating	Level of	Failure prob-	Remarks and Recommendations
	detectability	Local Effect	End Effect	provision	Severity		Hemai ks and Hecollimendations
and the second s	No current to motor	Same as end effect	Conveyor inoperative	None	3	1	Replace faulty coil or replace over-the-door Jam Sensing Relay
t.	None	None	Conveyor operative but does not have over-the- door protection	Torque Limiter will take over at 115% of full load torque	2	1	Replace Over-the-door Jam Sensing Relay
							Page - 79 -

Indenture Level No. 2 VERTICAL CONVEYOR SYSTEM
Control System

Controller Indenture Level No. 3 .

Load/Unloader Interlock Jam Sensing Relay Commercial Part Indenture Level No. 4

Drawing ___

Output specification	Failure Mode		Possible causes	Symptoms-	Effect o	Exi	
functional description	SN	Description	Lozzinie canzez	detectability	Local Effect	End Effect	pro compe
Load/Unloader Interlock Jam Sensing Relay This jam sensing	d	shorted coil	-mechanical damage -faulty or overage mater- ial	No current to motor in down mode	Same as end effect	Conveyor inoperative in down mode	Not
to protect the conveyor in the down direction if any platform is in the horizontal position		Contacts welded together	-high current -faulty material	None	None	Conveyor operative but does not have loader/ unloader protection	Torque will tal at 115% load to

lelay

Contract No. NOOO24-72-C-5500
Organization KORNYLAK CORPORATION
By ENGINEERING DEPT., KORNYLAK CORP.

APPROVE	D:	DATE:	

a Colonia	Symptoms-	Effect of	Failure	Existing compensating	Level of	Failure prob-	Remarks and Recommendations
	detectability	Local Effect	End Effect	provision	Severity		riemai ka amu rieconsimemuationa
	No current to motor in down mode	Same as end effect	Conveyor inoperative in down mode	None	3	1	Replace faulty coil or replace loader/unloader interlock jam sensing relay
Line in the state of the state	None	None	Conveyor operative but does not have loader/ unloader protection	Torque Limiter will take over at 115% of full load torque	2	1	Replace loader/unloader interlock jam sensing relay
d prophetory (Page - 80 -

Form No. 276 6

Indenture Level No. 1 VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2 Control System
Controller
Audio Signal Timer In fonture Level No. 4 Commercial Part

Drawing .

Output specification	Failure Mode		Possible causes	Symptoms-	Effect o	f Failure	Exi
functional description	SN	Description	Possible causes	detectability	Local Effect	End Effect	compe prov
40.1.11 Audio Signal Timer This signal timer in provide to warn users that the conveyor is about to start. The conveyor starts only after the warning signal ceases		-burned or open coil -welded contacts	-faulty material -overage material -mechanical damage	-no warning sound -conveyor will not run	No current to motor	Conveyor	Non

Contract No.	N00024-72-C-5500
Organization	KURNYLAK CORPORATION
By EN	GINEERING DEPT., KORNYLAK CORP.

APPROVED:	 DATE:	

Symptoms-	Effect of Failure		Existing compensating	Level of	Failure prob·	Remarks and Recommendations		
detectability	Local Effect	End Effect	provision	Severity	ability			
-no warning sound -conveyor will not run	Local Effect No current to motor	End Effect Conveyor inoperative	Provision None	2	ability 1	Repair or replace audio signal timer.		
						Page - 81 -		

Form No. 2/6 6

Indenture Level No. 1
Indenture Level No. 2
Indenture Level No. 3
Indenture Level No. 4

VERTICAL CONVEYOR SYSTEM

Control System

Controller Station

Power Off/On Selector Switch

Indenture Level No. 4

Commercial Part Drawing .

Output specification	Failure Mode		Pussible causes	Symptoms-	Effect o	Exid	
functional description	SN	Description	russinie causes	detectability	Local Effect	End Effect	com pe prov
40.2.1 Power Off/On Selector Switch		material -overheating -overage	-Red "Power On" light does not lightNo power to control circuit		Conveyor inoperative	Noi	
This switch is provided to turn on main control power.			-over usage				,
							•
							!
							:
							:

Contract No. N00024-72-C-5500
Organization KORNYLAK CORPORATION
By ENGINEERING DEPT., KORNYLAK CORP.

APPROVED: _____ DATE: ____

-Red "Power No power to Conveyor None 3 1 Replace power off/on switch. On" light does motor inoperative not lightNo power to		Symptoms- Effect of		f Failure	Existing compensating	Level of	Failure prob-	Remarks and Recommendations
On" light does motor inoperative not light. -No power to	,	detectability	Local Effect End Effect		provision		ability	Mellia ky and Merchillisina(i01)2
Page - 82 -		On" light does not lightNo power to	motor			3	1	

Form No. 276 6

Indenture Level No. 1
Indenture Level No. 2
Indenture Level No. 3
Indenture Level No. 4
Orawing

VERTICAL CONVEYOR SYSTEM

Control System

Controller Station

Three-position Speed Selector Switch

Commercial Part

Output specification	Failure Mode		Possible causes	Symptoms-	Effect o	l Failure	Exi
functional description	SN	Description	1 0331810 048303	detectability	Local Effect	End Effect	bro/ combe
40.2.2 Three- position Speed Selector Switch This switch is provided for	40.2.2.1	Burned or worn contacts in one position		One speed range is inoperable	Same as end effect	Conveyor operates in two speeds only.	Use op e speed s
speed selection depending on skill of operating crew and the desired transfer rate.		Burned or worn contacts in two positions	-Faulty material -Mechanical damage -Overheating -Overage material	Two speed ranges are inoperable	Same as end effect	Conveyor operates on one speed only	Use r em workin g
	40.2.2.3	Burned or worn contacts in all positions.	-Faulty material -Mechanical damage -Overheating -Overage material	All speeds are inoperable	No power to motor	Conveyor inoperative	No

Contract No.	N00024-72-C-5500
Organization	KORNYLAK CORPORATION
By EN	GINEERING DEPT., KORNYLAK CORP.

APPROVED: _____ DATE: ____

	Symptoms-	Effect of Failure		Existing compensating	Level of	Failure prob-	Remarks and Recommendations		
	detectability	Local Effect	End Effect	provision	Severity		Titing to and Title giftine markets		
4	One speed range is inoperable	Same as end effect	Conveyor operates in two speeds only.	Use operational speeds		1	Replace faulty speed selection switch.		
	Two speed ranges are inoperable	Same as end effect	Conveyor operates on one speed only	Use remaining working speed.	2	1	Replace faulty speed selection switch.		
	All speeds are inoperable	No power to motor	Conveyor inoperative	None	4	1	Replace faulty speed selection switch.		
							Page - 83 -		

Indenture Level No. 1 VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2 Controller Station
Indenture Level No. 3 Power On Light "Red"

Drawing Commercial Part

Output specification		Failure Mode	0.44	Syniptems-	Effect o	f Failure	Existi
functional description	SN	Description	Possible causes	detectability	Local Effect	End Effect	compens provisi
40.2.3 Power On Light "Red" This light indicates that the 110V and 440V power are on to the conveyor		Burned out bulb.	-Lack of	detectability Red light does not come on to indicate readiness	Same as end	Operating status is not known to operating personnel	previsi None

Contract No. N00024-72-C-5500
Organization KORNYLAK CORPORATION
By ENGINEERING DEPT., KORNYLAK CORP.

APPROVED: _____ DATE: ____

a a indiana	Symptoms-	Effect of	Failure	Existing compensating	Level of	Failure prob·	Remarks and Recommendations	
الم	detectability	Local Effect	End Effect	provision	Severity	ability		
ومستفلاتين	Red light does not come on to indicate readiness	Same as end	Operating status is not known to operating personnel	None	1	1	Check wiring - replace bulb or replace power-on red light.	
							Page - 84 -	

Form No. 276 6

Indenture Level No. 1 VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2 Control System
Controller
Identure Level No. 3 Emergency Run Switch

Drawing							····
Output specification	Failure Mode		Possible causes	Symptoms-	Effect	of Failure	Ex
functional description	SN	Description	LASSINIC CONSES	detectability	Local Effect	End Effect	pre
The emergency run switch is provided which overrides the overload controls	40.2.4.1	Emergency run switch locks in	Burned contact	s None	None	If conveyor should jam motor may buin out due to overheating without protection	will tal if torq reaches normal
	40.2.4.2	Emergency run switch does not make contact	Mechanical damage	Detectable only if IOL or thermal overload cut out need to be bypassed	None	IOL and thermal overload control cannot be passed in case of emergency	No

Contract No.	N00024-72-C-5500
Oceanization	KORNYLAK CORPORATION
By EN	GINEERING DEPT., KORNYLAK CORP.

						APPRO	VED: DATE:
	Syniptoms-	Effect	of Failure	Existing compensating	Level of	Failure prob-	Remarks and Recommendations
ار زندین	detectability	Local Effect	End Effect	provision	Severity	abikty	
act	s None	None	If conveyor should jam motor may burn out due to overheating without protection	Torque Limiter will take over if torque reaches 115% of normal	2	1	Normal jam conditions would be detected by jam switches which would still be operable. This would have to be a jam of rare or unusual origin, before emergency run switch would be suspected
manasse, vilidaudian, nichte demissans das de sentis den distribuir de distribuir de la dis	Detectable only if IOL or thermal overload cut out need to be bypassed	None	IOL and thermal overload control cannot be passed in case of emergency	None	1	1	Remove cause of IOL and thermal overload cut out then replace emergency run switch
their many series and the							Page - 85 -

Farm No. 276 6

ndenture Level No. 2 Control System Intermediate Station Orawing Conmercial Part Failure Mode			: - T		Effect of Failure				
Output specification functional description	SN	Description	Possible causes	Symptoms- detectability	Local Effect	End Effect	pro comp		
Chis light is crovided to dvise operating that conveyor is ready to run at all other stations.		Burned out bulb Loose wire Faulty socket	-Lack of maintenance -Excessive -ibration -Overage material	Light does not come on to indicate readiness	Same as end effect	Operational status is not known to crew	Crew m call to with o statio readin equipm		

Contract No. NOOD24-72-C-5500
Organization KORNYLAK CORPORATION
By ENGINEERING DEPT., KORNYLAK CORP.

APPROVED: _____ DATE: ____

0 5	Symptoms-	Effect of	Failure	Existing compensating	Level of	Failure prob-	Remarks and Recommendations
2.2	detectability	Local Effect	End Effect	provision	Severity	ability	vellares and vecommendations
	Light does not come on to indicate readiness	Same as end effect	Operational status is not known to crew	Crew member can call to or check with other stations for readiness of equipment.		1	Check wiring - replace bulb or replace power-on light.
	,					ļ	Page - 86 -

Form No 276 6

Indenture Level No. 1 VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2 Control System
Intermediate Station

Indenture Level No. 3 _ Stop Push-On Pull (Red Light on Stop) Commercial Part In 'nture Level No. 4 __

Drawing _

Output specification	Failure Mode		Possible causes	Symptoms-	Effect o	Exis	
functional description	SN	Description	Possible causes	detectability	Local Effect	End Effect	comp e pr ov
40.3.2 "Stop Push/On Pull" (Red Light on Stop) In the "Pull- On" Position this switch	40.3.2.1	Burned contacts Worn contacts	-Overheating -Faulty material -Overage material	Conveyor will not run when up or down switch are activated	Same as end effect	Conveyor inoperative (all stations must be set to on "on")	N
activates the conveyor circuit and allows up or down motion. In the "Push-Stop" position this switch deactivates the circuit and stops te conveyor.	40.3.2.2	Contacts welded together	-Overheating -Faulty material -Overage material	Conveyor always on in subject station (No red light in stop position)	Same as end effect	Conveyor operation cannot be stopped at subject station	N

Contract No.	N00024-72-C-5500	
Organization	KORNYLAK CORPORA	TION
By EN	GINEERING DEPT., K	DRNYLAK CORP.

APPROVED:	 DATE:	

	Symptoms-			Existing compensating	Level of	Failure prob-	Remarks and Recommendations
	detectability	Local Effect	End Effect	provision	Severity	ability	(Tentarias and Theodillinonias), ons
Note that we have the second	Gonveyor will not run when up or down switch are activated	Same as end effect	Conveyor inoperative (all stations must be set to on "on")	None	4	1	Verify switch condition. Replace "Stop Push-On Pull" button in faulty station.
	Conveyor always on in subject station (No red light in stop position)	Same as end effect	Conveyor operation cannot be stopped at subject station	None	4	1	Replace "Stop Push-On Pull" button in faulty station.
							Page - 87 -

Indenture Level No. 1
Indenture Level No. 2
Indenture Level No. 3
Indenture Level No. 4
Drawing

Drawing

VERTICAL CONVEYOR SYSTEM

Control System
Intermediate Station
Up/Down Push Buttons
Commercial Part (s)

Output specification		Failure Mode	Possible causes	Symptoms-	Effect of	Failure	Exic compe
functional description	SN	Description	e Assinic Censes	detectability	Local Effect	End Effect	prov
40.3.3 40.3.4 "Up" Push Button "Down" Push Button		Burned or worn contacts	-Faulty material -Overheating -Overage material	Conveyor will not operate in one direction	Same as end effect	Conveyor operates in one direction only	No
This conveyor motion up or down push button is provided for selecting the direction of travel	40.3.3.2	Contacts welded together	-Overheating -Faulty material	Conveyor locked in to one run direction	Same as end effect	Conveyor operates in one direction as soon as "C. Full" switch is activated	N

Contract No. N00024-72-C-5500
Organization KORNYLAK CORPORATION
By ENGINEERING DEPT., KORNYLAK CORP.

APPROVED:	 DATE:	
,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	 W/7 1 1 1 1 1	

	Symptoms-	Effect of Failure		Existing Level compensating of	Failure prob-	Remarks and Recommendations	
	detectability	Local Effect	End Effect	provision	Severity		nemarks and necommendations
Annual refusive Marketonia - a refusi	Conveyor will not operate in one direction		Conveyor operates in one direction only	None	3	1	Replace faulty "Up" or "Down" push button
	Conveyor locked in to one run direction	Same as end effect	Conveyor operates in one direction as soon as "On Pull" switch is activated	None	3	1	Replace faulty "iJp" or "Down" push button
							Page - 88 -

Form No. 2/6 6

Indenture Level No. 1 VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2 Safety Devices
Indenture Level No. 3 Instantaneous Overload (TOL)

Indenture Level No. 3

Indenture Level No. 4

Commercial Part

Output specification	í	Failure Mode	Oith	Symptoms-	Effect o	f Failure	Exi
functional description	SN	Description	Possible causes	detectability	Local Effect	End Effect	bt er com be
50.1 Instantaneous Overload (IOL)				- * *			
See Remarks Column							
							20 C C C C C C C C C C C C C C C C C C C
							:
							-

Contract No. NOO024-72-C-5500
Organization KORNYLAK CORPORATION
By ENGINEERING DEPT., KORNYLAK CORP.

APPROVED:	 DATE:	

Symptoms-	Effect of Failure		Existing compensating	Level of	Failure prob-	Remarks and Recommendations
detectability	Local Effect	End Effect	provision	Severity	ability	remarks and recommendations
			*** **	7		This item is analyzed as part of the control system as element number 40.1.3
						Page - 89 -

Indenture Level No. 1	VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2	Safety Devices
Indenture Level No. 3	Thermal Overload
Indenture Level No. 4	
Drawing	Commercial Part

Output specification	1	Failure Mode	Possible causes	Symptoms-	Effect of	Failure	Ех
functional description	SN	Description	Possible Causes	detectability	Local Effect	End Effect	comp pre
50.2 Thermal Overload	 -						
See Remarks Column							

ontract No.	N00024-72-C	-5500	
)rganization	KORNYLAKCI	DRPORATION	
y EN	GINEERING DE	PT., KORNYLAK	CORP.

APPROVED:	 DATE:	
A	 2012.	

es	Symptoms-	Effect of Failure		Existiny Level compensating of		Remarks and Recommendations			
	detectability	Local Effect	End Effect	provision	Severity	ability			
The state of the s							This item is analyzed as part of the control system element number 40.1.2		
The second secon									
							Page - 90 -		

Indenture Level No. 1 VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2 Safety Devices
Indenture Level No. 3 Audio Signal
Indenture Level No. 4

Orawing

Output specification functional description	Failure Mode		0	Symptoms-	Effect of	Exis	
	SN	Description	Possible causes	detectability	Local Effect End Effect		comp e pr ovi
50.3 Audio Signal The audio signal sounds off at each level to warn personnel	50.3.01	Sounding coil shorted out	-electrical damage -high current	Low volume or no sound	Same as end effect	Conveyor operative however it has no start-up signal	Non
-	50.3.02	Sounding coil open	Electrical damage	No sound	Same as end effect	Conveyor operative however it has no start-up signal	Non
starts	50.3.03	Diaphram ruptured	-mechanical damage -faulty or overage material	Distorted or inaudible sound	Same as end effect	Conveyor operative but has no clear start up signal	Not

Contract No.	N00024-72-C-5500
Organization	KORNYLAK CORPORATION
By EN	GINEERING DEPT., KORNYLAK CORP.

APPROVED:	 DATE:	
/11 1 110		

Service and	Symptoms-	Effect of	Failure	Existing compensating		Failure prob-	Remarks and Recommendations		
الله وتسلته الأسا	detectability	Local Effect End Effect		compensating of provision Severi					
t and the second	Low volume or no sound	Same as end effect	Conveyor operative however it has no start-up signal	None	1	1	Repair or replace horn		
	No sound	Sam · as end effect	Conveyor operative however it has no start-up signal	None	1	1	Repair or replace horn		
	Distorted or inaudible sound	Same as end effect	Conveyor operative but has no clear start up signal	None	1	1	Repair or replace horn		
							Page - 91 -		

Form No. 276 6

Indenture Level No. 1	VERTICAL CONVEYOR SYSTEM Sarety Devices
Indenture Level No. 2 Indenture Level No. 3	Brake
Indenture Level No. 4	
Drawing	Commercial Part

Output specification	Failure Mode		Possible gauses Symptoms-	Effect of Failure		Exi	
functional description	SN	Description	Possible causes	detectability	Local Effect	End Effect	pr evi comp e
50.4 Brake				**			
See Remarks Column							

Contract No. N00024-72-C-5500
Organization KORNYLAK CORPORATION
By ENGINEERING DEPT., KORNYLAK CORP.

APPROVED:	 DATE:	

T. A.	Symptoms-	Effect n	l Failure	Existing compensating	Level	Failure	
No. of the	detectability	Local Effect	End Effect	htosision	Severity	prob- ability	Remarks and Recommendations
With the state of		LOCALETICAL	ENG EJJECT	provision			This item is analyzed as part of the drive system element number 10.5
							Page - 92 -

Indenture Level No. 1 VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2 Safety Devices
Indenture Level No. 3 Bottom Overtravel Limit Switch

Indenture Level No. 4 __

Drawing Commercial Part

functional description SN Description Des	Output specification	Failure Mode		Possible causes	Symptoms-	Effect o	Ex- comp	
Travel Limit Switch 50.5.01 travel limit switch locked open 50.5.02 Bottom limit switch locked closed This bottom overtravel limit switch senses and prevents packages from passing through, it operates on strike down only 50.5.02 Bottom limit switch damaged -poor contacts -bottom limit switch is not damaged capable of damaged -capable of detecting and stopping -locked actuator -damaged contacts spring -damaged contact spring -damaged contact spring -damaged contact spring -damaged contact spring -damaged contact spring -damaged contact spring -damaged contact spring -damaged contact spring -damaged -poor contacts -bottom limit switch is not capable of detecting and stopping -locked -conveyor in down travel -damaged -conveyor in down travel -damaged -poor contacts -poor contacts -bottom limit switch is not capable of detecting and stopping -locked -poor contacts -poor contacts -bottom limit switch is not capable of detecting and stopping -locked -poor contacts -poor contact -poor contacts -poor contact -poor contact -poor contact -poor contact -poor	functional description	SN	Description	Lossible canses		Local Effect	End Effect	pr
overtravel limit switch locked closed switch senses and prevents packages from passing through, it operates on strike down only switch locked switch is not capable of damaged capable of detecting and contacts stopping conveyor in down travel is increased torque significant y contact spring jammed	Travel Limit		travel limit switch locked	switch damaged	inoperative in down			Ne
	overtravel limit switch senses and prevents packages from passing through, it operates on strike down		switch locked	switch damaged -welded contacts -locked actuator -damaged	switch is not capable of detecting and stopping conveyor in down travel even with a jammed	may jam without	operative in down travel but the poten- tial to jam is increase	torqu

Con	tract No.	N00024-7	2·C·550	0		
Ora	anization	KORNYLAN	CORP	DRATION		_
By	EN	GINEERING	DEPT.	, KORNYL	AK CORP.	

APPROVED:	 DATE:	
MI 1 110 1 ED.	U/11-	

	Symptoms-	Effect of	Failure	Existing compensating	Level of	Failure prob·	Remarks and Recommendations
	detectability	Local Effect	End Effect	provision	Severity	ability	esements and esecutiones periods
nit	Conveyor inoperative in down travel	Same as symptom		None	4	1	Correct cause of problem at bottom of conveyor. Replace bottom over-travel limit switch
ring	Bottom limit switch is not capable of detecting and stopping conveyor in down travel even with a jammed package	Package may jam without protection	Conveyor operative in down travel but the poten- tial to jam is increase significant		2	1	Remove cause of limit switch damage. Replace bottom over-travel switch. Page - 93 -
				<u> </u>	<u></u>		•••
			18)			Form No 276-6

Indenture Level No. 1 VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2 Safety Devices
Indenture Level No. 3 Loader/Unloader Interlock
Indenture Level No. 4

Drawing Commercial Part

Output specification	Failure Mode		Possible causes	Symptoms-	Effect o	Exi	
functional description	SN	Description	Possible causes	detectability	Local Effect	End Effect	com p i
50.6 Loader/ Unloader Interlock	50.6.01	Loader/Unloader interlock switch is locked open	-limit switch damaged -poor contacts	Conveyor is inoperative in down travel		Same as symptom	No
The Loader/ Unloader inter- lock prevents strike down operation should the Loader/ Unloader be in horizontal position instead of the tilted unload position- operates during strike down.		Loader/Unloader interlock switch is locked in closed position	-limit switch damaged -welded contacts -locked actuator -damaged contact spring	Loader/Unloade switch is not capable of detecting that Loader/ Unloader is in horizontal position and cannot prevent down travel.	may jam without protection	Conveyor operative however the possibility of a jam in down travel is significantly increased.	

Contract No. NO0024-72-C-5500
Organization KORNYLAK CORPORATION
By ENGINEERING DEPT., KORNYLAK CORP.

APPROVED: _____ DATE: _

Standard and	Symptoms-	Effect o	f Failure	Existing compensating	Levei	Failure	Remarks and Recommendations
s. abrigado	detectability	Local Effect	End Effect	provision	Severity	prob- ability	Hemarks and Necommendations
tch	Conveyor is inoperative in down travel	~	Same as symptom	None	4	1	Correct cause of problem at Loader/Unloader interlock. Replace Loader/Unloader interlock switch.
ch	Loader/Unloade switch is not capable of detecting that Loader/ Unloader is in horizontal position and cannot prevent down travel.	may jam without protection	Conveyor operative however the possibility of a jam in down travel is significantly increased.	Torque Limiter will take over if jam creates a torque of 115% of full load torque.	2	1	Remove cause of limit switch damage. Replace Loader/Unloader interlock switch
ir.		<u></u>	1.		L		Furm No. 276-6

Indenture Level No. 1 VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2 Safety Devices
Indenture Level No. 3 Loader/IInloader Jam Sensing Switch

Indenture Level No. 4 __

Drawing Commercial Part

ecification	Failure Mode			Symptoms-		f Failure	Exis
description	SN	Description	Possible causes	detectability	Local Effect	End Effect	com pe pr ev
der/ Jam Switch der/ Jam Switch	50.7.01	Loader/Unloader Jam Sensing switch is locked open	-limit switch damaged -bad contacts	Conveyor is inoperative in down travel		Same as symptom	Non
should oming ike a not ly after age has d the nloader t	50.7.02	Loader/Unloader Jam Sensing Switch is locked closed	-limit switch damaged -welded contac -locked actuator -damaged contact spring	switch is not capable of detecting a	Package may jam without protection	Conveyor operative but the propensity to jam is increased significantly	Torque i will tall if jam da torque 115% of load to

Contract No.	N00024-72-C-5500
Organization	KORNYLAK CORPORATION
By EN	GINEERING DEPT., KORNYLAK CORP.

APPROVED:	 DATE:	
ATTHORED.	 DITTE.	

	Symptoms-	Effect of	Faiture	Existing compensating	Level	Failure prob-	Remarks and Recommendations
jš	detectability	Local Effect	End Effect	provision	Severity		
	Conveyor is inoperative in down travel		Same as symptom	None	4	1	Correct cause of problem at Loader/Unloader jam sensing switch. Replace Loader/Unloader jam sensing switch
ntac	Loader/ Unloader jam sensing switch is not capable of detecting a package not completely ejected from Loader/ Unloader	Package may jam without protection	Conveyor operative but the propensity to jam is increased significantly	Torque Limiter will take over if jam creates a torque of 115% of full load torque	2	1	Remove cause of Loader/ Unloader Jam Sensing Switch damage. Replace Loader/ Unloader Jam Sensing Switch.
بالحالكيس وكالكمان							Page - 95 -

Form No 276 6

Indenture Level No. 1	VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2	Safety Devices
Indenture Level No. 3	Top Overtravel Limit Switch
Indenture Level No. 4	
Atawina	

Output specification	Failure Mode		Possible causes	Symptoms-	Effect of	Ex	
functional description	SN	Description	Possible Causes	detectability	detectability Local Effect End E		bta could
50.8 Top Over- travel Limit Switch	50.8.01	Top Overtravel Limit Switch lockec open	-top limit switch damaged poor contacts	Conveyor inop- erative in "up" travel	Same as symptom		No
This top over- travel limit switch prevents packages from passing through and jamming at the top of the conveyor. Operates on strike up only.	50.8.02	Top Overtravel Limit Switch locked closed	-top limit switch damaged -welded contacts -locked actuator -damaged contact spring	Top overtravel limit switch is not capable of detecting and stopping conveyor in "up" travel even with a package in the jam position	jam without protection		Torque will taif jam a torque 115% of load to

Contract No. N00024-72-C-5500
Organization KORNYLAK CORPORATION
By ENGINEERING DEPT., KORNYLAK CORP.

APPROVED: _____ DATE: ____

	Symptonis-	Effect of	Failure	Existing compensating	Level of	Failure prob-	Remarks and Recommendations
	detectability	Local Effect	End Effect	provision	Severity		
acts	Conveyor inop- erative in "up" travel	Same as symptom	~~~	None	4	1	Correct cause of problem at top of conveyor. Replace top overtravel limit switch.
CCC	Top overtravel limit switch is not capable of detecting and stopping conveyor in "up" travel even with a package in the jam position	jam without protection		Torque Limiter will take over if jam creates a torque of 115% of full load torque	2	1	Correct cause of problem. Replace top overtravel limit so itch.
الله ومداره إلى أكد مداره إن							Page - 96 -

Form No 216 6

Inderture Level No. 1 VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2 Safety Devices
Indenture Level No. 3 Over-the-door Jam Sensing Switch

Indenture Level No. 3 __

Indenture Level No. 4 ..

Commercial Part Drawing _

Output specification	Failure Mode SN Description		Possible causes Symptoms- detectability		Effect of Failure		Exi
functional description					Local Effect	End Effect	bre combi
50.9 Over-the- door Jam Sensing Switch	50.9.01	Over-the-door jam sensing switch locked open	-door jam switch damaged -poor contacts	Conveyor inoperative in both direction		Same as symptom	Not
This over-the- door jam sensing switch stops the conveyor if activated by a mislocated package prevents a jam between the tray and the upper door coaming.	50.9.02	Over-the-door jam sensing switch locked closed	-door jam. switch damaged -welded contac -locked actuator -damaged contact spring	detecting and stopping conveyor in up or down	Package may jam without protection		Torque will talif a jalif a torque 115% of load to

Contract No. N00924-72-C-5500
Organization KORNYLAK CORPORATION
By ENGINEERING DEPT., KORNYLAK CORP.

APPROVED:	. DATE:	
-----------	---------	--

	Symptoms-	Effect of	Failure	Existing compensating	Level of	Failure prob-	Remarks and Recommendations
	detectability	detectability Local Effect End Effect		provision Severity ability		•	
cts	Conveyor inoperative in both direction		Same as symptom	None	4	1	Correct cause of problem. Replace over-the-door jam sensing switch.
ntac	Switch is not capable of detecting and stopping conveyor in up or down travel with a jammed package	Package may jam without protection		Torque Limiter will take over if a jam creates a torque of 115% of full load torque.	2	1	Remove cause of limit switch damage. Replace over-the-door jam sensing limit switch.
the table tradition of the design of the table of							Page - 97 -

Form No. 276-6

Indenture Level No. 1	VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2	Safety Devices
indenture Level No. 3	Torque Limiter
Indenture Level No. 4	
Drawing	Commercial Part

Output specification	Failure Mode		Possible causes Symptoms-	Effect v	Exist		
functional description	SN	Description	Possible causes	detectability	Local Effect	End Effect	compen provid
50.10 Torque Limiter							
See Remarks Column							
							Spire was a supple of the supp
							e de de la companya d
							e order ede over
							And the second s

Contract No.	N00024-72-C-5500
Organization	KORNYLAK CORPORATION
By EN	GINEERING DEPT., KORNYLAK CORP.

				APPHU	VEU: DATE:
Effect of	Failure	Existing compensating	Level	Failure arab	Remarks and Recommendations
Local Effect	End Effect	compensoring	Sameira		nemeral and recommensations

Secretaria de la composição de la compos	Symptoms-	ability Local Effect End Effect		Existing compensating	Level of	Failure prob-	Remarks and Recommendations
d Dec	detectability			provision	Severity	ability	
							This item analyzed as part of the drive system as element number 10.3
edusalistikas e život kiduskastači i s om.							Page - 98 -

Form No. 276 6

Indenture Level No. 1 VERTICAL CON VEYOR SYSTEM
Indenture Level No. 2 Ioad/Unload Devices
Indenture Level No. 3 Indenture Level No. 3 __ Indenture Level No. 4 __ 2-1026-51F

Drawing _

Output specification	Failure Mode		Possible causes	Symptoms-	Effect of	Effect of Failure		
functional description	SN	Description	Possible causes	detectability	Local Effect	End Effect	com p i pr o l	
The platform is the device which is used to position the loads for pick off in the up mode or extract loads in the down mode	50.1.01	Platform is not readily positioned between brackets	Improper clearance between brackets	Difficult to move from stowed position to load position and/or unload	ļ	Nuisance factor		

Contract No. N00024-72-C-5500
Organization KORNYLAK CORPORATION
By ENGINEERING DEPT., KORNYLAK CORP.

APPROVED.	 DATE:	

Symptoms-	Effect of	Failure	Existing compensating	Level of	Failure prob-	Remarks and Recommendations
 detectability	Local Effect	End Effect	provision	Severity	ability	remarks and recommendations
Difficult to move from stowed position and/or unload	Difficult to put into n use	Nuisance factor	None	2	1	Replace shim washer to get proper clearance
						Page - 99 ~

Form No. 2/6-6

Indenture Level No. 2 Load/Unload Devices
Indenture Level No. 3 Mounting and Stowing Bracket R.H. and L.H.

Indenture Level No. 4 _

Drawing 2-1026-52F/2-1026-53F

Output specification	Failure Mode		Possible causes	Symptoms-	Effect o	f Failure	Existi
functional description	SN	Description	Lossinia canses	detectability	Local Effect	End Effect	comp e nt provis
60.2 Mounting and Stowing Bracket R.H. 60.3 Mounting and Stowing Bracket L.H.	60.2.01 60.3.01	Bent bracket	External damage	Impossible or difficult to position platform in load and/or unload positions	Limited direction travel	No down travel if not able to place in unload position	Note:
Supports the platform in various positions							रेशुलाकारम् महामान्यस्य सम्बद्धाः सम्बद्धाः स्टब्स्टरस्टन्स्टरस्टन्स्टरस्ट
							فيالي المرفولية وكالمتابع الثانية والتابية ويترامون مستواهما كالمتابعة للمتات
							PICEP POR PROGRAME SETTE (ANCHORUMES CONTRACTOR OF

ь́н.

Contract No. NOOO24-72-C-5500
Organization KORNYLAK CORPORATION
By ENGINEERING DEPT., KORNYLAK CORP.

APPROVED: _____ DATE: ____

فيتأمسنا	Symptoms-	Effect o	f Failure	Existing compensating	Level	Failure prob-	Remarks and Recommendations
واستعدا	detectability	Local Effect	End Effect	provision	Severity		Demarks and Decommendations
では、かけているできないが、これのでは、ないないできないが、これでは、これでは、これでは、これでは、これでは、これでは、これでは、これでは	Impossible or difficult to position platform in load and/or unload positions	Limited direction travel	No down travel if not able to place in unload position	None	4	1	Remove pivot studs. Remove platform straighten brackets. Re-assemble platform.

Form No. 216 6

Indenture Level No. 1 VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2 Load/Unload Devices
Indenture Level No. 3 Platform Depress Mechanism R. H. and L. H.

Indenture Level No 4
Orawing

2-1026-P10F

0

F	ailure Mode		Symptoms-	Effect of	Failure	Existin comp ens
SN	Description	Possible causes	detectability	Local Effect	End Effect	provis
60.4.01 60.5.01	Binding of guide shaft in guide plate slide	Wear	finger cannor be depressed	not depress to open down travel	travel circuit still engaged there is no	
60.4.02	Binding in guide plate slide	Wear	Platform finger cannot be depressed	Platform will not depress to open down travel circuit		
		f Wear	Loss of sprin	gCannot position unloader	No down travel	N
		Wear	of platform	reaction du	for	N.
	60.4.01 60.5.01 60.4.02 60.5.01 60.4.03 60.5.03 60.5.03	SN Description 60.4.01 Binding of guide shaft in guide plate slide 60.5.01 Binding in guide plate slide 60.5.01 Pins work out o connecting arms 60.4.04 Pivot block holes are oversize	SN Description 60.4.01 Binding of guide shaft in guide plate slide 60.5.01 Binding in guide plate slide 60.5.01 Pins work out of connecting arms 60.4.03 Pivot block holes are oversize	SN Description 60.4.01 Binding of guide shaft in guide plate slide 60.4.02 Binding in guide plate slide 60.5.01 Pins work out of 60.5.03 Connecting arms 60.4.04 Pivot block holes are oversize Possible causes detectability Wear Platform finger cannot be depressed Loss of springer cannot be depressed Sensing trave of platform is increased	SN Description Binding of guide shaft in guide plate slide Wear 60.4.02 Binding in guide plate slide Binding in guide plate slide Wear 60.5.01 Fins work out of connecting arms 60.4.03 Fins work out of connecting arms 60.4.04 Pivot block holes are oversize Possible causes Wear Platform finger cannot be depressed Platform finger cannot be depressed Platform finger cannot be depressed Symptoms Local Effect Local Effect Local Effect Platform finger cannot be depress to open down travel circuit Platform finger cannot be depressed Sensing travel Slower reaction duto the increased sensing movement required	SN Description 60.4.01 Binding of guide shaft in guide plate slide 60.4.02 Binding in guide plate slide 60.5.01 Binding in guide plate slide 60.4.02 Binding in guide plate slide 60.5.01 Binding in guide plate slide 60.5.01 Binding in guide plate slide 60.5.01 Binding in guide plate slide 60.5.01 Binding in guide plate slide 60.5.01 Binding in guide plate slide 60.5.01 Binding in guide plate slide 60.5.01 Binding in guide plate slide 60.5.01 Binding in guide plate slide 60.5.01 Binding in guide plate slide 60.5.01 Binding in guide plate slide Flatform will with down travel circuit still engaged there is no jam protection in down mode Flatform will with down travel circuit still engaged there is no jam protection in down mode Flatform will with down travel circuit still engaged there is no jam protection in down mode Flatform will with down travel circuit still engaged there is no jam protection in down mode Flatform will with down travel circuit still engaged there is no jam protection in down mode Flatform will with down travel circuit still engaged there is no jam protection in down travel circuit still engaged there is no jam protection in down travel circuit still engaged there is no jam protection in down travel circuit still engaged there is no jam protection in down travel circuit still engaged there is no jam protection in depress to open down travel circuit still engaged there is no jam protection in depress to open down travel circuit still engaged there is no jam protection in down travel circuit still engaged there is no jam protection in down travel circuit still engaged there is no jam protection in down travel circuit still engaged there is no jam protection in down travel circuit still engaged there is no jam protection in down travel circuit still engaged there is no jam protection in down travel circuit still engaged there is no jam protection in down travel circuit still engaged there is no jam protection in down travel circuit still engaged there is no jam protection in do

Contr	act No.	N00124	4-72-C-	5500			_
Organ	ization	KORNY	LAK CO	RPORAT	ION		_
Ву	EN	GINEERI	NG DEF	T., KO	RNYLAK	CORP.	

APPROVED: _____ DATE: ____

and the factor	Symptoms-	Effect of	Failure	Existing compensating	Level	Failure prob-	Remarks and Recommendations	
أووت كالماء	detectability	Local Effect	End Effect	provision	Severity		itematics and trecommendations	
	_	Platform wil not depress to open down travel circuit	I With down travel circuit still engaged there is no jam protection in down mode	None	4	1	Dis-assemble guides. Replace worn guide shaft.	
No. and the second of the seco	firger cannot be depressed	Platform will not depress to open down travel circuit	With down travel circuit still engaged there is no jam protect ion in down mode	None	4	1	Remove guides - replace worn ''le guides	
	-	Cannot position unloader	No down travel	None	4	1	Replace pins in connecting arm - replace connecting arm	
	is increased	Slower reaction due to the increased sensing movement required	Nuisance shut down for adjustment	None	1	1	Adjust bolt on shifter arm	
		-					Page - 101 - - continued -	

Form No. 276 6

Indenture Level No. 1 VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2 Load/Unload Devices (page -2-)
Indenture Level No. 3 Platform Depress Mechanism R.H. and L.H. (cont'd) Indenture Level No. 3 .

Indenture Level No. 4

2-1026-P10F Drawing .

ailure Mode	Possible causes	Symptoms-	Effect of	Exi	
Description	Possible causes	detectability	Local Effect	End Effect	com pe
		- cont	inued -		
Worn pivot arm bushing	Wear	Slight loss of spring pressure	Increased sensitivity to smaller loads	Nuisance shut down for adjustment	N
	-fatigue -faulty material	Unable to raise plat- form from load to unload position	If platform is not in unload position there can be no down travel	No down travel	
ı.	Description Worn pivot arm bushing	Possible causes Description Wear bushing Broken spring -fatigue -faulty	Possible causes Description Possible causes Symptoms- detectability - cont Slight loss of spring pressure Broken spring -fatigue -faulty material form from load to unload	Description Possible causes Continued - Continued - Slight loss of Increased sensitivity pressure Broken spring -fatigue -faulty material Possible causes Unable to raise plation form from unload position unload position be no down	Description Possible causes Continued - Continued -

H. (cont'd)

Contract No. NOO024-72-C-5500
Organization KORNYLAK CORPORATION
By ENGINEERING DEPT., KORNYLAK CORP.

APPROVED:	DATE:	
WILLIAM PR.	 DUIL	

S. Barrer	Symptoms-	Effect of	Failure	Existing compensating	Level	Failure prob-	Remarks and Recommendations
	detectability	Local Effect	End Effect	provision	Severity		nemarks and neconstituendacions
فريون وتواصيا وعا	- cont	inued -					
والمراجعة المستركين والمراجعة والمراجعة والمراجعة والمراجعة والمراجعة والمراجعة والمراجعة والمراجعة	Slight loss of spring pressure	Increased sensitivity to smaller loads	Nuisance shut down for adjustment	None	1	1	Adjust spring pressure
	raise plat- form from	If platform is not in unload position there can be no down travel	No down travel	Fione	4	1	Replace broken spring. Adjust linkage and spring pressure to suit
							Page - 102 -

Form No. 276-6

Indenture Level No. 1	VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2	Load/Unload Devices
Indenture Level No. 3	Cross Shaft
Indenture Level No. 4	
O	2-1026-54F

Output specification		Failur e Mode	Possible causes	Symptoms-	Effect of	Eg Menoo	
functional description	SN	Description	LOssible canses	detectability	Local Effect	End Effect	pr
60.6 Cross Shaft Links two sides together to maintain parallelism. Gives platform support on both sides	60.6.01	Loose coupling	Vibration	-coupling visably loose -looseness of stub shaft -loss of spring pressure	Guides will not lock into unload position	-platform would cock or jam -would not reach unload position -no down mode operation	

Contract No.	N00024-72-C-5500
Organization	KÖRNYLAK CORPORATION
By EN	GINEERING DEPT., KORNYLAK CORP.

APPROVED:	 DATE:	

Symptoms-	Effect of			Failure prob-	Remarks and Recommendations	
detectability	Local Effect	End Effect	provision	Severity	ability	***************************************
-coupling visably loose -looseness of stub shaft -loss of spring pressure	Guides will not lock into unload position	-platform would cock or jam -would not reach unload position -no down mode operation	None	4	1	Place platform in load position. Re-position stub shaft and levels. Tighten coupling.
						Page - 1.1, -

Form No. 276-6

Indenture Level No 1	VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2	Load/Unload Devices
Indenture Level No. 3	Interlock Micro-Switch
Indenture Level No. 4	Communatal Part

Output specification	Failure Mode		Possible causes Symptoms-	Effect o	Exist		
functional description	SN	Description	Possible causes	detectability	Local Effect	End Effect	provil
60.7 Interlock Micro-Switch							~ ~
See Remarks Column							e de de la completa de la completa de la completa de la completa de la completa de la completa de la completa d
							स्त्री प्राप्तिक हैं हैं है है है है है है है है है है है है है

Contract No. NOO024-72-C-5500
Organization KORNYLAK CORPORATION
By ENGINEERING DEPT., KORNYLAK CORP.

APPROVED: _____ DATE: ____

	Symptoms-	A A . B . C				Remarks and Recommendations	
	detectability	Local Effect	End Effect		Severity	y ability	
White word White State of the s	•	Local Effect	End Effect	provision		ability	This item analyzed as part of the safety devices as Element Number 50.6
							Page = 104 =
							Page - 104 -

Form No. 276 6

Indenture Level No. 1 VERTICAL CONVEYOR SYSTEM
Indenture Level No. 2 Load/Unload Devices
Jam Sensing Micro-Switch
Indenture Level No. 4
Commercial Part

Output specification	Failure Mode		Possible causes	Symptoms-	Effect of	E	
functional description	SN	Description	Lassinis canses	detectability	Local Effect	End Effect	con
60.8 Jam Sensing Micro- Switch See Remarks Column						•	

Contract No. N00024-72-C-5500
Organization KORNYLAK CORPORATION
By ENGINEERING DEPT., KORNYLAK CORP.

APPROVED:	 DATE.	
APPHUVEU:	 UAIC:	

36	Symptoms-	ptoms- Effect of Failure		Existing Level compensating of	Failure prob-	Hemarks and Recommendations	
	detectability	Local Effect	End Effect				tremarks and recommendations
and the state of t	→ → ~		- -	•••		-	This item analyzed as part of the s.fety devices as Element Number 50.7
المعالمة المستعدد والمستعدد							
							Page - 105 -

11. Conclusions and Recommendations

- 11.1 Figure 14 provides an overview of the number of potential failures in each probability and severity block and the percentage of such failures compared to the total number of potential failures. There are no failures with a probability greater than two -- all failures with a severity of three or four were covered individually in the analysis section of this report (See Section 9).
- 11.2 Any loss of conveyor operation was assigned a severity factor of three or four. As a result, potential failure of ancillary equipment such as micro-switches, push buttons and elements of the Controller and Drive System were included and contributed significantly to the numbers shown in the three or above severity level blocks. Such equipment is not related to the conveyor structure or the conveyor's operating componentry. If potential failure of ancillary equipment is eliminated from consideration, the total number of potential failures from structural and operating system components only reduces the number of potential failures in the three or above catagories from an overall total of 67 to a total of 30.
- During the analysis it was determined that the "Emergency Run" by-pass circuitry did not enable the conveyor to be run so as to clear a jam sensed and stopped by the "overthe-door" jam sensing safety device. The other safety devices are, in a sense, self-clearing. For instance: should a package jam during strike-down on the load/unload device, the platform will collapse and stop the conveyor. However,

the conveyor can be operated in the up direction and the jan cleared. The same is true for the bottom and top jam safety devices. By making a simple change in the wiring location of the over-the-door jam sensing relay, relative to the wiring of the Emergency Run by-pass circuit, the Emergency Run circuit could be used to by-pass the over-the-door cut-out circuit and enable a jam at a top-of-the-door coaming to be cleared. This change will be incorporated by the Contractor unless otherwise instructed by Naval Ships Command.

- During the calculations which preceded the analysis of the Operating System, it was determined that the "narrow track section" represented the weakest member of the Operating System componentry. The Contractor will revise the design of the track to strengthen this section.
- In concert with Paragraph 3.4.(e) of Specification

 Ships-C-5552 reading, in part, "...in the event of jamming,
 easily replaceable components shall yield or be damaged.",
 the Contractor is considering a series of shear bolts,
 sized to the anticipated load carrying capability of the
 family of various lengths of conveyors, be incorporated to
 fasten the carrier tray to the carrier arm and chain link.

 The Contractor forsees a potential problem should a jam occur
 which would shear such bolts and allow the tray to pass
 through the jam, if, the instantaneous overload does not trip
 and stop the conveyor. Not stopping the conveyor with a
 tray out of position could create serious damage when the
 tray transitions through the head and tail cam plates. The

problem is one of sensitivity of the IOL sensing coil and is particularly acute with smaller length conveyors. Should shear bolts be adopted, the Contractor feels a re-set device must be added to the IOL circuitry to prevent restarting the conveyor without first determining and correcting the cause of the IOL cut-out. The Contractor recommends a study of the sizes of shear bolts needed and the relative sensitivity of the IOL sensing coils be made prior to incorporation of the shear bolt design, although adaptation of this concept presents an ideal solution to the requirements of Paragraph 3.4(e) of Ships-C-5552.

11.6 The Contractor recommends that the mounting and stowage brackets of the Loader/Unloader be bolted to the conveyor rather than welded as presently shown. Bolt-on brackets will enable easier removal and maintenance of the rather complex load/unload device.





FIGURE NO. 1 Second indenture level functional block diagram.



NOTE: All components are sized and rated as a function of conveyor loading.

FIGURE NO. 2 Third indentured level functional block diagram for drive system (Number 10)




FIGURE NO. 3 Third indentured level functional block diagram for operating system (Number 30)





FIGURE NO. 4 Third indentured level functional block diagram for the control system (Number 40).



- 113 -




FIGURE NO. 6 - Third indentured level functional block diagram for safety devices (Number 50).




FIGURE NO. 7 - Third level indentured functional block diagram for the load/unload device (Number 60).

SEVERITY

Figure No. 8

CRITICALITY MATRIX - DRIVE SYSTEM (No. 10)

Matrix Tabulation - Drive System

	Level 3	Level 4
10.2 Motor	2	1
10.3 Torque Limiter	0	0
10.4 Reducer	2	2
10.5 Brake	0	0
10.6 Coupling	1	2
10.7 Jack Shaft	1	2
10.8 Bearing	0	1
10.9 Drive Sprocket	1	1
10.10 Drive Chain	0	1
10.11 Chain Take-up	0	0

Figure No. 8 (a)

Tabulation for Drive System (No. 10)




Figure No. 9
CRITICALITY MATRIX - CONVEYOR STRUCTURE (20)

Matrix Tabulation - Conveyor Structure

Level 3 Level 4

20.1 Trunk ----

Figure No. 9 (a)

Tabulation for Conveyor Structure (No. 20)

	4				
LITY	3				
PROBABILITY	2		30.1.01 30.1.01 30.15.01 30.16.01	30.9.01	30.1.02 30.15.02 30.16.02 30.17.02
	1		30.2.04 30.3.02 30.5.01 30.7.02 30.18.01 30.19.02 30.20.01	30.2.01 30.7.01 30.21.01	30.2.02 30.2.03 30.3.01 30.4.01 30.5.02 30.6.01 30.8.01 30.10.01 30.11.01 30.19.01 30.21.02
		1	^	2	,

SEVERITY

Figure No. 10


CRITICALITY MATRIX - OPERATING SYSTEM (Nc. 30)

Matrix Tabulation - Operating System

		Level 3	Level 4
30.1 Head Cam	Plate	0	1
30.2 Head Sha	ft	1	2
30.3 Head Sha	ft Bearing	0	1
30.4 Head Bear	ring Housing	0	1
30.5 Head Sha	ft Sprocket	0	1
30.6 Carrier	Chain	0	1
30.7 Carrier	Link	1	0
30.8 Chain Pin	n	0	1
30.9 Carrier	Shaft	1	0
30.10 Guide Am	m.	0	1
30.11 Guide Am	m Cap	0	1
30.12 Cam Follo	ower Flanged	0	0
30.13 Cam Foll	ower	0	0
30.14 Carrier		0	0
30.15 Front Tr	ack	0	1
30.16 Rear Tra	ck	0	1
30.17 Tail Cam	Track	0	1
30.18 Tail Car	rier Sprocket	0	0
30.19 Tail Spr	ocket Bearings	0	1
30.20 Chain Tai	ke-up	0	0
30.21 Head Dri	ven Sprocket	1	1

Figure No. 10 (a)

Tabulation for Operating System (No. 30)



SEVERITY

Figure No. 11

CRITICALITY MATRIX - CONTROL SYSTEM (No. 40)

Matrix Tabulation - Control System

		Level 3	Level 4
40.1.1	Reversing Starter	0	0
40.1.2	Thermal Overload	0	1
40.1.3	Instantaneous Overload Relay	1	0
40.1.4	IOL By-pass Timer	3	0
40.1.5	110V. Transformer	0	0
40.1.6	First Speed Relay	0	0
40.1.7	Second Speed Relay	0	0
40.1.8	Third Speed Relay	0	0
40.1.9	Overdoor Jam Relay	1	0
40.1.10	Load/Unload Relay	1	0
40.1.11	Signal Timer	0	0
40.2.1	Power On/Off Switch	1	0
40.2.2	Three-position Speed Switch	0	1
40.2.3	Power "On" Light (Red)	0	0
40.2.4	Emergency Run Switch	0	0
40.3.1	Power "On" Light (Green)	0	0
40.3.2	Stop Push-On Pull Switch	ı 0	2
40.3.3	"Up" Push Button	2	0
40.3.4	"Down" Push Button	2	0

Figure No. 11 (a)

Tabulation for Control System (No. 40)




Figure No. 12

CRITICALITY MATRIX - SAFETY DEVICES (50)

Matrix Tabulation - Safety Devices

		Level 3	Level 4
50.1	Instantaneous Overload	(see	40.1.3)
50.2	Thermal Overload	(see	40.1.2)
50.3	Audio Signal	0	0
50.4	Brake	(see	10.5)
50.5	Bottom O'Travel Limit	0	1
50.6	Load/Unload Interlock Switch	0	1
50.7	Load/Unload Jam Switch	0	1
50.8	Top O'Travel Limit	0	1
50.9	Over Door Jam Switch	2	1
50.10	Torque Limiter	(see	10.3)

Figure No. 12 (a)

Tabulation for Safety Devices




Figure No. 13

CRITICALITY MATRIX - LOAD/UNLOAD DEVICE

Matrix Tabulation - Load/Unload Device

		Level 3	Level 4
60.1	Platforms	0	0
60.2	Mounting and Stowing Bracket R. H.	o	1
60.3	Mounting and Stowing Bracket L. H.	o	1
60.4	Platform Depress Mechanism L. H.	0	4
60.5	Platform Depress Mechanism R. H.	o	4
60.6	Cross Shaft	0	1
60.7	Interlock Micro-switch	(see 50.	6)
60.8	Jam Sensing Micro-switch	(see 50.	7)

Figure No. 13 (a)

Tabulation for Load/Unload Device

				,	استناد المساوات والمساوات
	4				
LITY	3				
PROBABILITY	2	2* 1.5%**	4* 3.0%**	1* 0.8%**	4* 3•0%**
	1	29* 22%**	28* 22%**	21* 16%**	41* 31•5%**
	'	1	2	3	4

*Number of Potential Failures SEVERITY
*** Percent of Total

Figure No. 14

CRITICALITY MATRIX - OVERVIEW OF ALL SECTIONS

Section VI

Calculations

The following pages contain detailed revised stress calculations for the de-rated jam conditon. A supplement to these calculations is also provided. Prior to submitting the revised calculations to Naval Ship Engineering Center on November 10, 1976 and the supplement on April 5, 1977, the Contractor provided a complete set of calculations for Phase I which were subsequentally revised and re-submitted as part of Phase II on November 18, 1975. The earlier, November 18, 1975, Calculation submittal is not being included in this final report in order to conserve space and minimize reproduction cost.

SUPPLEMENT

DE-RATED JAM CONDITION

PER S. OTTO'S TELEPHONE CONVERSATION OF 3-29-77

CDRL ITEM BOO1AL

USN CONTRACT N00024-72-C-5500

OF NOVEMBER 3, 1976

Submitted: 13 April 1977

By: Kornylak Corporation

Hamilton, Ohio

Summary of telephone conversation of 3-29-77 between S. Otto and R. arson - with replies.

Attn: V. Doty R. Martin

- 1. Liked R. Martin's stress calculation work!
 - Thanks, Bob Martin
- 2. Questions size of finger-to-backbone welds on load trays. Where stated?
 - Will appear on fabrication drawings as %" fillet welds as noted on page (8) of report.
- 3. Suggested Bob check stress concentrations at keyway of carrier shaft.
 - See page B and C attached.
- 4. Requested Bob re-do stress calculations of carrier shaft where it ties to guide arm and add approximately 1300# shear load to torsion load (referring to Fig. 11-A).
 - See page C attached.
- 5. Requested that Kornylak send letter to delete 150# four foot drop spec. requirement since this load impossible for design to survive.
 - See page D attached.

Item 3 of 3-29-77 telephone conversation stress concentrations at keyway of carrier shaft:

Reference: Report page 13; Roark's "Formulas for Stress & Strain" 4th edition, page 334

Assuming that the key takes the entire load (no cap) and that the torsional moment produces a true horizontal force that tries to compress and shear through the shaft:

Torsional Moment M_t: 3069 in. lbs. Shaft Radius: .75 inches Key: 3/8 sq. x l½" lg.

Force =
$$\frac{M_t}{\text{shaft rad.}} = \frac{3069}{.75}$$


= 4092 lbs.

Compressive Stress =
$$\frac{F}{Comp. Area}$$

= $\frac{4092}{1.25 \times .1875}$
= 37,248 psi

Shear Stress =
$$\frac{F}{Shear Area}$$


= $\frac{4092}{1.25 \times .309}$
= 22,601 psi



Supplement to Fig. 11_C

While the compressive stress of 37,248 psi is less than the allowable 48,000 psi for stainless steel, the shear stress of 22,601 psi will exceed the allowable 18,000 psi.

However, since according to Roark, "Photoelastic Analysis of the stress in square keys shows that the shear stress is not uniform across the breath" but is greater in the corners tending to rock the key, especially since the carrier shaft is subject to pulsations. (Reference Fig. 11_D)



(B)

Therefore, since the key is rocking, direct shearing through the shaft is not the true case; moreover, the cap would surely limit the shear stress to less than the allowable 18,000 psi if it were.

Roark concluded the key stress segment: "When conservative working stresses are used, however, and the proportions of the key are such as have been found satisfactory in practice, the approximate methods of stress calculation that have been indicated result in satisfactory design". Which is the case as used in the report.

Item (4) of 3-29-77 telephone conversation add 1300# shear load to carrier shaft where it ties to guide arm.

Reference: Drawing 2-1026-SC3

The 1300# shear load (chain pull) was neglected with respect to Fig. ll_{λ} because where the carrier shaft ties to the guide arm there is no fixed restraint (direct shear). The guide arm is trying to pivot about the cam roll which is pure torsional shear.


I can, however, place the neglected 1300# shear load on the opposite side of the carrier link where the cross section is full.

Area of
$$1\frac{1}{5}$$
" ϕ shaft = 1.76 sq. inch

Torsional Shear = $\frac{M_t}{rad. \times area}$
= $\frac{3069}{.75 \times 1.76}$ = 2325 psi

Direct Shear = $\frac{1300}{1.76}$ = 739 psi

Total Shear = 2325 + 739 = 3064 psi



Since the allowable shear for Type 304 Stainless Steel is 18,000 psi, the carrier shaft is adequate for the application.

OPERATING SHOCK LOAD

- Reference: (a) Para. 3.5.23.4 of Spec. SHIPS-C-5552
 - (b) Operating Shock Load Calculations Sht. 1 through 5
 - (c) Impact test results Sht. 1 through 4
 - (d) Shock Load Test per Para. 4.3.5 of SHIPS-C-5552
- The impact loading as specified in reference (a) and (d) is
 too excessive and destructive, as pointed out in reference
 (b) and (c), and would require an increase in size of
 components which would not be practical or in keeping with
 the conveyor design.

In view of this, we recommend that para. 3.5.23.4 and 4.3.5 be deleted from the spec. and that the dynamic and static overload tests per para. 4.3.2 and 4.3.3 are sufficient for testing the conveyor.

REVISED STRESS CALCULATIONS

FOR

DE-RATED JAM CONDITION

CDRL ITEM BOO1AL

USN CONTRACT N00024-72-C-5500

NOVEMBER 3, 1976

Submitted: November 3, 1976

By: Kornylak Corporation

Hamilton, Ohio

The following drawings and reports are referred to in the text of this report:

2-1026-P20F-Rev. A (Carrier Assembly)

2-1026-P26-Rev. B (Carrier)

2-1026-P27-Rev. A (Guide Arm)

2-1026-P28-Rev. B (Carrier Shaft)

2-1026-47F-Rev. A (Cap)

*2-1026-SCI/J (Shaft & Bearing Calculations - Jam)

*2-1026-SC2 (Carrier Calculations)

*2-1026-SC3 (Carrier Shaft & Guide Arm Calculations)

**2-1026-SC3/J (Carrier Shaft & Guide Arm Calculations - Jam)

Track System calculations for jam condition in letter of transmittal dated October 14, 1976

*These drawings were superseded, and prints of them are included with this report.

**This drawing was voided, and prints of it are included with this report.

REVISED STRESS CALCULATIONS FOR DE-RATED JAM CONDITION

DE-RATED JAM CONDITION

The jam condition was de-rated from motor stall torque to 115% live load setting on the torque limiter by N.E.V.E.C.'S amendment letter of May 20, 1976, modification No. P00014 revising Par. 3.5.23.1, Line 5, as clarified in Design Review Meeting held June 21 through June 23, 1976.

Live Load = 20 trays x 100# each

= 2000 # x 1.15 = 2300 # (torque limiter slip setting)

"The load is to be spread equally over four fingers of the tray".

Case I: One side finger and three intermediate fingers.

Case II: Four intermediate fingers (worst condition)

Case II-A Carrier Finger (Ref. Dwg. 2-1026-P26-Rev. B)
- Mat'l.: ASTM A513

Jam Stress Calculations (Ref. Dwg. 2-1026-SC2)

Per Fig. 2

Assuming no gusset as shown on drawing


Load WL = 575# uniform cantilever

Effective Length L = 21.125 inches

Finger Section Modulus Z = 0.334

Bending Moment

 $M_b = \frac{WL \times L}{2} = \frac{5.75 \times 21.125}{2} = 6073$ in. lbs



Finger Loading (without gusset)

Bending Stress

$$S_b = \frac{M}{Z} = \frac{6073}{0.334} = 18,160 \text{ psi}$$

Therefore, since the 18,160 psi is less than 26,600 psi, or the allowable combined stress per Spec. 3.5.23.1 (0.7 yield stress), the finger tubing is adequate for bending in this application.

Case II-B Finger Welds (neglecting bar gusset) - (Ref. dwg. 2-1026-P26 Rev. B)

Max. Allowable Shear Stress = 22,800 psi (ASTM A513)

Bending Moment $M_b = 6073$ in. lbs.

Req'd. Min. Section Modulus Z

$$z = \frac{M_b}{S_s} = \frac{6073}{22,800} = 0.266$$

NOTE: $Z = \frac{I}{C}$

where I = Moment of Inertia,

and C = Distance from neutral axis
 to outermost fiber (inches)

Neglecting bar gusset between finger and crossmember per Fig. $\mathbf{3}_{\mathbf{A}}$

Recommended fillet weld thickness for #14 ga. tubing is 1/16" (.0625)

From the parallel axis theorem, using throat area of welds (.707 x leg):

Moment of Inertia $I_W = 0.258$ of the welds

C Welds = 1.294

Section Modulus
$$Z_w = \frac{I_w}{C_w} = \frac{0.258}{1.294} = 0.199$$





fig. 3 Finger weld (To Crossmember) Using throat area



Bending Shear Stress
$$S_s = \frac{M}{Z_w} = \frac{6073}{\cdot 199} = 30,517 \text{ psi}$$

Therefore, since the section modulus of the welds, 0.199 (neglecting the bar gusset) is less than the minimum required section modulus of 0.266, (30,517 psi exceeds the allowable shear stress of 22,800 psi) the finger welds are not adequate for this application.

To reduce the bending shear stress of the finger welds, add a gusset between the finger and crossmember so as to reduce the bending moment.

Case II B Finger Welds including bar gusset
per Fig. 4 - (Ref. Item 3 on Dwg. 2-1026-P26 Rev. B)

Fig 4A

Gusset: 3/8" x 1" AISI 1020 HRS Bar x 5" Lg.


Finger with Gusset

Assuming the gusset is strong enough Maintaining WL=575# As Worst Condition to resist bending:

Revised Effective Length L = 16.625"

Revised Bending Moment Mb (using entire uniform load @ L = 16.625" for worst condition)

$$M_b = \frac{575 \times 16.625}{2} = 4780 \text{ in. lbs.}$$




Revised Req'd Section Modulus Z w

$$Z_w = \frac{M_b}{S_s} = \frac{4780}{22,800} = 0.210$$

From the parallel axis theorem, using throat area of welds (.707 x leg)

Moment of Inertia $I_w = 1.684$

$$C_{\text{welds}} = 5.34$$



Section Modulus Z

$$z_w = \frac{I_w}{C_w} = \frac{1.684}{5.34} = 0.315$$

Bending Shear Stress
$$S_s = \frac{M_b}{\frac{2}{S_w}} = \frac{4780}{.315} = 15,175 \text{ psi}$$

Considering the additional strength that the bar gusset weld adds to the finger welds, the section modulus of 0.315 exceeds the min. required section modulus of .210 (15,175 psi is less than the allowable shear stress of 22,800 psi). Therefore, the finger welds are adequate for the application.

To confirm the additional strength that the bar gusset adds to the finger welds, the following physical tests were made on two different carrier fingers.

Finger I: 2½" x 1" x #14 Ga. Finger Plain, i.e., no gusset

Finger II: 2½" x 1" x #14 Ga. Finger with 3/8" x 1" x 5" 1g. bar


Gusset per dwg. 2-1026-P26-Rev. B

Both fingers were subjected to the rated load, and then additional weight was added until the first sign of failure was observed, documenting weights, deflections and mode of failure(s). Note: A third finger with a $2\frac{1}{2}$ " x 1" x 14 ga. mitered tube gusset was also tested at the same time as the other two (ref. Fig. $5_{\rm C}$); however, tests results showed that it was no stronger than the bar gusseted finger (Fig. $5_{\rm B}$).

TESTS AND RESULTS PER PAGES 5,6,7, & 8

BENDING SHEAR TESTS ON CARRIER FINGER WELDS


These three carrier fingers were loaded as shown to test the strength of the welds joining them to the crossmember, and also to test what effect the gussets had on them.



TEST	WEIGHT	DEFLECT.	DEFORM. SET INCHES	DESCRIPTION FAILURE MODE	COMMENTS
Finger I	303 877 1059	0.125 0.375 0.406	0 0 0.125	Finger Bent	Welds O.K. See Pics. 1,2,3,4, &5
Finger II	303 877 1059	0.062 0.250 0.281	0 0 0	None	Welds O.K. See Pic. 6
Finger III	303 877 1059	0.062 0.218 0.281	0 0 0	None	Welds O.K. See Pic.7

PICTURES TAKEN DURING FINGER WELD TESTS

Sheet 1 of 2










PICTURES TAKEN DURING FINGER WELD TESTS

Sheet 2 of 2







The results of the tests indicate more than the strength value of the graset, however, as the welds themselves withstood over 3½ times the weight of the rated load at jam condition.

NOTE: While the recommended fillet weld thickness for #14 ga. tubing is 1/16", the mig-welded ½" fillet welds, applied to the fingers at the crossmember, supported 1059# without failure in bending shear which is equivalent to a section modulus of .952 for the welds; hence, considering throat area of the welds (.707 x leg), they are equivalent to a fillet leg thickness of over 5/16" (.3125), which is stronger than the parent metal thickness of .075" (#14 ga.)

Calculations:

Max. Allowable Shear Stress
$$S_s = 22,800 \text{ psi}$$
 (ASTM A513)

Max. Weight Used Without Failure W = 1059# (plain finger, i.e., no gusset)

Bending Moment M_b = W x L (Point Load, Cantilever)

= 1059 x 20.5"

= 21,710 in. lbs.

Bending Moment
$$M_b = \frac{WL \times L}{2}$$
 (Uniform Load, Cantilever)

Since jam condition was specified as a uniform load, the equivalent uniform load for a bending moment of 21,710 in.

1bs. would be 2118# (3.68 x rated jam condition)

Section Modulus of the Welds
$$z_w = \frac{M_b}{S_{\text{max}}^2} = \frac{21,710}{22,800} = .952$$

From Fig. 5_A , using an equivalent section modulus of .952 and a throat area (.707 x leg), from the parallel axis theorem, the fillet leg of the welds joining the finger to the crossmember calculates to a thickness in excess of 5/16".

Case II - C Crossmember (Ref. Dwg. 2-1026-P26-Rev. B) - Mat'l.: ASTM A500

Load (W) = 575#, r places, simply supported


Section Modulus (Z) = 1.24

$$M_{R_2} : R_1 = \frac{575(12 + 18 + 24 + 30)}{36}$$

$$R_1 = 1342#$$

$$F_{vert}: R_2 = 958#$$

Max. Bending Moment M = 13,806 in. 1bs. from shear - mom. diag.




<u>Max. Bending Stress</u> = $S_b = \frac{M_b}{2} = \frac{13,806}{1.24} = 11,134 \text{ psi}$

Therefore, since 11,134 psi is less than 32,200 psi, the allowable combined stress per Spec. 3.5.23.1 (0.7 yield stress), the tubing is adequate for bending in this application.

Crossmember Stresses at Side Bar


Area (A) of crossmember = 1.74 sq. inc.

Max. Direct Shear Stress
$$S_s = \frac{R_1}{A} = \frac{1342}{1.74}$$



Torsional Moment M_t using uniform load acting through the center of the crossmember for worst condition

 $M_t = \frac{575 \times 22.375}{2}$ (per finger) x 4 fingers x $\frac{1}{2}$ (assuming symm. loading each end)



Torsional Shear Stress
$$S_t = \frac{M_t}{Q}$$

$$= \frac{12,866}{2.01}$$


$$= 6,401 \text{ psi}$$

Therefore, since the direct shear of 771 psi and the torsional shear of 6,401 psi are respectfully less than the allowable direct shear of 27,600 psi and the torsional shear of 29,900 psi, the tubing is adequate for shear and torsion in this application.

Weld Stress (Crossmember to Side Bar)

Recommended fillet weld thickness for 3/16" tubing = 1/8" (0.125)

Total area of welds (A) = 0.88 sq. in.using throat area (.707 x leg)



Max. Direct Shear Stress
$$S_s = \frac{R_1}{A} = \frac{1342}{0.88} = 1525 \text{ psi}$$

$$\frac{\text{fig. 8}_A}{\text{Crossmember Welds}}$$

Torsional Section Modulus $Q_w = 2(.088) (2.676-.088)^2$

Ref. Roark's "Formulas for Stress & Strain" pg. 196 using throat area (.707 x leg)

Ref. Roark's "Formulas for Stress & Strain" pg. 196 using throat area (.707 x leg)

Torsional Shear Stress
$$S_t = \frac{M_t}{Q_w} = \frac{12,866}{1.18} = 10,903 \text{ psi} \frac{\text{fig 8}_B}{\text{Loads on Welds}}$$


Welds

Crossmember to Side Bar

1342#

Therefore, as in the case of the crossmember proper, the welds joining the crossmember to the side bar are likewise adequate for this application.

Case II - D Carrier Shaft Mounting Bolts (Ref. Dwg. 2-1026-P20F Rev. A)
- Mat'l: MIL-B-857 Grade 2, 5/8-11 UNC




 $F_{vert}: R_1 = R_2 + 1342#$

$$M_{b} : R_{2} = 51\#$$

Therefore, $R_1 = 1393#$

Combined Shear Stress
(direct & torsion)
from freebody diagram
using worst cond. (R₁)

$$S = \frac{P}{A} = \frac{1393}{.202} = 6,896 \text{ psi}$$



Req'd Tensile Yield Stress

 $\frac{\text{Min. Tensile Y.S.}}{\text{(shear)}} = \frac{\text{Actual Shear Stress}}{0.6}$

$$= \frac{6,896}{0.6} = 11,493$$
 psi

Fhysical & Freebody Diagram of
Bolt Loading

Therefore, since the tensile yield stress of a 5/8-11 Grade 2 bolt is 64,000 psi per MIL-B-857, which exceeds the req'd 11,493 psi, they are adequate for this application.


Case II-E Carrier Shaft Welds (Ref. Dwg. 2-1026-P28-Rev. B)
- ½" Fillet Welds

Net Vert. Force = 1393 - 51 = 1342#

Area of $\frac{1}{2}$ " fillet weld using throat area (.707 x leg) = 1.11 sq. in.


Direct Shear Stress on Welds

$$S_{sd} = \frac{F_y}{A} = \frac{1342}{1.11} = 1209 \text{ psi}$$



Loading on Carrier Shaft

Mounting Plate
(from Bolts)



Torsional Moment M.

$$M_{t} = [1393 \times 2.125] + [51 \times 2.125] \frac{\text{Fillet Weld}}{\text{Leg}}$$

= 3069 in. lbs.

Carrier Shaft Welds (to mounting plate) $\frac{\text{Torsional Section Modulus}}{\text{of the welds}} Q_{w} = \frac{1}{10} \left[R_{o}^{4} - r_{i}^{4} \right]$

 $= \chi [(1.052)^4 - (.875)^4]$ Ref. Roark's "Formulas for Stress & Strain" pg. 195 using throat area (.707 x leg)

$$Q_{u} = .952$$

Torsional Shear Stress
$$S_{st} = \frac{M_t}{Q_{tt}} = \frac{3069}{.952} = 3224 \text{ psi}$$

Using AISI 1020 HRS mtg. plate and ASTM A276 Type 304 stainless steel shaft, and assuming that the weld properties will equal those of the parent metals:

> Min. Tensile Yield = 30,000 psi (stain. stl.) Max. Allowable Direct Shear = 60% yield = 18,000 psi Max. Allowable Torsional Shear = 65% yield = 19,500 psi

Therefore, since the direct shear of 1209 psi and the torsional shear of 3224 psi are respectfully less than the allowable direct and torsional shear, the materials and welds are adequate for this application.

CASE II-F Carrier Shaft (Ref. Dwg. 2-1026-P28-Rev. B) - Mat'l.: ASTM A26 Stainless Steel Type 304

The weakest portion of the shaft occurs at its least area which includes the .185" flat for the cap, the .75" dia. bore for the cam follower, and the 3/8 x 3/16" keyway.

<u>Jam Stress Calc.</u> (Ref. Dwg. 2-1026-SC3) per Fig. 11_B

Torsional Section Modulus Q Ref. Roark's "Formulas for Stress & Strain" pg. 194 and 199 using Case 26 due to its worst condition

Q carrier = Q shaft = Q bore
shaft proper
=
$$C \times r_1^3 - \frac{r_2^3}{2}$$

where C = .912 (actually higher)

$$Q = 0.302$$

Torsional Moment $M_t = 3069$ in. lbs.

Torsional Shear Stress


$$S_{st} = \frac{M_t}{Q} = \frac{3069}{.302}$$

= 10,162 psi

Req'd Tensile Yield Stress = $\frac{10,162}{65}$

$$= 15,634 \text{ psi}$$

The req'd. tensile yield stress of 15,634 psi is less than the 30,000 psi yield stress of the ASTM A26 Type 304 Stainless Steel Carrier Shaft, therefore, it is adequate for the application.



Therefore, since the shear stress of 8,730 psi is less than the allowable shear stress of 32,400 psi for AISI 1018 CRS, the 3/8" sq. key is adequate for the application.

Worst Condition

Case II-G Guide Arm (Ref. Dwg. 2-1026-P27-Rev. A)

-Mat'l AISI 1018 & 1020 HRS

Jam Stress Calculations (Ref. Dwg. 2-1026-SC3)

Per Fig. 12

 $\frac{\text{Normal Force to Resist}}{\text{Carrier Shaft Torque}} \ ^F_n$

$$F_n = \frac{M_t}{4} = \frac{3069}{4} = 76.7$$

Bending Moment $M_b = F_n \times L$

Assuming the normal

force working on the average

cross-section of the guide arm

$$(at L = 2.5")$$

 $M_b = 76.7 \times 2.5 = 1918 \text{ in. lbs.}$

Bending Section Modulus Z = 1.302 @ L = 2.5"

$$\frac{\text{Bending Stress}}{\text{Bending Stress}} \, S_b = \frac{M_b}{Z} = \frac{1918}{1.302}$$

$$= 1473 \text{ ps}$$
:


= 1473 psi


Torsional Moment M_t (due to eccentric load on Camrol) L= 2½"

$$M_t = F_n \times 2.4 = 76.7 \times 2.4 = 1841$$
 in. 1bs.

Torsional Section Modulus $Z_p = .866$

Torsional Stress
$$S_t = \frac{M}{Z_p} = \frac{1841}{.866} = 2126 \text{ psi}$$





 $\underline{\text{Combined Stress}} \ \textbf{S}_{n} \ (\text{bending \& torsion})$

$$s_n = \frac{s_b}{2} + \sqrt{(\frac{1}{2}s_b)^2 + (s_t)^2}$$

= $\frac{1473}{2} + \sqrt{(737)^2 + (2126)^2}$

= 2987 psi

Max. Shear Stress =
$$\sqrt{(\frac{1}{2} S_b)^2 + (S_t)^2}$$

= 2250 psi

Therefore, since the combined stress of 2987 psi is less than the allowable combined stress of 22,400 psi (.7 Y.S.), and the max. shear stress of 2250 psi is less than the allowable shear stress of 19,200 psi, the guide arm proper is adequate for the application.

Case II-H Camrol Mounting Arm Welds (Ref. Dwg. 2-1026-P27-Rev. A)
- 1/8" Fillet Welds

 $\frac{\text{Worst Condition:}}{\text{Per Fig. 13A}} \quad \text{Assume no compressive assistance from Camrol stud mounting}$

Bending Moment
$$M_b = 767 \times 1.25$$

= 959 in. lbs.

Section Modulus of the Welds Z using throat area (.707 x leg)^W

using throat area (.707 x leg)"
$$Z_{w} = \frac{1}{(R_{o})^{4} - (r_{i})^{\frac{3}{2}}}$$

$$= \frac{1}{(.713)^{4} - (.625)^{\frac{3}{2}}}$$

$$= .117$$

$$F_{n} = 767\#$$

$$.707 \times 1/8" = .088$$




fig 13_A
Camrol Mounting Arm Welds

$$\frac{\text{Weld Shear Stress}}{\text{due to bending}} = S_s = \frac{M_b}{Z_w} = \frac{959}{.117} = 8197 \text{ psi}$$

Since the bending shear stress of 8197 psi is less than the allowable direct shear stress of 19,200 psi, the welds are adequate for the application.

Checking Bending Strength of Camrol Mounting Arm

ref. Fig. 13_B

Section Modulus of Arm Z

$$z = \frac{(.625)^4 - (.375)^4}{4 (.625)} = .167$$

Bending Stress
$$S_b = \frac{M_b}{Z} = \frac{959}{.167}$$

= 5743 psi




fig 13_B
Camrol Mounting Arm

Therefore, the Camrol mounting arm is likewise adequate for the application.


Case II-J Cap (Ref. Dwg. 2-1026-47F-Rev. A)

- Mat'l.: AISI 1018 CRS

Carrier Shaft Torque M_t - 3069 in. lbs.

Tangential Force
$$F_t = \frac{M_t}{rad} = \frac{3069}{.75}$$

= 4092#



Cap Loading

$$0 = 90^{\circ} - 41.12^{\circ} = 48.88^{\circ}$$

Normal Force $F_n = F_t \cos 0$

$$= 4092 (\cos 48.88^{\circ}) = 2691\#$$

Cap Loading: Ref. Fig. 14B

Bending Moment $M_b = F_n A \times B$

$$= 2691 \times .757 \times 1.743 = 1420 \text{ in. lbs.}$$

Cap Section Modulus $Z = \frac{bh^2}{6}$

$$= 1 \times (.75)^2 = 0.09375$$

Ref. Fig. 14B

A.757

B.757

B.757

B.757

B.757

Cap Loading

Bending Stress
$$S_b = \frac{M_b}{Z} = \frac{1420}{0.09375} = 15,146 \text{ psi}$$

Since the max. allowable stress for AISI 1018 CRS is 37,800 psi (.7 Y.S.) which is greater than the 15,146 psi bending stress, the cap is acceptable for the application.

Case II-K Cap Mounting Bolts (Item 12 Dwg. 2-1026-P20F-Rev. A)

- Mat'l.: MIL-B-857 Grade 2, \(\frac{1}{2} - 13 \) UNC

Bolt Loading:
$$R_1 = \frac{2691 \times 1.743}{2.5} = 1876 \%$$
Above
$$R_2 = \frac{2691 \times .757}{2.5} = 815 \%$$

Therefore, since the min. breaking or stripping force of the ½-13 bolts is 9790#, they are adequate for the application.

Track System Calculations for Jam Condition

NOTE: Stress calculations concerning the track system under jam condition were included in ltems (d) through (h) inclusive, in our letter of transmittal dated October 14, 1976.

Section VII

Engineering Studies and Investigations

This Section contains three Engineering studies conducted by the Contractor during Phase II of R & D Contract No. N00024-72-C-500.

- A. Design Study on the Posidyne Clutch/Brake
- B. Investigation to Determine if Interal Bracing can be used to Eliminate External Stiffeners on Watertight Trunk Applications for Vertical Stores Conveyors
- C. Design Study of Conveyor Overload Protection

DESIGN STUDY ON THE POSIDYNE CLUTCH/BRAKE

DD1423 Item B001AK

(partial fulfillment of line item 004 of Contract N00024-72-C-5500)

Copies: 5

Reproducibles: 0

Submitted to:

Commander, Naval Ship Engineering Center

Center Building

Prince George's Center

Hyattsville, Maryland 20782

Code 6164

Attention: Mr. Satterthwaite

Mr. Otto

NOTE: The original of the enclosed DD250 should be signed at destination and destribution made including a signed copy to:

Kornylak Corporation 400 Heaton Street Hamilton, Ohio 45011

Attention: Mr. R. A. Larson

DESIGN STUDY
ON THE
POSIDYNE CLUTCH/BRAKE
CDRL ITEM B001AK
USN CONTRACT N00024-72-C-5500
JULY 28, 1976

Submitted: July 28, 1976

By: Kornylak Corporation

Hamilton, Ohio

DESIGN CONSIDERATIONS

FOR INCORPORATING THE

POSIDYNE CLUTCH/BRAKE UNIT

INTO THE

VERTIFLO POWER TRAIN

JOHN E. GERSTLE


KORNYLAK CORPORATION


SYNOPSIS

The Posidyne Clutch/Brake unit is a versatile tool that offers potential safety to the conveyor system much superior to that of other torque limiting devices. However, in order to utilize this potential for safety, an auxiliary precision air supply must be incorporated and carefully adjusted. A fail-safe mode is inherent in the unit.

TABLE OF CONTENTS

		PAGE
Title	Page	i
Synops	is	ii
Table	of Contents	iii
I	Introduction	1
II	Required Hardware	5
III	Operational Procedures	10
IV	Comparison of Torque Limiting Devices	14
v	Conclusions	17





I. - INTRODUCTION

1.1 Background - Due to the confined nature of the Vertiflo style of conveyor system, jam conditions inevitably arise. The Kornylak Vertiflo has a variety of safety switches to detect misloaded packages before a jam can occur. However, switch failure, or some condition unrelated to the cargo could cause a physical jam of the system.

计算数据数据数据数据数据数据数据数据数据

The immediate result of a jam situation on the conveyor is an instantaneous increase in the torque drawn from the drive train. This is transmitted from the carrier chains to the head sprockets, to the reducer, to the drive clutch, and to the motor. The motor uses extra power to provide the elevated torque requirements. If unrelieved, this extra power will burn out the motor, or the extra torque will destroy some part of the power train to release the tension.

1.2 Existing Safety Features - All Kornylak conveyor drive motors are provided with the motor overcurrent protection devices standard in industry. The Vertiflo conveyors are further protected by instantaneous trip overcurrent relays which are so sensitive that they must be bypassed during startup. Further, various photoelectric and cable switches are installed to check the package orientation on the carrier trays.

Mechanical safety consists of some type of slip clutch which will limit the amount of torque that can be exerted by the motor, and possible installation of easily replaceable "weak links" in the system.

1.3 Limitations of Existing Devices - The standard motor overload is designed to protect the motor and thus responds slowly
to brief peaks of excess torque which the motor can stand. Thus
the torque could cause excessive damage before this switch shut
the system down. On the other hand, the instantaneous trip overcurrent relays, if set to be really effective for jam safety,
after trip out on a current surge not directly related to a
true jam. A patch of rust in the wrong place could stop the
conveyor each time a particular link in the chain passes by.

Mechanical slip clutches suffer from basic inaccuracy, and are limited by start-up requirements. The friction force between two pressure plates can vary drastically due to wear, temperature, humidity, and static versus sliding friction. For ball detent type torque limiters, the setting must be adjusted high enough to allow for start-up and cannot easily be reduced while the conveyor is running. Likewise, a different torque limit could not be provided for the "up" versus "down" motion. Refer to section IV on page 14.

1.4 Advantages of Posidyne - The Posidyne clutch unit reduces these disadvantages. Its torque is directly proportional to the air pressure applied to the unit. Thus, it is only necessary to change the applied pressure following start-up to reduce the torque limit to that for "running" jam protection. The torque limit can be set as accurately as needed using precision air pressure regulators for each torque setting. The environment has much less effect on the torque setting than is the case with a friction clutch, since the Posidyne pressure plates are immersed in oil to maintain uniform conditions. Further, this

unit dies not provide the "all or nothing" problem of the ball-detent or instantaneous trip overload torque limiting devices. Instead it continues to provide a limited torque to the load until shut off by a zero-speed switch. This allows it to ride over rough spots and survive voltage surges without stopping the conveyor.

In addition the Posidyne clutch provides a "soft start" capability. The start-up torque can be controlled to provide an acceleration ramp, if desired.

1.5 Disadvantages of the Posidyne Clutch - The chief disadvantage of the unit is the requirement for pressurized air and the extra hardware to control this air. A 3-way valve and a precision pressure regulator and gage are required for each torque setting. Also, to make the conveyor less dependent upon external systems, a small compressor must be linked directly to the drive motor to provide the air to operate the clutch.

Temperature has some effect on the torque setting of the unit due to the viscosity change in the oil inside the clutch unit. This leads to a slight torque change between initial turn on and the steady state level. But this is less variation than exists with a friction clutch exposed to the atmospheric humidity as well as temperature. The temperature change from Arctic to Equatorial operation could be compensated for by readjusting the pressure settings as needed.

The standard unit is built of cast iron, which does not meet Navy specs. However, the manufacturer has an optional ductile iron unit which was designed to meet the specs. when these units

were used on other Navy projects. This option adds about \$100 to the cost of each unit.

1.6 Conclusions - After studying a large number of types of torque limiting devices, the Posidyne Clutch/Brake system was chosen. This system provides the capability to control all phases of the conveyor operation. Its advantages appear to justify the additional cost involved. Refer to section IV on page 14.

II. - HARDWARE

2.1 Posidyne Unit - The clutch and brake within the Posidyne unit each consists of a series of interleaved pressure discs.

For the clutch, half of the discs are keyed to the drive member and the rest to the driven member. For the brake, the discs are keyed to the driven member and to the case respectively.

When no pressure is applied to the unit, internal springs hold the brake discs together resisting any rotation of the driven shaft. This provides fail-safe braking. If compressed air is applied to the clutch port, the brake is released as the force of the air overcomes the brake spring tension. When more pressure is applied the clutch discs are pressed together to transmit driving torque. The air pressure, minus the pressure required to release the brake, is linearly proportional to the torque transmission capability of the unit.

If any "slip" occurs within the Clutch/Brake unit, the friction forces generate heat. In this unit a built-in oil pump circulates cooling oil between the discs to keep the rubbing surfaces cool and lubricated. The heat is transferred to the finned case to be dissipated. If the unit is unable to eliminate this heat and the oil gets too hot, a temperature switch will shut down the conveyor to prevent destruction to this unit.

An important advantage of the Posidyne unit is the low maintenance required. The manufacturers has performed routine check out of units in the field and has found negligible wear on

the pressure plates after years of service except in a few cases of extremely severe duty cycles. This latter case involved driving a flying shear cutting bar stock, in which the cutting mechanism had to be accelerated to the speed of the bar stock in half a revolution, and decelerated during reset to stop within a fraction of an inch of nominal. A small demonstration/test unit has been alternately starting and stopping for several years and has logged over 18 million cycles with negligible plate wear.

The oil used in the units is a high grade of automotive automatic transmission fluid designed for a 20 year service life and capable of operation over a wide temperature range. So, unless something should cause the oil to leak out, the units should not have to be touched for the life of the conveyor.

On the other hand is the problem of run-in. The surfaces of the plates are such that more torque is output per PSI of air pressure when the plates are new than after some use. In order to provide the precision and repeatability needed, the units must each be cycled until the torque relationship no longer changes. This can be done by the manufacturer for an additional charge.

2.2 Compressor - The pressurized air to operate the clutch unit can be generated by a Gast oil-free air compressor belt driven by the conveyor drive motor itself. This eliminates the conveyor dependency on ship air. The motor and compressor are started when the warning horns sound, and there is plenty of air available by the time the clutch is energized to start the

conveyor. Only small quantities of air are required but a constant pressure head must be maintained. The chosen compressor can supply the necessary shot of air for start-up even with the motor at its lowest speed, and can remain dead headed for continuous running.

2.3 Air Filter - Since the quantity of air used is so small, there will not be a large build-up of oil or water in the system. However, removal of water from the clutch unit is difficult and is better handled by minimizing the amount of water taken in. Further, micron sized particles in the air system could reduce the accuracy of the precision pressure regulators. Consequently, a Watts air filter with a water limiting coalescin element and automatic drain will be used with the system.

Oil in the system will not hurt the clutch as will water, and might help the valve operation, but the flow of air is too small to operate an oil mist lubricator. The valves chosen do not need oil.

2.4 Pressure Regulators - Since the only control available of the torque transmission of the clutch is the air pressure provided to the unit, precision pressure regulators must be used. Most important is a high degree of repeatability over the environmental conditions that must be faced. Primarily, this is temperature variations, since the regulators will be installed in an enclosed box for security. Chosen was the Fairchild model 10 which is designed to repeat to a fraction of a PSI under all conditions.

- 2.5 Precision Gages Although the pressure and torque are controlled by item 2.4 above, the set-up man needs a true readout of this pressure. Provided are Helicoid style 410TD test gages with 1/8 accuracy and .2 PSI meter sub-divisions. With these the set-up man can fine tune the unit to a fraction of a foot-pound of torque.
- 2.6 Pressure Selector Valves Three-way direct operated solenoid air valves are needed to control the selection of which pressure is to be applied to the clutch. These are arranged in a cascade fashion with the "start-up" pressure overriding the others.

 Consequently, at least two of the three valves must be of "universal" type operation in which pressure can flow both ways. The only other requirement of these valves is for long trouble free life without lubrication (ref. item 2.3). A number of valves are under consideration for this function.
- 2.7 Locked Enclosure Since the setting of the pressure regulators is so delicate and critical, adjustments must be made by authorized personnel only. For this reason, the (3) regulators (item 2.5) and the (3) solenoid valves (item 2.6) will be installed inside a locked oiltight enclosure. However, since the pressure regulators must bleed air to maintain their precision, a breather hole will be provided in the bottom of the box with a filter/ muffler installed to block entry of dirt or other ojects into the box.

The regulators with gages and the solenoid valves with a terminal strip will be premounted and plumbed on a metal panel insert. This panel can be quickly mounted in the enclosure with

(4) nuts, (2) air lines, and a 4-wire electric cable. If necessary the panel can be just as easily removed for repair without disturbing the air line to the clutch or to the compressor.

If the compressor (item 2.2) is not to be used, another source of clean dry compressed air can be connected to the input fitting to this enclosure, and the system will work in identical fashion.

2.8 Zero Speed Switch - A true jam of the conveyor will cause the system to stop. A zero speed switch can detect this condition and cut the power to the drive motor. This becomes more useful when there is a slip clutch of some type since the motor could go on running until the clutch burns up. In the case of the Posidyne unit, the internal temperature switch would shut down the system before the unit were damaged.

The zero speed switch need not be set to trigger on zero speed but can be adjusted to operate whenever the clutch driven member slows below a pre-set minimum speed. This set speed must be somewhere below the slowest of the speeds on the 3-speed motor. Since the slowest conveyor motor speed is 850 RPM, the zero speed switch could be set to operate below 500 RPM.

In order to avoid shutting off the system during start-up, this switch must be bypassed. A start-up timer shorts across the switch contact for the length of time normally required for the conveyor to get up to speed. Thereafter a jam would operate the switch to shut off the system.

III. - OPERATIONAL PROCEDURES

- 3.1 Operating Sequence:
- a. Operator presses "ON" pushbutton at Master Control Station to provide power to the conveyor controls, and selects the running speed.
- b. Operator presses one of the "UP" or "DOWN" pushbuttons to initiate the start sequence.
- c. Start delay timer (UTR = up, DTR = down) seals in and begins timing down.
- d. Corresponding motor starter is energized to accelerate the motor and air compressor to running speed.
- e. Simultaneously, the various warning horns sound to warn personnel to move clear of the conveyor mechanism.
- f. At time out of the start delay timer, the horns shut off and the start-up timer is energized.
- g. At the same time the UP or DOWN solenoid valve is energized along with the START-UP solenoid valve, to apply pressure to the Posidyne clutch.
- h. The Vertiflo conveyor accelerates to speed.
- i. At time out of the start-up timer, the START-UP valve is de-energized to drop the clutch pressure back to the jam protection level.
- j. Simultaneously the by-pass circuit around the zero speed switch is opened, providing the system with full overload protection.

- k. If a jam should occur, torque will rise to the level set on the Posidyne and the clutch will slip, leaving the motor running.
- 1. As soon as the conveyor slows so that the clutch output drops below 500 RPM, the zero speed switch de-energizes the motor circuit to stop the motor.
- m. If the jam occurs during the start-up time delay, the clutch will slip at a higher torque, and then the zero speed switch will shut everything off when the start-up timer times out.
- 3.2 Clutch Set-Up Procedure (by qualified personnel only)
 If the air supply to run the clutch is derived from a compressor

 powered by the conveyor drive motor, a cut-out switch will be

 installed in the regulator box to de-energize all of the start-up

 cycle except the motor itself.
- a. Unlock and open the locked pressure regulator box, then turn off the conveyor out-put switch inside.
- b. At the nearest control box start the conveyor drive motor and air compressor in either direction. This should provide pressure to the (3) air regulators inside the box. NOTE: If an external air supply is used instead of a compressor, turn this air on and ignore steps a and b.
- c. Choose the torque requirements for each of the three operating conditions: start-up, up running and down running.
- d. From the table provided, compute the exact air pressure requirements in each case, and adjust the respective regulators until these pressures are available as read on the precision gages provided.

- e. Restart the conveyor by turning the cut-off switch on. The horns will sound as usual prior to start-up. Watch the pressure gages to see if there is any shift in pressure as the air valves operate to start the clutch.
- f. Close and lock the regulator box.
- 3.3 Clutch Test Procedure It is necessary for the conveyor manufacturer at some point to determine the actual torque and corresponding air pressure requirements of the clutch during each phase of the conveyor operation.
- a. Start the unloaded conveyor in the DOWN direction at the highest speed, and open the locked pressure regulator box.
- b. Turn the pressure on the "down" regulator to zero, the conveyor should stop.
- c. Raise the pressure to 22 PSI (or 41 PSI for "B" Model) to release the brake, then slowly raise the pressure until the conveyor is driven in full synchronism with the motor.
- d. Repeat step c with a full load riding down on each tray.
- e. Take the higher pressure valve from steps c and d, add 2 PSI and adjust the "down" regulator to this valve.
- f. Repeat steps b to e with the "up" regulator and the conveyor moving at the highest speed in the UP direction.
- g. With the conveyor at the highest speed, start it in the UP direction, with full load on each tray.
- h. Measure the time from the shut-off of the horns until the conveyor is at full speed.
- i. Determine if this acceleration ramp is acceptable. If not, increase or decrease the pressure on the "start-up" regulator in increments no larger than 1 PSI, and repeat steps g and h.

NOTE: A longer acceleration ramp allows a lower torque setting at lower pressure, and better jam protection on start-up. The start-up timer must be adjusted to agree with this ramp.

- j. When the desired acceleration ramp is formed, record this pressure setting as well as the pressures determined in step e, for future reference.
- k. Close and lock the regulator box.

IV. - COMPARISON OF METHODS FOR TORQUE LIMITING

There are a number of ways to limit the torque transmitted by the conveyor drive system. Below is a breakdown of the methods showing advantages and disadvantages, and specifically the reason that method was not chosen.

EST. COST OF UNIT & REQD. ACCESSORIES	\$70 per motor speed, plus cost of brake	\$500 for clutch/ brake unit and (3) adj. voltage P.S.	\$800 for unit & (3) P.S. plus cost of brake	\$600 for unit plus cost of brake	\$2000 plus for clutch & controls, plus cost of separate brake
DISADVANTAGES	Inertia of motor can produce high torques even after power is snut off separate brake is reqd., closely set cutoff valve may react to transients.	Not very accurate or repeatable on torque setting, firction discs need periodic replace-ment	Unit cannot be mtd. vertically, included brake is not fail-safe and will require a separate spring operated brake which needs maintenance.	Single torque setting permitted must be high enough to take start-up torque without releasing, reset of the unit is a definite problem, cannot be adjusted while conveyor is running, separate brake required.	Expensive, no direct speed lock between motor & conveyor, brake is not fail-safe and will require a separate spring operated brake which needs maintenance.
the reason that method was not chosen: ETHOD	Inexpensive, quick reacting senses load directly off the motor.	Inexpensive, simple to install, easy to select torque settings, different torque for different situations.	Highly accurate remote sotting of torques, virtually no maintenance required.	Instantaneous release of jam tension to free-wheeling condition, single to install, no perepherical accessories required except L.S.	Highly accurate remote setting of torques, virtually no maintenance regd., can be mtd. in any position, different torques for each situation.
the reason that met	l. Instantaneous Trip Overcurrent Relay	2. Adj. Voltage Friction Clutch/Brake	3. Adjustable Voltage Magnetic Particle Clutch/Brake	4. Ball Detent Torque Jimiter	5. Eddycurrent or Hysteresis Clutch

(14)

IV. - COMPARISON OF METHODS FOR TORQUE LIMITING (CONTINUED)

EST. COST OF UNIT	t \$1000, plus cost of brake.	\$600 for unit, plus \$400 for scs accessories. e- ies to to ate	Air supply and controlling \$1000 for unit accessories required, plus \$400 for extra cost for vertical accessories. mount, expensive to some extent.
DISADVANTAGES	Inaccurate, difficult to adjust, expensive for what it does, no direct speed lock between mtr. and load, requires separate brake.	Not very accurate or repeatable on torque sitting, friction discs need periodic replacement, air supply and controlling accessories required, air needed to apply brake or separate brake required.	Air supply and controllist accessories required, extra cost for vertical mount, expensive to some extent.
ADVANTAGES	Single simple to install unit, low maintenance requirements.	Simple to install, easy to select torque settings, different torque for different situations.	Simple to install, easy to remotely select torque, different torque for different situations, virtually no maintenance required, quick reacting, can be mtd. in any position. fail-safe braking.
METHOD	6. Hydraulic/fluid Coupling	7. Air Actuated Friction Clutch/Brake	8. Posidyne Oil-bathed Friction Disc Clutch/ Brake

All methods except #1 require some switch to detect the slip or zero speed condition to shut-off the drive motor. NOTE:

andring and something the second some solds. The solds of the solds of the solds and the solds are

Rating 0 - 1 = Ideal

2 - 3 = Acceptable

4 = Undesirable

	Posidyne Oil-Bathed Friction Disc Clutch/Brake	Air Actuated Friction Clutch/Brake	Hydraulic or Fluid Coupling	Eddy-Current or Hysteresis Clutch/Brake	Ball-Detent Torque Limiter	Adjustable Voltage Magnetic Particle Clutch	Adjustable Voltage Friction Clutch/Brake	Instantaneous Trip Overcurrent Relay(s)		1
	ယ	2	ယ	4	2	2	2		UNIT ITSELF	
	_	2	ယ	2	ယ	2		w	ADDITIONAL BRAKE REQUIRED	
	ယ	ယ	ယ	ယ	0	2	2		ACCESSORIES REQUIRED	
	ယ	ယ	ယ	ယ		ယ	2		INSTALLATION	COST
	2	_	4	-	—	4	-	0	MOUNTING POSITION	-
	ယ	ယ	ယ	2		2	~	-	SIZE OF UNIT AND ACCESSORIES	
	2	2		2	0	2	2	0	POWER REQUIREMENTS	
		2	w	-	ယ	-	ယ	2	ACCURACY AND REPEATABILITY	EFFE(
	: 2	2	4	2	4	2	2	ယ	MULTIPLE SETTINGS FOR DIF. SITUATIONS	FEC
	•	ယ	4	ယ	4	ယ		4	FAIL-SAFE BRAKING	VII
	***	_			_	-	_	2	REACTION TO JAM CONDITION	ENESS
		~	2				2	~	PROTECTION OFFERED FROM JAM	ESS
			ယ		ယ		-	-	EASE OF SETTING TORQUE(S)	C
			4	-	4		-		ABILITY TO SET TORQUE DURING RUNNING (remote)	USEFULLNESS
		ယ	ယ	-	2		ယ	_	MAINTENANCE REQUIRED	ULL
		~	4	2	~	~	ယ	ယ	INDICATION OF TORQUE SETTING	NE
			,	-	4	-	; -	2	RECOVERY FROM JAM SITUATION	SS
	28	ಜ	क	8	 ക	8	28	28	TOTAL	

V. - CONCLUSION

Since jams are a serious problem with conveyor of this type, it is important to use the best available system to protect against the effects of a jam. A thorough study of the various torque limiting devices on the market leads to the conclusion that the one chosen, Posidyne, offers the best all around capabilities. Its advantages outweigh its disadvantages.

The operational and maintenance requirements of the chosen clutch/brake system are no worse than those of the current system, and could offer some improvement. Every part of the system is chosen to minimize maintenance requirements. The compressor V-Belt is the only item which may require regular maintenance; the clutch pressure plates should never need replacement.

The unit not only offers automatic torque selection for the different phases of operation, but set-up of the torque levels is much easier than adjusting the spring tension on a standard friction or ball-detent clutch.

INVESTIGATION TO DETERMINE IF

INTERNAL BRACING

CAN HE USED TO ELIMINATE

EXTERNAL STIFFENERS ON

WATERTICHT TRUNK APPLICATIONS

FOR

VERTICAL STORES CONVEYORS

USN CONTRACT NUMBER NOCO24-72-C-5500
PARTIAL FULFILIMENT OF LINE ITEM OCO4:
CDRL ITEM BOOIAK

Submitted: November 9, 1976

By: Kornylak Corporation

Hamilton, Ohio 45011

TRUNK REDESIGN STUDY

CONTRACT NO. N00024-72-C-5500

DIRECTED BY DESIGN REVIEW MEETING REF. PARAGRAPH 12, MINUTES OF 22 JUNE 1976 MEETING

TO DETERMINE IF INTERNAL BRACING

CAN BE INCREASED TO ELIMINATE EXTERNAL

STIFFENERS ON WATERTIGHT TRUNK APPLICATIONS

CONTENTS

SIDE PANEL STUDY SECTION I
FRONT & REAR PANEL STUDY SECTION II

OPTIONAL SIDE PANEL DESIGN SECTION III

SECTION I

SIDE FANEL STUDY

A study of the side panel in an effort to eliminate the outside stiffeners by increasing the thickness of the hat section and adding a 3/8 thick rib in place of the shield support.


Reference Drawing:

Panel sizing with stiffeners 2-1026-SC9

Sheet 2 of 2 Rev. B

CALCULATIONS ARE BASED ON THE FOLLOWING

12 DDS 1100-4 APPENDIX B



(b) BEAM FIXED AT BOTH ENDS.


R.= REACTION AT 0.

R.=REACTION AT 1.

M-BENOING MOMENT AT O.

M = BENDING MOMENT AT 1. 0
PIE 9
No = LOAD PER UNIT OF LENGTH AT 0.


M = LOAD PER UNIT OF LENGTH AT 1.



362

STAINGTH OF MATERIALS

Movement of Innertic of Built-up Sections. — The usual method of calculation the moment of inertia of a built-up section involves the calculations of the momen of inertia for such element of the section about its own neutral axis, and the translating of this moment of inertia to the previously found movemal axis of the stability postion. A much simpler method that can be used in the case of up section, which can be divided into recomments be added by lines most



and preparationize to the numeral axis is the so-called takeiner method beard the the features $I=\frac{h\left(h^{2}-h^{2}\right)}{\ln \sinh k I}$ in which I=0 the seasons of leaves arise III.

Fig. 2, and 3, 5 and 3, are dimensions as given in the same Mangasion.

The method may be illustrated by applying it to the sention shown in Fig. 3; and far simplicity of calculation shown " memod " in Fig. 3. The calculation may then be utherised in shown in the assumpting table. The distance input the same be uthered as d) is found by divident of the present of the geometrical measures by the area. The excepted of inserties above the same of the geometrical measures by the area. The excepted of inserties above the same this area that measures of inertia above the same this measures of inertia above the same the.

Section.	Brendth	Height.	Area b (k - b)	*	Manual b (b, 5 - 27) 2	4.2	7 shoot supplied to 1 (2) 1 (2
A B C	E. 500 0. 53 E 0. 229	0.115 0.615 1.500	0.187 0.266 0.191	0.016 0.391 1.250	0.002 0.208 9.203	0.000 0.544 3-373	6 129 6 26) 6 46
			1 - 0.644	1	(-0.315	l p	g = 0.372 L


The distance d from DE, the sale through the base of the configuration, $\Phi^{(0)}$

The manner of inestinal the entire section with relations to the section $I_{H} = I_{BH} - Ad^2$

S = Max. Allowable Stress = 27,030 (Per Gen. Spec. for Ships of USN Section 100, Pg. 2, Line 25)

Use 60t for effective plate width or stiffener spacing, whichever is less. (Per LDS,1100-3-e)

HEAD PRESSURE FROM 28.44 to 23.1 P.S.I.



$$W_0 = 23.1 \times 20 = 462$$
, $W_1 = 28.44 \times 20 = 568.8 \#/in$. of length $X = \frac{144}{106.8} \left[-462 + \sqrt{\frac{568.8^2 + (568.8 \times 462) + 462^2}{3}} \right] = 73.24 \text{ in}$.

 $R_0 = \frac{144}{6}$ (2 x 462 + 568.8) = 35827.2 in. lbs.

M = 35827.2 x 73.24 -
$$\frac{462 \times 73.24^2}{2}$$
 - $\frac{106.8 \times 73.24^3}{864}$ = 1356678.8 in. lbs.

Z reqd. =
$$\frac{1336678.8}{27000} = \frac{49.5}{27000}$$
 in. 3 for the above condition with one vertical stiffener at 20" location

With a horiz. stiffener located at 6'-0" above the base along with a vert. stiffener at 20", the sec. mod. can be reduced as indicated below.


$$X = \frac{72}{52.6} \left[-516.2 + \sqrt{\frac{568.8^2 + (568.8 \times 516.2) \times 516.2^2}{2}} \right] = 36.29$$

$$R_0 = \frac{72}{6}$$
 (2 x 516.2 + 568.8) = 19214.4 in. lbs.

$$M = 19214.4 \times 36.29 - \frac{516.2 \times 36.29^2}{2} - \frac{52.6 \times 36.29^3}{432} = 351562.95 in. lbs.$$

$$z \text{ reqd.} = \frac{351562.95}{27000} = \frac{13.92}{27000} \text{ in.}^3 \text{ at tail frame side panel}$$

HEAD FRESSURE FROM 28.44 TO 25.81 PSI




Hat Section which is used as a stiffener but cannot extend into the tail frame past the 4" lap as shown.

TYP. TAIL FRAME SECT.	14 — E
1.62 -419 2-C 7@14.75 MOCIFIED	20 C 1.87
25 EQUIVALENT	n B 4.95
2 ST. 5 @ 10.5	-5.75

SEC	<u>b</u>	h ₁	A	h ₁ ²	W	h ₁ 3	IDE
A	5.75	.34	1.95	.12	.34	.04	.076
В	.24	4.95	1.11	24.5	2.92	121.28	9.70
С	15	5.2	3.75	27.04	19.05	140.61	96.65
D	1.67	6.4	2.0	40.96	11.62	262.14	67.65
E	14	6.82	5.86	46.51	38.85	317.22	257.04
			14.67		72.78		431.11

SECTION I

HEAD PRESSURE FROM 23.1 TO 17.8 PSI



$$w_0 = 17.8 \times 20 = 356, w_1 = 23.1 \times 20 = 462$$

$$X = \frac{144}{106} \left[-356 + \sqrt{\frac{462^2 + (462 \times 356) + 356^2}{3}} \right] = 73.55$$

$$R_0 = \frac{144}{6} (2 \times 356 + 462) = 28176$$

$$M = 28176 \times 73.55 - \frac{356 \times 73.55^2}{2} - \frac{106 \times 73.55^2}{864} = 998708.8$$


Z Required = 36.98 in. This is the maximum Z required. For the side panel use hat section as stiffener and increase plate thickness to 1/4" and add a 3/8 thick rib in place of the shield support.

See next page for increased hat section calculations.

502.03

Revised Hat Section

Increase material thickness from 3/16" to 1/4". Add new 3/8 thick continuous rib at front shield location.



SEC.	b	h ₁	A	hi ₂	M	h ₁ ³	IDE.
A	15	.25	3.75	.062	. 46	.015	.075
В	3	.5	.75	.25	.28	.125	.11
С	.88	7.75	6.38	60.06	26.31	465.48	136.5
D	.5	9.38	.81	87.98	6.98	825.29	59.96
E	1.5	9.87	.31	97.42	5.9	961.5	68.11
F	9.5	10.12	2.38	102.41	23.7	1036.43	237.28

$$d = \frac{63.63}{14.38} = 4.42$$


In. =
$$502.03 - 14.38 \times 4.42^2 = 221.1$$

63.63

$$z = 38.85 \text{ in.}^3$$
,

14.38

This exceeds 36.98 in. 3 required, reference Page 5



Typ. trunk side panel. The maximum span of a panel will be 12'. A horizontal stiffener should be at each span unless a deck is at this location.

The bottom 12' panel will require a horizontal and vertical stiffener as shown.

Panel plate thickness will be 1/4 throughout the length of the trunk.

Total weight = 6885 lbs. per side



SECTION I

CONCLUSION

The outside vertical side panel stiffeners can be eliminated by doing the following:

- 1. Adding horizontal and vertical stiffeners to the bottom panel since the hat section cannot extend into the tail frame. See Pg. 3 & 4.
- 2. Increasing the thickness of the hat section from 3/16 to and adding a 3/8 thk. rib in place of the shield support.

SECTION II

FRONT & REAR PANEL STUDY

A. STUDY OF THE TRUNK FRONT AND REAR PANEL IN AN EFFORT TO REDUCE THE SIZE & WEIGHT OF THE PANEL TO A MINIMUM WITH STIFFENERS AND MAKE THE PANEL MORE UNIFORM IN CROSS-SECTION. THIS CAN BE DONE BY ADDING HORIZONTAL AS WELL AS VERTICAL STIFFENERS TO EITHER THE INTERNAL OR THE EXTERNAL SURFACE OF THE REAR PANEL AND THE EXTERNAL SURFACE OF THE REAR PANEL AND THE EXTERNAL

REF. DWG. PANEL SIZING WITH STIFFENERS 2-1026-SC 9

SHT 10F2 REV. B

CALCULATIONS ARE BASED ON THE FOLLOWING

DDS 1100-4

I GENERAL FORMULA FOR BEAMS WITH A UNIFORMLY VARYING LOAD SIMPLER FORMULAE FOR DIRECT APPLICATION TO BULKHEAD STIPFENERS ARE STATED LATER!

(A) BEAM PIXED AT BOTH ENDS. ROS REACTION AT O.


RI-REACTION AT I.

M-BENDING MOMENT AT G.

M = BENDING MOMENT AT I.

M = LOAD PER UNIT OF LENGTH AT Q.


M = LOAD PER UMP OF LENGTH AT I.



17 DDS 1100-4 APPENDIX B

(c) SIMPLY SUPPORTED BEAMS


MMAR OCCURS WHEN



362

STRENGTH OF MATERIALS

Moment of Inertin of Built-up Section - The usual method of calculated the moment of inertia of a built-up section involves the calculations of the me of inertia for each element of the section about its own neutral axis, and the tra farring of this moment of inertia to the previously found neutral axis of the way built-up section. A much simpler method that can be used in the case of a section which can be divided into rectangular elements bounded by lines pass



and perpendicular to the neutral axis is the so-called tabular method based the formula $I=\frac{b\left(k_{1}^{2}-k_{2}^{2}\right)}{a}$ in which I= the moment of inertia about and R_{+}^{2}

Fig. 1, and b, h and h, are dimensions as given in the same illustration. The method may be illustrated by applying it to the section shown in Fig. 2 and for simplicity of calculation shown " massed" in Fig. 3. The calculation may then be rabulated as shown in the accompanying table. The distance from the sais DE to the neutral axis or (which will be designated as 6) is found by dividing the sam of the geometrical measures by the area. The moment of inertia some the neutral axis is then found in the usual way by subtracting the area multiplies by of form the moment of inertia about the age DE.

Section	Breadth	Height	Area b (A ₁ b)	*	Morrosst b (k/t = 14) 2	Ąž	Labout man DE 3 (3,2 — 39)
4 8 C	e. 531 0. 219	0.125 0.62 5 1.500	o. 187 o. 166 o. 191	0.016 0.391 2.250	0,013 6,109 0,103	0.002 0.244 3-375	6.03E 0.045 0.228
		4	l = 0.644	3	f = 0.315	Ip	2-0.272


 \mathbf{z} d are DE, the seis through the base of the configuration, is the

The moment of inertie of the entire section with reference to the neutral at

S = Max. Allowable Stress = 27,000 (Per Gen. Spec. for Ships of USN Section 100, Pg. 2, Line 25)

Use 60t for effective plate width or stiffener spacing, whichever is less (Per DDS,1100-3-e)

STIFFENER & PLATE REQUIREMENTS FROM 28.44 TO 23.1 PSI



1 = 144"

Trunk Plating = ½"

Use (60t) for effective width or stiffener spacing (Ref. DDS1100-3-C) whichever is less, in this case 15"

$$W_O = H_O \times S = 23.1 \times 15 = 346.5 = lbs./in. of length$$

$$w_1 = H_1 \times S = 28.44 \times 15 - 426.6 = lbs./in. of length$$

$$X = \frac{144}{80.1} \left[-346.5 + \sqrt{\frac{426.6^2 + (426.6 \times 346.5) + 346.5^2}{3}} \right]$$

 $X = 1.79 \times 40.74 = 72.44 in.$

$$R_0 = \frac{144}{6}$$
 (2 x 346.5 + 426.6) = 26870.4 in. lbs.


$$M = 26870.4 \times 72.44 - \frac{346 \times 72.44^2}{2} - (\frac{80.1 \times 72.44^3}{864})$$

$$M = 1946491.7 - 907826.15 - 35241.47$$

$$M = 1,003,424.2$$
 in. lbs.

Z Reqd. =
$$\frac{M}{S} = \frac{1,003424.2}{27,000} = \frac{37.16}{27}$$
 in.³

SECTION II



SEC	<u>b</u>	hl	A	h ₁ ²	M	h ₁ ³	IDE
A	15	• 5	7.5	.25	1.875	.125	.62
В	.38	7.9	2.81	62.41	11.81	493.04	62.44
С	7.07	8.53	4.44	72.76	36.59	620.65	300.73

14.75 50.27 363.79

$$d = \frac{50.27}{14.75} = 3.4 In = 363.79 - 14.75 x 3.42 = 193.28$$
$$z = \frac{37.67}{14.75} in.3$$

This exceeds 37.16 in. Ref. Pg. 3

Changing the stiffener spacing on Drawing 2-1026-SC9 from 20" to 15" causes the required Z to drop to 37.16 in. 3. The stiffeners will change from (2) St. 10 @ 37.5# to (3) St. 8 @ 25#.


The weight per foot of the plate and stiffeners will remain the same. Wgt. of a $\frac{1}{2}$ " thk. x 5' x 12' plate with stiffeners:

Wgt. of Stiffeners = $3 \times 25 \times 12 = 900$

Wgt. of Plate = 102 x 12 = $\frac{1224}{2124}$ lbs.

 $\frac{2124}{12} = 177 \# / \text{Ft. of Hgt./Side}$

FROM 28.44 TO 25.81 PSI



$$S = 15$$

$$W_{O} = 25.81 \times 15 = 387.15$$

$$w_1 = 28.44 \times 15 = 426.6$$

$$x = \frac{72}{39.45} \left[-387.15 + \sqrt{\frac{426.6^2 + (426.6 \times 387.15) + 387.15^2}{3}} \right]$$

$$z = 1.82 \times 19.88 = 36.28 in.$$


$$R_0 = \frac{72}{6}$$
 (2 x 387.15 + 426.6) = 14410.8 in. lbs.

$$M = 14410.8 \times 36.28 - \frac{387.15 \times 36.28^2}{2} - \frac{(39.45 \times 36.28^3)}{432}$$

$$M = 263671.88$$
 in. lbs.

2 reqd. =
$$\frac{14}{5}$$
 = $\frac{263671.80}{27000}$ = 9.76 in. ³ for vert. stiffeners

HORIZ. STIFFENER, REQUIREMENTS (1) REQD.




Use 60t fcr effective width of plate with stiffener

$$60 \times 1 = 15$$

$$w = 15 \times 25.81 = 387.15$$

$$M = \frac{w1^2}{8} = \frac{387.15 \times 60^2}{8} = 174217.5 \text{ in. lbs.}$$

2 reqd. =
$$\frac{M}{S} = \frac{174217.5}{27,000} = \frac{6.45}{2000}$$
 in.³




NOTE: USE ST 5 @ 10.5 which is the same stiffener reqd. for vert. stiffener's See Pg. 7

SEC	<u>p</u>	h	<u>A</u>	<u>h1²</u>	M	h ₁ ³	IDE
A	15	.25	3.75	.062	.46	.0156	.078
В	.23	3.942	.85	15.54	1.78	61.25	4.69
С	5.25	4.25	1.62 6.22	18.06	6.62 8.86	76.76	27.14 31.90

$$d = \frac{8.86}{6.22} = 1.42$$
 $I_n = 31.9 - 6.22 \times 1.42^2 = 19.35 \text{ in.}^4$ $Z = 6.83 \text{ in.}^3 \text{ This exceeds 6.45 in.}^3 \text{ reqd.}$

VERTICAL STIFFENER REQUIREMENTS (3) REQD.



SEC	b	hı	<u>A</u>	h ₁ ²	M	h ₁ 5	IDE
A	15	. 25	3.75	.062	.46	.0156	.078
В	.24	4.86	1,11	23.62	2.83	114.79	9.13
С	5.75	5.2	1.95	27.04	9.83	140.61	49.49
			6.81		13.12		59 749

 $d = \frac{13.12}{6.81} = 1.93$ $I_n = 58.74 - 6.81 \times 1.93^2 = 33.37 in.^4$

 $z = 10.2 \text{ in.}^3 (9.76 \text{ regd.})$

Wgt. of a $\frac{1}{2}$ x 5' x 12' plate with (3) vert. & (1) horiz. stiffeners:

Wgt. of horiz. stiffener = $5 \times 8.5 = 42.5$ lbs. $(5 \times 10.5 = 52.5)$

Wgt. of vert. stiffeners = $3 \times 10.5 \times 12 = 378$ lbs.


Wgt. of plate = $51 \times 12 = 612$ lbs.

Total Wgt. = 1032.5 lbs.

 $\frac{1032.5}{12}$ = 86.04#/ft. of hgt.

86 lb/lin.ft. vs. 177 lb/lin.ft. (Ref. Section II Pg. 4) is a weight savings of 91 lb/lin.ft.

FROM 23,1 TO 20.45 PSI



$$w_0 = 20.45 \times 20 = 409 \text{ PSI}$$

$$w_1 = 23.1 \times 20 = 462 \text{ PSI}$$

$$X = \frac{72}{53} \left[-409 + \sqrt{\frac{462.2^2 + (462.2 \times 409) + 409^2}{3}} \right] = 36.4 \text{ in.}$$

$$R_0 = \frac{72}{6} (2 \times 409 + 462) = 15360 \text{ in. lbs.}$$

$$M = 15360 \times 36.4 - \frac{409 \times 36.4^2}{2} - \frac{53 \times 36.4^3}{432}$$


$$= 559104 - 270954.32 - 5916.92$$

M = 282232.76 in. lbs.

 $z \text{ reqd.} = 10.45 \text{ in.}^3$

NOTE: (2) St. 5 @ 10.5 stiffeners from 23.1 PSI to 20.45 PSI have a Z of 10.2 in. 3 per stiffener when a Z of 10.45 is required. Therefore (2) as shown is not strong enough. Run (3) St. 5 @ 10.5 up to 20.45 PSI. See next page for (3) stiffener calculations.

FROM 23.1 TO 20.45 PSI



$$w_0 = 20.45 \times 15 = 306.75$$

$$w_1 = 23.1 \times 15 = 346.5$$

$$x = \frac{72}{40} \left(-306.75 + \sqrt{\frac{346.5^2 + (346.5 \times 306.75) + 306.75^2}{3}} \right)$$

z = 36.14 in.

 $R_0 = \frac{72}{6}$ (2 x 306.75 + 346.5) = 11520_{1N}

 $M = 11520 \times 36.14 - \frac{306.75 \times 36.14^2}{2} - \frac{40 \times 36.14^3}{432}$

= 416332.8 - 200323.1 - 4370.59


M = 211639.11 in. lbs.

Z reqd. = 7.84 in. 3 per stiffener

Use (3) St. 5 @ 10.5 with a Z of 10.2 in. 3. See Pg. 7.

 $S = \frac{M}{2} = \frac{211639.11}{10.2} = 20748.9 \text{ PSI}$ This is within 27000 PSI allowable stress.

FROM 20.45 TO 17.8 PSI



$$x = \frac{72}{53} \left(-356 + \sqrt{\frac{409^2 + (409 \times 356) + 356^2}{3}} \right) = 36.42 \text{ in.}$$

$$R_0 = \frac{72}{6}$$
 (2 x 356 + 409) = 13452 in. lbs.

$$M = 13452 \times 36.42 - \frac{356 \times 36.42^2}{2} - \frac{53 \times 36.42^3}{462}$$

M = 489921.84 - 236102.76 - 5541.8


M = 248277.28 in. lbs.

$$Z \text{ reqd.} = \frac{248,277.28}{27000} = 9.2 \text{ in.}^3$$

Use (2) St. 5 @ 10.5 with & thick plate which gives a Z of 10.2 in. 3 per Tee, see Pg. 7.

$$S = \frac{248277.28}{10.2} = 24340.9 \text{ PSI (27000 PSI allowable)}$$

FROM 17.8 TO 15.15 PSI



$$X = \frac{72}{53} \left[-303 + \sqrt{\frac{356^2 + (356 \times 303) + 303^2}{3}} \right] = 36.48 \text{ in.}$$

$$R_0 = \frac{72}{6}$$
 (2 x 303 + 356) = 11544 in. lbs.


$$M = 11544 \times 36.48 - \frac{303 \times 36.48^2}{2} - \frac{53 \times 36.48^3}{462}$$

$$M = 421125.12 - 201614.7 - 5569.3 = 213941.12 in. lbs.$$

$$Z \text{ reqd.} = \frac{213941.12}{27000} = 7.92 \text{ in.}^3$$

Use (2) St. 5 @ 10.5 with horiz. stiffener, see Pg. 7.

FROM 12.5 TO 9.8 PSI



$$x = \frac{72}{81} \left(-294 + \sqrt{\frac{375^2 + (375 \times 294) + 294^2}{3}} \right) = 36.72 \text{ In.}$$


$$R_0 - \frac{72}{6}$$
 (2 x 294 + 375) = 11556 in. lbs.

M = 11556 x 36.72 -
$$\frac{294 \times 36.72^2}{2}$$
 - $\frac{81 \times 36.72^3}{432}$ = 216844.17 in. lbs.

$$Z \text{ reqd.} = \frac{216844.17}{27000} = 8.03 \text{ in.}^3$$

Use St. 5 @ 10.5 with % thick plate with a Z of 10.2, see Pg. 7.

$$S = \frac{216844.17}{10.2} = 21259.2 \text{ PSI} \quad (27000 \text{ PSI allowable})$$



Typical trunk showing rear panel arrangement of vertical and horizontal stiffeners with & thick plate stiffener arrangement to apply to front panels between door frames as required.

SECTION II Pg. 14

CONCLUSION


The plate of the trunk panel can be kept at ½ thick throughout the trunk by adding horizontal and vertical stiffeners as indicated. Except where noted, all stiffeners will be St. 5 @ 10.5. This will enable a nontight trunk to be changed to a watertight trunk with a minimum amount of change.

- 1. The maximum deck height is 12 foot.
- 2. Horizontal stiffeners are to be spaced at no more than 6 foot apart except at the deck location where the horizontal stiffener will be eliminated.

At each deck location the vertical stiffeners are to be cutout in the field at installation so that the deck closure material can extend on into the trunk side panel.

DOOR FRAME


Strength of door frame at lowest position on trunk:



$$X = \frac{66}{43.2} \left(-753.6 + \sqrt{\frac{796.8^2 + (796.8 \times 753.6) + 753.6^2}{3}} \right) = 33.15$$


$$R_0 = \frac{66}{6}$$
 (2 x 753.6 + 796.8) = 25344 in. lbs.

M =
$$25344 \times 33.15 - \frac{753.6 \times 33.15^2}{2} - \frac{43.2 \times 33.15^3}{396} = 422105.5 in. lbs.$$



Typ. Door Frame (Ref. Dwg. 2-1026-117F)

See next page for Frame Sect. calculations.



Assume that the side panel will carry part of the load.

SEC	<u>b</u>	h ₁	<u>A</u>	h12	<u>M</u>	h ₁ ³	IDE
A	.25	1.5	.375	2.25	.28	3.375	. 28
В	4.75	1.75	1.187	3.06	1.92	5.35	3.12
С	.25	9.5	1.937	90.25	10.89	857.37	71
D	5.5	10	2.75	100	26.81	1000	261.48
E	2.5	10.25	.62	105.06	6.32	1076.89	64.07
F	.25	15	1.187	225	14.99	3375	191.51
			8.056		61.21		591.46

$$d = \frac{M}{A} = \frac{61.21}{8.056} = 7.59 \qquad I_n = IDE - Ad^2 = 591.46 - 8.056 \times 7.59^2 = 127.37$$

$$Z = \frac{127.37}{7.59} = 16.78 \text{ in.}^3 \text{ (reqd.} = 15.63)$$

CONCLUSION:


Door frame will withstand the maximum water head on the conveyor.

SECTION III

OPTIONAL SIDE PANEL DESIGN

A study of the conveyor side panel in an effort to keep the thickness and weight of the plate at a minimum.

DDS 1100-4 APPENDIX B



ME LOAD PER UNIT OF LENGTH AT D. FIR 9


ME LOAD PER UNIT OF LENGTH AT 1.

(c) SIMPLY SUPPORTED BEAMS $R_{0} = -\frac{1}{6} (2m + m_{0}); R_{1} = -\frac{1}{6} (m_{0} + 2m_{0})$ $F = R_{0} + m_{0} + \frac{(m_{0} - m_{0})x^{2}}{2!}$ $M = R_{0} \times + \frac{m_{0}x^{2}}{2!} + \frac{(m_{0} - m_{0})x^{2}}{4!}$ $M_{MAR} OCCURS WHEN$ $X_{0} = \frac{1}{4} \left[\frac{m_{0} - m_{0}}{3} \right]$ Fig. 14

362

STRENGTH OF MATERIALS

Moment of Inertia of Built-up Sections. — The usual method of calculations the moment of inertia of a built-up section involves the calculations of the moment of inertia for each element of the section about its own neutral axis, and the majoring of this moment of inertia to the previously found neutral axis of the was built-up section. A much simpler method that can be used in the case of a section which can be divided into retrangular elements bounded by lines purely



and perpendicular to the neutral axis is the so-called tabular method based space the formula: $I = \frac{b \cdot (h_0^2 - h^2)}{3}$ in which I — the moment of inertia about axes B_0^2 .

Fig. 1, and b, b and b, are dimensions as given in the same illustration.

The method may be illustrated by applying it to the section shown in Fig. 2: and for simplicity of calculation shown "massed" in Fig. 3. The calculation may then be tabulated as shown in the accompanying table. The distance from the sais DE to the neutral axis as (which will be designated as d) is found by dividing the same of the geometrical measures by the area. The moment of inertia shour the neutral axis is thus found in the usual way by subtracting the area multiplied by of from the moment of inertia about the axis DE.


Tabulated Calculation of Monuest of Innetia

Sertion	Breach	Height by	Area b (k ₂ — b)	¥	Moment b (5,2 - M)	44	I about see D.E. b (b) = i/l
A B C	0.219 6.531 1.508	0. 125 0. 625 1. 500	a. 187 a. 266 a. 191	0.016 0.391 2.350	0.012 0.108 0.203	0.002 0.244 3.375	0.00f 0.043 0.238
		A	-0.644	1	-0.315	I DI	v= 0.277

The distance d from DE, the axis through the base of the configuration, is the neutral axes as is:

The section of inertia of the entire section with reference to the neutral axis start

SECTION III



Side Panel

bottom 12' of trunk length as shown.

$$W_O = 25.81 \times 20 = 516.2 \#/In. of Lg.$$

$$w_1 = 28.44 \times 20 = 56.88 \#/In. of Lg.$$

$$X = \frac{72}{52.6} \left(-516.2 + \sqrt{\frac{568.8^2 + (568.8 \times 516.2) + 516.2^2}{3}} \right) = 36.29$$


$$R_O = \frac{72}{6} (2 \times 516.2 + 563.8) = 19214.4 \text{ in. 1bs.}$$

$$M = 19214.4 \times 36.29 - \frac{516.2 \times 36.29^2}{2} - \frac{52.6 \times 36.29^3}{432} = 351562.95 \text{ in. lbs.}$$

Z Required =
$$\frac{351562.95}{27000} = \frac{13.02}{27000}$$
 In.³

For horizontal stiffener use St. 5 @ 10.5 In.³. See Pg. 7 of conveyor rear panel study.

For vertical stiffener use St. 5 @ 10.5 In.3. See next page for calculations.



Keep thickness of side panel at \(\frac{1}{4} \) thick as indicated. Use 60t for effective width of plating = 15". Reference drawing 2-1026-99F tail frame.

SEC	b	hl	A	h ₁ ²	М	h ₁ 3	IDE
A	5.75	.34	1.95	.12	.34	.04	.076
В	.24	4.95	1.11	24.5	2.92	121.28	9.7
С	15	5.2	3.75	27.04	19.05	140.61	96.65
D	1.67	6.4	2.42	40.96	11.62	262.14	67.65
Е	14	6.83	5.86	46.51	38.85	317.22	257.04
			15.09		72.78		431,11


$$d = \frac{72.78}{15.09} = 4.82 \qquad I_n = 431.11 - (15.09 \times 4.82^2) = 80.53 \text{ in.}^4$$

$$Z = 16.7 \text{ in.}^3$$

$$Z \text{ reqd.} = \frac{13.02}{4.82}$$

Conclusion

h thick plate with horizontal and vertical stiffeners as shown is okay for tail section. Head' Pressure From 25.81 to 23.1 P. S. I.



$$W_0 = 23.1 \times 20 = 462 \text{ #/in. of length}$$
 $W_1 = 25.81 \times 20 = 516.2 \text{ #/in. of length}$

$$X = \frac{72}{53.2} \left[-463 + \sqrt{\frac{516.2^2 + (516.2 \times 462) + 462^2}{3}} \right] = 36.33 \text{ in.}$$

$$R_0 = \frac{72}{6} (462 \times 2 + 516.2) = 17282.4 \text{ in. lbs.}$$

$$M = 17282.4 \times 36.33 - \frac{462 \times 36.33^2}{2} - \frac{53.2 \times 36.33^3}{432} = 317074.83$$

$$Z \text{ Required} = \frac{317074.83}{27000} = 11.74 \text{ in.}^3$$

From 23.1 To 20.42 P. S. I.

$$W_{0} = 20.42 \times 20 = 408.4 \qquad wl = 23.1 \times 20 = 462$$


$$X = \frac{72}{53.6} \left[-408.4 + \sqrt{\frac{462^{2} + (462 \times 408.8) \times 408.8^{2}}{3}} \right] = 36.36 \text{ in.}$$

$$R_{0} = \frac{72}{6} (408.4 \times 2 + 462) = 15345.6 \text{ in. lbs.}$$

$$M = 15345.6 \times 36.36 - \frac{408.8 \times 36.36^{2}}{2} - \frac{53.6 \times 36.36^{3}}{432} = 281774.88$$

$$2 \text{ Required} = \frac{281774.88}{27000} = \frac{10.43}{27000} \text{ in.}$$

Head Pressure From 17.8 to 12.5 P. S. I.



$$X = \frac{144}{106} \left(-250 + \sqrt{\frac{356^2 + (356 \times 250) \times 250^2}{3}} \right) = 74.09 \text{ in.}$$

$$P_0 = \frac{144}{6} (2 \times 250 + 356) = 20544$$

$$M = 20544 \times 74.09 - \frac{250 \times 74.09^2}{2} - \frac{106 \times 79.09^3}{864} = 775243.38$$

Z Required =
$$\frac{775243.38}{27003}$$
 = $\frac{28.71 \text{ in.}^3}{27003}$ standard section is not strong enough. See Pg. 8


By adding a horizontal stiffener to the above, we can change the requirements.

$$w_0 = 15.1 \times 20 = 302$$
, $w_1 = 17.8 \times 20 = 356$
 $X = \frac{72}{54} \left(-302 + \sqrt{\frac{356^2 + (356 \times 302) + 302^2}{3}} \right) = 36.49 \text{ in.}$
 $R_0 = \frac{72}{6} (2 \times 302 + 356) = 11520 \text{ in. lbs.}$

$$M = 11520 \times 36.49 - \frac{502 \times 36.49^2}{2} - \frac{54 \times 36.49^3}{432} = 213231.88 in. lbs.$$

Z Required =
$$\frac{213231.88}{27000} = \frac{7.9 \text{ in.}^3}{}$$

Head Pressure From 12.5 To 7.1 P. S. I.




$$X = \frac{144}{108} \left(-142 + \sqrt{\frac{250^2 + (250 \times 142) + 142^2}{3}} \right) = 75.28$$

$$R_0 = \frac{144}{6} (2 \times 142 + 350) = 15216$$

$$M = 15216 \times 75.28 - \frac{142 \times 75.28^2}{2} - \frac{108 \times 75.28^3}{864} = 689770.7 \text{ in. lbs.}$$

$$Z \text{ Required} = \frac{689770.7}{27000} = \frac{25.54 \text{ in.}^3}{2}$$

Cross Section 2-1026-P3-A-F



SEC.	þ	h _l	A	h ₁	М	h ₁ ³	IDE
A	15	.25	3.75	.062	.46	.015	.075
В	.375	9.75	3.56	95.06	17.81	926.86	115.85
С	1.437	9.93	.269	98.6	2.54	979.15	25.04
D	9.5	10.12	1.78	102.4	18.05	1036.44	181.42

9.359 38.86


322.385

$$d = \frac{38.86}{9.359} = 4.15$$
 In. = 322.385 - 9.351 x 4.15² = 161.19

Minimum
$$z = \frac{161.19}{5.97} = \frac{27 \text{ in.}^3}{}$$

Conclusion

The standard side panel with a 1/4 thick plate and a 3/16 thick hat section without outside stiffeners is good down to 28 ft. head or 12.5 P. S. I. The required Z = 25.54 in. 3 from Pg. 6 The available Z = 27 in. 3



Typ. trunk side panel showing arrangement of vertical and horizontal stiffeners with 1/4 thick plate.

The standard side panel with a 1/4 thick plate and 3/16 thick plate hat section can be used down to 12.5 P. S. I. without any outside stiffeners below 12.5 P. S. I. Horizontal stiffeners will be added at 6 ft. intervals as indicated. At the bottom section (1) vertical stiffener will also be added. All outside stiffeners will be St. 5 @ 10.5.

The maximum length of a panel will be 12' long. A horizontal stiffener should be at each 12' span unless a deck is at this height.

Total weight = 5564# per side

This is comparable with 6885 lbs. per Section I, Pg. 7

Conclusion

A standard side panel with a 1/4 thick plate and a 3/16 thick hat section can be used the full length of the trunk with a minimum amount of change to make it W. T. by doing the following:

- 1. Add horizontal and vertical stiffeners to the bottom panel since the hat section cannot extend into the tail frame.
- 2. Add horizontal stiffeners at 6' intervals as indicated on Pg. 9.
- 3. All calculations have not taken the horizontal channels located on the inside of the side panels into consideration although they do add strength to the construction of the trunk.

The main advantage to this study is that the basic trunk will remain the same whether the trunk is $W.\ T.$ or Non T.

The addition of a minimum amount of stiffeners will be required to change from a Non T. trunk to a W. T. trunk.

DESIGN STUDY

OF

CONVEYOR OVERLOAD PROTECTION REVISION I

CONTRACT N00024-72-C-5500

CDRL ITEM BOOLAK

Submittal Date:

Submitted By: KORNYLAK CORPORATION

400 Heaton Street

Hamilton, Ohio 45011

CONVEYOR OVERLOAD PROTECTION REVISION I INTRODUCTION

- REF: (a) NAVSEC LETTER 6164D2/SJO SER. 685
 - (b) KORNYLAK LETTER 2-1026/D. SMITH DATED 29 June '76
 - (c) CONVEYOR SPEC. SHIPS C-5552
- 1. In compliance with paragraph 2 of ref. (a), this study shall cover the following:
 - (a) Review of mechanical friction clutches with torque limiting capabilities.
 - (b) Also an evaluation of positive type torque limiting devices.
 - (c) An electrical overload device to monitor the power circuit as part of the conveyor overload protection.
- 2. Based on the parameters formed by ref. (a) and (c), along with the reasons for disapproval of the posidyne unit submitted with ref. (b), the different types of torque limiting devices has been narrowed down to a select few which have such features as simplicity, minimal maintenance, economical and no external power requirements for transmitting and/or limiting torque.
- 3. Although friction type clutches are the most common type of torque limiting device, a realtively new positive type device which uses a spring loaded ball or key detent for limiting torque transmittal will also be reviewed and considered in this study.

4. Since the tray overload protection device as defined in paragraph 3.4 (b) and 3.4.22 (d) of ref. (c) has been temporarily shelved in Phase II, another type of electrical overload device must be selected to provide added protection to the conveyor system.

TABLE OF CONTENTS

ITEM	PAGE
INTRODUCTION	i,ii
TABLE OF CONTENTS	iii
1. TORQUE LIMITER LOCATION	1,2
2. DESIGN REQUIREMENTS AND LIMITATIONS	3,4,5
3. MECHANICAL FRICTION TYPE CLUTCHES	6 thru 22
FIG. 3	9
FIG. 4 and 4A	10,11
FIG. 5 and 5A	12,13
FIG. 6 thru 6H	14 thru 22
4. POSITIVE TYPE TORQUE LIMITERS	23,24
4.6 AUTOGARD TORQUE LIMITER	25 thru 35
FIG. 7	2 7
4.7 FERGUSON MACHINE RITE-TORQ TORQUE LIMITE	R 36 thru 52
FIG. 8	38
FIG. 9	44
4.8 FORMSPRAG RESET CLUTCH	53 thru 70
FIG. 10	62
4.9 HELLAND TORQ-TENDER	71 thru 84
FIG. 11	75
5.0 TORQUE LIMITER COMPARISON & SELECTION	85,86,87
6.0 ELECTRICAL OVERLOAD DEVICE SELECTION	88,89,90
FORMSPRAG BULLETIN X-3012-A (4 pages)	91 thru 94
DED INCODUNCTO CONTRACTO BULLETIN DED 2003	05 thru 10


TORQUE LIMITER LOCATION

- 1.1 Most torque limiting devices are recommended, by the manufacturer, to be located on the output shaft or slow speed side of the reducer (ref. Fig. 1) for the following reasons:
 - (a) Helps prevent friction disc glazing.

1.


- This can occur during continuous or prolonged slippage at high speed.
- (b) Dampens motor startup torque.
- This will allow a closer torque setting to be made to full load requirements.
- (c) Reducer error in torque setting.

An error in torque setting on the input side of the reducer is magnified by the reducer ratio at the output shaft.



Torque Limiter located on Output Shaft of Reducer

- 1.2 The torque limiter location as shown in Fig. 1 is not ideal for application in a drive train for a vertical type conveyor because the location is on the load side of the reducer and also in between the brake and the load. Eventual wear or even accidental lubrication from excessive lubricant on a drive chain could cause slippage under load, allowing the conveyor to backtravel and cause damage.
- 1.3 Therefore, the proper location for the torque limiter in this case and as specified by SPEC. SHIPS-C-5552, is in between the motor and the input shaft of the reducer (ref. Fig. 2) thus defeating the advantages mentioned in paragraph 1.



2. DESIGN REQUIREMENTS AND LIMITATIONS

- 2.1 Requirements by specification
 Ships C-5552 Ref. paragraph 3.5.13 & 3.5.15
 - (a) Friction clutch to include a flexible coupling.
 - (b) Adjustable setting to allow slippage between 110-115% of rated full load.
 - (c) Further adjustment required to allow dynamic testing per paragraph 4.3.2.

2.2 TORQUE LIMITER SIZE SELECTION

- 2.2.1 Drive calculations per K.C. Drawing 2-1026-DC Rev. A indicate that drive sizes from 3 HP to 10 HP inclusive are required to cover the required 20 ft. to 90 ft. center distance range of conveyors.
- 2.2.2 Past purchases of standard 85# Capacity Vertical Stores Conveyors for Navy ships, ranging from the shortest units on the "LSD" Class ships to the tallest units on the "AS" and "CVA" Class ships, provide the following input collected from 255 installations.
 - 13%, (a quantity of 34) would have a 3 HP drive
 - 72%, (a quantity of 184) would have a 5 HP drive
 - 13%, (a quantity of 35) would have a 7½ HP drive
 - 2%, (a quantity of 5) would have a 10 HP drive

 The above figures are based on the 85# size conveyor

 center distances applied to the drive selection chart

 on the above drawing, using the 60" tray space column.

2.2.3 The torque range and bore sizes required for each drive size are as follows,

	Drive H.P.	3	5	7눌	10
	Operating Lb. Ft.	9	15	22.5	30
	Torque Lb. In.	(108)	(180)	(270)	(360)
(1)	Input Motor Bore	1.625	1.625	1.875	1.875
(2)	Output Reducer Bore	1.625	1.750	1.875	2.000
	Adj. Range 50% to 150% of Oper. Torque Lb. In.	54	90	135	180
		162	270	405	540

- (1) Motor input bore based on 3 speed constant torque motors using 254T through 286T Frames.
- (2) Reducer bore sizes based on using Core Drive HU

 Models with 4", 6", 7" and 8" C.D.

2.3 Other design requirements:

- (a) Automatic shut-off limit switch activated by Torque Limiter at point of overload.
- (b) Bi-directional operation.
- (c) All position (vertical or horizontal) mounting
- (d) Externally and infinately adjustable.
- (e) Capable of withstanding frequent overload.
- (f) Steel construction (no cast iron permitted).
- (g) Automatic reset in either direction.
- (h) Maintain accuracy of trip setting under abnormal conditions. Such as corrosive salt laden atmosphere, ambient temperature range of -20° to $+120^{\circ}$ F, high humidity, dusty or oily atmosphere.

- (j) Limited maximum setting and/or tamperproof setting.
- (k) Enclosed unit (for environmental protection).
- (1) Minimum maintenance.

- 3. MECHANICAL FRICTION TYPE CLUTCHES
- 3.1 The most common torque limiting devices available are mechanical friction type clutches which basically consist of two different designs, Rim or Drum and axial type.
- 3.2 The rim or drum type (ref. Fig. 3) are of the internal-expanding or external-contracting shoe type. Both types rely on a combination of air pressure and release springs or centrifugal force for centrol. The expanding type is commonly used for continuous slippage in controlled torque applications while the contracting type is best suited for cyclic applications, neither of which are suitable for vertical conveyor operation or overload protection.
- 3.3 The axial type consist of the following designs, cone, disc and multidisc.
- 3.3.1 CONE DESIGN Ref. Fig. 4 and 4A

The present tendency is to limit cone type clutches to low speeds where sudden pick-up of load is not objectionable. Past performance of certain cone type clutches, operating at motor speed (1750/1800 RPM), failed to provide protection since the cone design is susceptible to heat build up during high speed slippage. This causes a malfunction or breakdown of the friction cone which defeats its torque limiting capabilities, and for this reason will not be considered any further.

3.3.2 DISC DESIGN - Ref. Fig. 5 and 5A


This design is the simplest and most economical, mechanical friction type clutch available, and is mechanically held in constant engagement by one or more springs.

- 3.3.3 Both makes shown in Fig. 5 and 5A, offer the following features in that,
 - (a) They can slip during engagement thus allowing the drive to pick-up and accelerate the load with minimum shock.
 - (b) They can be used at either high or low speed engagements and will slip under shock loads, providing cushioning to the system.
 - (c) They automatically re-engage when the overload is removed.


- 3.3.4 Disadvantages of this design are as follows:
 - (a) Inaccuracy of torque setting and repeatability due to changes in humidity, temperature, friction lining wear or contamination by oil, rust or dirt.
 - (b) Erratic or unstable spring pressure based on torque setting being in low range of spring pressure.
 - (c) No definate movement available (other than normal slippage) to use for tripping a motor cutout limit switch.
- 3.4 MULTI DISC TYPE Ref. Fig. 6 thru 6H
- 3.4.1 Multi Disc units are similar in operating principle to single disc units. The major difference being that alternately stacking or interleaving of the driven and driving discs can increase the friction area thus creating a greater torque capacity for a given clutch diameter.
- 3.4.2 Limitations to this design are,
 - (a) Restrictions to the number of starts per hour when compared to a single disc clutch of the same mechanical capacity and material, due to heat build up when they are used in air as a dry clutch without lubrication.
 - (b) Loss of capacity at the time of engagement due to disc sliding resistance.
 - (c) Complexity of parts and more maintenance is required when compared to a single disc unit.
 - (d) Periodic cleaning of the discs is required to assure that the adjustment or setting remains the same, even for a wet type clutch.
 - (e) Accumulation of occasional slippage will eventually cause a false overload tripping of the unit shown in Fig. 6.
- 3.4.3 The unit shown in Fig. 6 is not recommended for use where the overload is only slightly higher than the maximum overload. The overload recommended by the manufacturer must be either a heavy shock or a suddenly applied load substantially greater than the maximum working load. Therefore, a gradual build up of overload might not trip the unit.


3.4.4 The overall picture presented by this unit indicates that many variables are involved in determining the overload limits or setting for this type of clutch and that maintenance is required at regular intervals for either the wet or dry type, to maintain the correct setting when found. Therefore, it is our opinion that the multi disc type is too complex and has several undesirable features which are not suitable for this application.

RIM OR DRUM TYPE CLUTCHES




Rim or drum






INTERNAL - EXPANDING TYPE




EXTERNAL - CONTRACTING TYPE

FIG. 3




PORCUE LIMITER



DALTON MODEL "OSDC" OVERLOAD SAFETY DEVICE

• The Dalton OSDC (Overload Safety Device Coupling) provides overload protection through the use of an OSD unit combined with a roller chain coupling half counterbored to fit the OSD flange. Standard double-width roller chain is used to couple the basic OSD unit and the coupling half.

The OSDC can be set with a torque wrench for maximum load desired. The unit functions as a roller chain coupling until an overload occurs, causing the OSDC to dis-engage. The device is automatically re-engaged when the overload is eliminated.



				MAXIMU	M BORE	MINIMUM	A BORE				
Coupling No.	Weight Lbs.	Max. Ft. Lbs. Torque	No. of Springs	Coupling Half	OSD Half	Coupling Half	OSD Half	Coupling Half No.	OSD Sprocket No.	Coupling Chain No.	
OSDC-225	4	35	1	1 1/2 "	3/4" *	3/8"	3/8 "	4020A	40A20GC	D40	
OSDC-225D	4	50	2	1 1/2 "	3/4" *	3/8"	3% "	4020A	40A20GC	D40	
OSDC-337	91/2	100	1	2 1/4 "	۱″ *	1/2"	1/2"	4027A	40A27GC	D 40	
OSDC-337D	91/2	175	2	21/4"	1″ *	1/2"	1/2"	4027A	40A27GC	D 40	
OSDC-450	16	190	1	3"	1 3/8"	3/4"	3/4"	5026A	50A26GC	D 50	
OSDC-450D	16	285	2	3"	1 3/8"	3/4"	3/4"	5026A	50A26GC	D 50	
OSDC-600	30	320	1	4"	1 ⁵ /8"	1"	1"	6031A	60A31GC	D 60	
OSDC-600D	30	440	2	4"	1 5/8"	1"	1"	6031A	60A31GC	D6 0	
OSDC-750	46	550	1	5″	21/2"	1"	۱″	8027A	80A27GC	D 80	
OSDC-750D	46	775	2	5″	21/2"	1"	1"	8027A	80A27GC	D8 0	

*For maximum bore on OSD225, OSD225D, OSD337 and OSD337D, a shallow keyway is used of $\frac{1}{2}$ standard depth. Use the next larger size "OSD" unit when a standard keyway is desired.



In furnishing a coupling half to be used in the "OSDC", care must be taken that a standard cut tooth sprocket is not used. The teeth of the "OSDC" coupling half are cut with special tooth form to compensate for shaft misalignment.

FORMULA FOR TORQUE-HORSEPOWER (Foot Pounds)

TORQUE (Ft. Lbs.) = $\frac{HP \times 5252}{RPM}$

HORSEPOWER = Torque X RPM 5252


MORSE

Torque Limiter couplings






torque limiter coupling



The Torque Limiter ^ upling*combines overload slip protection with the ability to couple driving and driven shafts. It is an assembly consisting of a standard Morse Torque Limiter and a roller chain coupling.
A stock "A" plate sprocket with ground faces serves as the center member of the Torque Limiter, and it is coupled to a type "B" sprocket by an ASA double strand roller chain which is easily connected by a single pin. This construction provides a dependable and easy-toassemble flexible coupling having shaft misalignment compensation.



Model Number	Mis:	nlign Max.	Ter Capa Lbs	que scity	Max.	Bore	Sti Min. Bo		List Price	Sto Finis Boi	hed	List Price	Spkt.		•		NSION:	3		Apprex. Wt.
	Parallel		Min.	Max.	Torque Limiter	Cpig. Spkt.	Terque Limiter	Cpls. Spkt	" Min. Plain Bore"	Torque Limiter	Cpig. Spkt.	Finished Bore*	Size	A	9	С	D	E	F	Lbs.
250A-1C	010	1∕2*	5	20	74	1'4	•	١,	\$ 92 60	1/2 5/6 5/4 7/6		\$ 96 60	4.	3	4	2	1	1%	1/6	41/2
250A-2C	.010	r2,	10	40	7/4	1%	٠,	١,	97 70	15 96 34 36		101.70	422	3	4	2	1	1%	1/4	41/2
350A-1C	.012	1/2°	15	55	1	12.	۰,	٠,	124 20	*** *** 1		129.30	524	4%	5,,	234	11/5	2%+	'4	111/2
350A-2C	.012	V ₂ °	25	110	1	1,4	,	١.	135 90	3/4 7/4 1		140 10	524	41	5,•	2'•	174	2%.	1/4	111/2
500A-1C	015	L ₂	35	155	1%	2',	٠.	٠,	235 00	'6, 1, 1%, 1'e, 1%, 1%, 1%, 1%		241 30	628	434	7'•	4	1%	3	1/6	27
500A 2C	015	ν₂•	65	310	1%	2',	,,	7,	248 30	'e, 1, 1% 6 1'6, 1%, 1%, 1%, 1%, 1%,		254 60	628	414	7'•	4	1%	3	36	27
700A 1C	020	1/2*	85	420	21/5	3':	ı	1	420 70	115, 134, 115 +. 2		427 90	828	6'.	9'•	6	2%	3%	1/4	69
700A-2C	020	<i>}</i> 2^	165	800	21/4	3',	1	1	444 20	1'2, 1'4, 1'3' •. 2		452 00	828	6'•	9'.	6	2%	3%	1/4	69

^{*}Coupling Sprocket Minimum Plain Bore *Torque Limiter only, includes one (1) setscrew

reworking charges for each half innestanded bore keyway or setscrew

					QUANT	TTY 1-49		
			TORQUE	LIMITE	R		COUPLING	SPROCKET
Model	Rel	Rebore		Keyway		etscrew	Rebore, Keywa	y, and Setscrew
No.	Mach. Set-Up Charge Charge		Mach. Set-Up Charge Charge		Mach. Set-Up Charge Charge			Set-Up Charge
250A-1C 250A-2C	\$7.50	\$59.70	\$.85	\$59 70	\$1 35 ,	\$59 70	\$ 8 70	\$121 75
350A-1C 350A-2C	9.50	59.70	1 00	59.70	2.00	59 70	11 70	121 75
500A-1C 500A-2C	10.50	59.70	1.85	59.70	2 35	59 70	13 35	121.75
700A-1C 700A-2C		59.70	3 00	59.70	3 35	59 70	24.00	121.75

Torque Limit Sprocket Standa	ter & Coupling rd Bore Tolerances
1/2 to 15/6	+.0015000
1 to 11%	+.002000
2 And Over .	+.003000

Reworking Charge (Net), ea

Machining + (Set Up Charge | Quantity Identical Units)

Maxitorq

AUTOMATIC OVERLOAD RELEASE CLUTCHES

MAXITORQ PRODUCTS



SERIES AH AIR OR HYDRAULIC CLUTCHES OR BRAKES BULLETIN NO. 101



SERIES 9000A ELECTRIC CLUTCHES AND FAIL-SAFE CLUTCHES OR BRAKES BULLETIN NO. 90A & 95



AUTOMATIC OVERLOAD RELEASE CLUTCHES BULLETIN NO. 150A





STANDARD SINGLE AND DOUBLE CLUTCHES OR BRAKES BULLETIN NO. 50




DISC-PAC
"HEART" OF
MAXITORQ CLUTCHES
BULLETIN NO. 55


ALSO AVAILABLE CLUTCH DISCS. SEPARATOR SPRINGS, DRIVING CUPS







Floating Disc, Automatic



SIMPLE, EFFICIENT, "BUILT-IN PROTECTION"
FOR POWER DRIVEN EQUIPMENT

The Maxitorq Overload Release Clutch has been designed for applications where it is desired to protect a machine and its products against damage resulting from accidental overloading of the mechanism. This type of clutch promises freedom from costly shutdowns, resulting in substantial savings to the user.

When overload occurs, the clutch automatically releases, stopping the machine and preventing damage. When the jammed condition has been cleared, the clutch is reengaged and the machine is again in operation.

The overload release clutch is specifically recommended for applications where the nature of the overload will be either a heavy shock or a suddenly applied load of a magnitude substantially greater than the normal driving load. Jamming and clogging of the mechanism, imposing as it does a severe shock on the driving components, is

characteristic of this type of overload. The clutch will perform most effectively under these conditions. Protection from such an overload, in the past, has usually been accomplished by the use of shear pins. The overload release clutch is not recommended for applications where the overload will be but slightly greater than the normal driving torque.

By means of a simple finger-tip adjustment, the clutch can be set to transmit the normal running load for a particular application. It automatically disengages when an overload occurs, and positively slips into neutral.


DOUBLE CLL'TCHES. The overload release feature can be incorporated on double clutches on special order on either one or both ends.


NOTE: Maxitory Clutches as furnished can run dry or in oil. We specifically recommend Series A oils. If high gear loading or worm and wheels are adjacent to the clutch and indicate extreme pressure additives that would reduce clutch torque, please contact the factory for recommendations.


SPECIFICATIONS . . . CLUTCHES NOTE: Dardelet self locking full dog point set screw must bottom in spotted hole in shaft.

Clutch No.		Dynamic Torque	Static Slip Point Torque	Axial Sleeve Pressure	Std. Body Bores .001 .000			A	В	Throw		K		P		x	0 ^M
	RPM	Ft. Lbs.	(Approx.) Ft. Lbs.	Lbs	Min.	Max	Keyway Max.	A	B	D	J	,	L		W	^	Οŵ
20	1 10	7	14	15	1/2	5/8	3/16 Pin	21%2	2 3/8	3/8	375	3/4	21/8	916	31/9	1,16	1 16
21	1/4	13	26	20	3/4	₹,	1/16 x 3/52	21%2	3	3/6	.500	13,16	21/8	5/8	31/0	1/8	14164
22	1/2	27	54	30	1	11/4	3/16 x 3/22	3 3/16	315/2	?16	500	1 1/16	2 %	4564	3 %	1184	11346
23	1	53	106	30	11/4	1 3/6	1/4 x 1/8	31516	4 1/2	17/32	625	1 1584	31/4	5164	4 3/8	3/6	21784
24	1 3/4	92	184	40	1 1/2	1 1/8	5,16 × 5/22	4 1/4	4 1/2	17/32	625	11584	3%16	5164	5	314	21764
25	3	158	316	60	1 3/4	1 1/8	3/8 x 3/16	415/16	41316	3º84	.750	1 716	4' 16	6184	5 1/6	1364	223/32
26	5	263	526	80	2	21/4	7 16 X 7/32	5 ¹⁵ 32	5	3º84	750	1 716	4 1/8	6184	6%	1784	22022
27	10	525	1,050	105	21/2	23/4	°16 × °52	ブ ¹⁰ つ	611/32	7∕€	812	1 3/4	61/2	11/4	91/8	5 ia	3 3/4
28	15	788	1,576	150	23/4	3	*16 × *52	8 %	6 ° 16	7/8	812	1 3/4	71/2	11%	101/4	\$ 14	ירוינ

OVERLOAD RELEASE CLUTCHES







*Keyway to suit conditions. Bearings-Spacer-Retaining Rings, Adapter furnished by customer.

DRIVING RING CUPS FOR OVERLOAD RELEASE CLUTCHES

Overload release-type driving ring cups are the means by which the overload release clutch is connected to either the driven or driving member.

Ring cups are accurately machined and finished ground. All working surfaces are heat-treated. The hub or cut-off coupling type adapter is furnished by user to suit installation requirements.

Because of the unusual cam construction, it is recommended that we furnish overload release-type driving ring cups as well as the clutch. We are equipped to make them correctly in reasonable quantities. Through an associated company we can provide a package incorporating the Carlyle Johnson clutch unit and other components required for a com-

plete installation. If this latter course is desired, preliminary drawings, a complete quotation, assembly instructions and recommendations will be provided.


SHIFTERS


Special overload release shifters are available for clutch sizes 20 through 26. Shoes and studs are available for all sizes including 27 and 28 for riveting into shifter yokes designed by the customer. The user can, if desired, incorporate a limit switch in the power input line. This switch is operated in conjunction with the clutch shifter sleeve to open the circuit when clutch release is effected by the overload. Maxitorq Overload Release Clutches may be used on a continuous shaft, or as a cut-off coupling type for connecting two shafts.


OVERLOAD RELEASE CLUTCH DRIVING RING CUPS AND ADAPTERS


Clutch No.	С	н	Shafi	Bore Y	Z	M	R 1. D.	บ	G ^M	Cap Screw Size	D Drilled Holes	No. of Thru Holes	A *	F°	N
20			1/2	3%		3.125 3.123	2.017 2.015	1/4	36	1/4	17/4	3	2 %	120°	132
21			34	7%		3.125 3.123	2.017 2.015	1 1/32	⅓,	1/4	1%4	3	2 %	120°	יאי.
22	NS NS	SZ SZ	1	11%	0 0	3.625 3.623	2.517 2.515	1 3⁄2	3,	14	1%4	3	3 1/4	120°	11/32
23	OMOITIONS	CONDITIONS	11/4	136	1 -	4.625 4.623	3.267 3.265	1 %	5,,	516	1352	3	315/16	120°	15%
24	ő	0 0	11/2	1%	BEARING	5.125 5.123	3.767 3.765	1 %	5,	3,6	11/52	3	4 %	120°	151
25	SUIT	SUIT	184	17%	SUIT	6.125 6.123	4.517 4.515	11352	1,6	*	13,2	4	5 %	90°	3744
26	٥	5	2	21/4	٥	7.125 7.120	5 517 5.515	125/2	1,4	*	1352	ه	6 %	60°	135
27		[] [2!5	234		9.125 9.120	7.017 7.015	2 4,	314	1/2	1351	6	8 ¼	60°	1%
28			234	3		10.125 10.120	8.017 8.015	234	14	1,	1752	6	9 1/4	60°	13%

*Bolt circle











Ask for Recommendations

There are so many varied applications of this overload release clutch that we suggest you submit your clutch problem to our engineering department for practical recommendations.

THE CARLYLE JOHNSON MACHINE CO.

52 MAIN STREET + MANCHESTER, CHAN GEGAG

MAINTENANCE AND ADJUSTMENT OF MAXITORQ CLUTCHES

The Carlyle Johnson Machine Company guarantees Maxitorq Clutches against imperfections in materials and workmanship. To assure good service the clutch must be kept properly adjusted and maintained. We offer the following bulletin as a guide to better clutch performance.

STANDARD CLUTCH ADJUSTMENT

The clutches are factory adjusted, yet, the machine builder may make a further adjustment to suit his particular requirements. During the run-in period of any machine it may be necessary to take up the adjustment due to initial wear-in period. To make a change in adjustment, lift the lock spring and move the adjusting ring one notch at a time. These notches can be seen on the outside diameter of lever retaining ring inside of the adjusting ring. Be sure to replace spring after making adjustment. To adjust the split type ring loosen the cap screw and rotate not more than 10 degrees at a time, making sure to tighten the cap screw after each adjustment. Contact the machine builder if the desired results are not obtained. CAUTION: Be careful not to over adjust the clutch. This condition does not allow the discs to separate sufficiently in the neutral position, causing loss of freeness, excessive wear, and possible breakage of the separator springs.

OVERLOAD RELEASE ADJUSTMENT

First back off the adjusting ring until the clutch will immediately throw out when power is applied. Then slowly take up one notch at a time. If the split type ring is used, do not turn the ring more than 10 degrees at a time. Apply the power after each change until the clutch will just stay in engagement. To over adjust means that too much overload must occure before the clutch will disengage itself. If the user wishes to protect for light loads, then a careful adjustment must be made. Under this condition, it is possible to adjust sufficiently to carry the load, but minor variations of torque will cause the clutch to slip by small amounts until the cams interfere and disengage a few times a day. It is up to the user to decide the degree of protection most suited to his particular application. Care must be taken to keep all disc surfaces clean to assure that the adjustment will remain the same. NOTE: -- If a variable speed drive is used, the adjustment must be changed if the speed is to be changed.

WET CLUTCH: (All steel discs)

tisting of the second position of the second

This clutch should always be run in oil. Periodic checks should be made to make sure oil is clean and free from carbonization. Depending upon the usage, gear boxes should be drained, flushed out and new oil put in on a scheduled basis. NOTE:—

Special low speed applications that have been approved by the factory to run without oil should be maintained like a dry clutch.


DRY CLUTCH: (Alternate steel and bronze faced discs)


This type of clutch has been designed so that the disc unit may be run as a dry unit without lubrication. It may also be run in oil. It has been the experience of the factory that carbonization will form if oil heavier than 200 viscosity is used. Heavy oil also reduces the freeness of the neutral position due to the hydraulic shear value of the oil and at the same time increases the working temperature as well as reducing the torque value of the unit. A clutch that is running dry and usually unprotected from all forms of contamination must be cleaned at regular intervals to assure proper operation. Unless the clutch unit is badly corroded, it is generally unnecessary to take the unit apart. Take an oil can filled with any of the commercial solvents and work the solvents down through the disc assembly and into the lever and cam system. The discs are readily accessible if a milled type cup is used. If our ring type cup is used, it is necessary to work the solvent in through the milled slots under the shifter sleeve. This milled slot runs the full length of the body and will carry the solvent into the disc assembly. On a single clutch, it may be necessary to use the finger to dam up the back of the milled slot on the shifter sleeve end of the body so the solvent will run into the discs instead of out the back end. When you have worked a sufficient amount of solvent into the clutch, start up the machine and engage and disengage the clutch to free up the unit. Repeat this procedure until the clutch works correctly. If this method fails, then it will be necessary to remove the clutch from the machine—disassemble and clean thoroughly. Before reassembling the clutch, study the exploded view and the following description to be sure the parts are put back in the right sequence.






F16 2







F10 4



F16. 5

HOW TO DISASSEMBLE THE CLUTCH

Place the clutch as shown in figure (1). Looking down on the clutch as in figure (2), raise lock spring, rotate adjusting ring in a clockwise direction until the face of adjusting ring just begins to draw away from the adjacent inner disc. Press down on the end locking plate until it can be rotated 60 degrees. This will free the bayonet lock and allow the end locking plate to be removed, followed by the discs, separator springs, thrust collar, adjusting ring, and levers. Unless the shifter sleeve or wedges are damaged or worn, it is not necessary to remove the lever retaining ring which is pressed on the body. Make sure that the lever retaining ring is pressed squarely up against the shoulder onto which it is pressed. Thoroughly clean all parts and reassemble, replacing any worn or damaged parts.

HOW TO REASSEMBLE CLUTCH

Place the thrust collar on the small diameter of the body with the three milled slots facing toward big diameter end. Rotate the thrust collar so the milled slots line up with the milled slots in the body. Place as shown in figure (3) assembling a lever in each milled slot in the body. Then with the fingers--raise thrust collar and levers up until the round head of the levers is in the circular recess in the lever retaining ring, as in figure (4). Now turn the unit over and screw on the adjusting ring as in figure (5) until the face of the adjusting ring is flush with the face of the thrust collar. Putting a light pressure on the face of the adjusting ring with the thumbs, engage the shifter sleeve with the fingers to be sure that the lever system is working correctly. Put on the first disc, making sure you have chosen a disc with the lugs on the inside diameter. Next add a separator spring, then a disc with the lugs on the outside diameter. Continue to assemble the discs in this manner, if steel and bronze discs are used, until ten discs have been assembled for the #21, #22; twelve discs for the #23, #24, #25; fourteen discs for the #26; sixteen for the #27, and eighteen for the #28 clutch. When all steel discs are used, twelve are required for the #21 and #22; fourteen for the #23, #24 and #25; and sixteen for the #26.

continued next page

Next assemble the end locking plate by matching up the milled faces on the end of the clutch body. Press lock plate against discs and rotate it. Release the hand pressure and rotate until the plate snaps into locked position. Take up on the adjusting ring until there is a distinct snap when the clutch engages. This is considered to be a normal clutch adjustment.

SUGGESTED MAINTENANCE PROGRAM FOR DRY CLUTCHES

Field experience has shown that a schedule of periodic flushing with kerosene keeps the clutch discs in good condition. At the same time, kerosene carries a light lubricant which is absorbed by the porous structure of the powdered bronze facing.

The shifter sleeve should be lubricated where it slides on the body as well as the lever ends that come in contact with the wedges in the sleeve. A light oil, perferably No. 10 or 20 motor oil, is suggested at these points.

The shifter shoes in the shifter sleeve groove wear better if "Lubriplate" or an equivalent grease is used sparingly. See diagram below---

KEROSENE GREASE

OUL

Experience will establish how often this program should be repeated to give best results.

FOR MAXITORQ MECHANICAL CLUTCHES

Locking Plate

Outer Disc

Separator Spring

Inner Disc

Balance Of Inner And Outer Discs With Separator Springs



Lock Spring

Adjusting Ring

Thrust Collar

Levers

Lever Retaining Ring

Single Sleeve



With Wedges Riveted In



Outer Disc

Locking Plate

Separator Spring



Inner Disc

Balance Of Inner And Outer Discs With Separator Springs



Standard Flange Cup

Shifter Shoe

Shifter Shoe Stud

Standard Ring Cup

Lock Spring



Adjusting Ring

Thrust Collar



Levers



Standard Overload Release Ring Cup



Double Sleeve With Wedges Riveted In



Single Clutch Assembly With Overload Release Sleeve



Body Set Screw



Double Body With Parts Shown Assembled On One End Only

READ THIS before ordering parts

Each part listed is identified by a part code number which serves as a reference to enable our Parts Department to interpret your requirements. Because the list covers more than one size clutch, it is of utmost importance that you specify not only the part code number and name of the part required, but, also the CLUTCH SIZE AND SERIAL NUMBER (stamped on O.D. of Sleeve), and whether for SINGLE, DOUBLE or OVERLOAD RELEASE TYPE CLUTCH.

Some Maxitory clutches contain parts which have been modified to a machine builder's specification, such as special clutch bodies and driving cups which can only be identified with serial number.

The above information will help us to better serve you and will, thereby, avoid delays and expense occasioned by idle equipment when our Parts Department is obliged to wire or write for serial number or other information.

STANDARD SINGLE CLUTCH

Part Code No.

- 103 Single Body (specify bore and keyway)
- 104 Single Sleeve (complete with wedges)
- 105 Adjusting Ring
- 107 Wedges
- 108 Thrust Collar
- 109 Lock Spring (specify width)
- 110 Levers
- 111 Lever Retaining Ring
- 112 Outer Steel Disc (specify quantity)
- 112-2 Outer Bronze Faced Disc (specify quantity)
- 113 Inner Steel Disc (specify quantity)
- 113-1 Inner Bronze Faced Disc (specify quantity)
- 114 Separator Springs (specify quantity)
- 115 Locking Plate
- 116 Body Set Screw

STANDARD DOUBLE CLUTCH

Part Code No.

- 101 Double Body (specify bore and keyway)
- 102 Double Sleeve (complete with wedges)
 All other parts same as for Single Ciutch

STANDARD OVERLOAD-RELEASE CLUTCH

Part Code No.

104-1 Single Sleeve, Overload Release type
All other parts same as for Single Clutch

STANDARD CLUTCH ACCESSORIES

Part Code No.

106-4 Standard Ring Cup

106-6 Standard Overload Release Ring Cup Standard Flange Cup

117 Shifter Shoes

118 Shifter Shoe Studs

HOW TO ORDER

Specify part code number, description, clutch size, and serial number. For example:

1 PART NO. 103, SINGLE BODY, 11/4" BORE, 1/4" x 1/4" KEYWAY, NO. 23 SIZE CLUTCH, SERIAL NO. 101562.

THE CARLYLE JOHNSON MACHINE COMPANY

MANCHESTER, CONNECTICUT, 06040

See Reverse Side

THE PROPERTY OF THE PROPERTY O

4. POSITIVE TYPE TORQUE LIMITERS

- 4.1 After reviewing all the different types of mechanical friction type clutches as requested and not finding a design which offers better features than have been previously used on existing vertical conveyors, it is apparent that other types of torque limiting devices should be considered at this point.
- 4.2 Spring loaded ball or key detent, positive type torque limiters which disengage, rather than slip, at a predetermined setting, are becoming more available and competitive in the commercial field of power transmission and offer a variety of new and different features which will be presented and evaluated in the following portion of this study.
- The different makes and designs which are presently on or about to be placed on the market, that will be reviewed at this time are, Autogard, Rite-Torq, Form-Gard and Helland Torq-Tender.
- with the torque limiter location established between the motor and reducer, an allowance for starting torque must be made for a positive type unit since there is no slippage. The selected torque range should have a minimum adjustment of 50% above and below the calculated operating torque required. The overload tripping torque setting should be at least 40% greater than the operating torque to prevent the torque limiter from tripping on start up.

4.5 To provide closer overload protection of 110-115% of rated full load, an electrical overload device to monitor the power circuit is required to supplement a positive type torque limiter.

neatentatathannanassiannana de tannanastathan settiae adtair bethan de company


4.6 AUTOGARD TORQUE LIMITER

- 4.6.1 The torque limiter recommended by Autogard for vertical conveyor operation with a motor cutoff switch is shown in Figure (7), drawing #AAC-206N/ACT/2/03.
- 4.6.2 The #2 size unit selected for this application, incorporates a torsionally soft coupling with a single position reset overload release, having a torque range of 20 to 1451 lb. in. (1.67 to 121 lb. ft.). Three different coil springs are required to cover the above torque range for 3 thru 10 HP drives.
- 4.6.3 The elastomer elements of the coupling half are made of "Perbunam", a synthetic material which is oil and chemical resistant and will operate satisfactorily in a salt laden atmosphere with an ambient temperature range of -25° to +175° F. The coupling will allow a maximum shaft misalignment of 0°-24' angular and .032" parallel.
- 4.6.4 The "ACT" type overload unit uses (3) %" diameter balls, each located on a different radius so that two (2) revolutions of movement are required to reset the unit after disengagement, thus cutting down on the wear rate when compared with the "AC" type unit, where the (3) balls are located on the same radius.
- 4.6.5 The torque limiter is bidirectional and will reset automatically. At the point of disengagement from an overload, the cutoff switch shuts off the motor and allows the brake to set on the reducer or load side of the drive. During the short period of time that the

brake brings the conveyor movement to rest, (normally 4 to 6 revolutions of the reducer input shaft). The motor will continue to rotate and shift the detent balls thru the reset position until the motor inertia drops below the overload trip setting which will allow the unit to reset.


4.6.6 Other features are:

- (a) Limited torque adjustment above maximum specified setting by using calibrated spacers beneath the spring.
- (b) Thrust bearing equipped with grease fitting for lubrication.
- (c) Torque setting accuracy ± 10% of setting.
- (d) Standard finish is black oxide. However, unit can be furnished cadmium plated.
- (e) Using an adapter on the overload half permits coverage of maximum bore requirements.
- A.6.7 The operating speed of 1750 RPM is beyond Autogard's normally recommended limit of 600 RPM. However, they feel the unit will provide satisfactory service and their normal parts and workmanship warranty will not be affected by the operating speed. Autogard's after thoughts recommend that a test under simulated operating conditions be mad~ to verify the above statement. They also advise the use of a brake on the motor side if possible.




()

2)



TORTUE RANGE 20-1451 LB IN. DEPENDING ON SPRING INSTALLED MAX, ANGULAR MISALIGNMENT 0°-24' MAX. PARALLEL MISALIGNMENT .032



SECTION "A-A"

REF. PG. 27A

TOLERANCES	AMERICAN AUTOGARD CORP									
DECIMAL	SCALE DRAWN BY T. KRAIMER									
±.005	FULL FULL									
±1/64	MODEL 206N/ACT/2 TORQUE LIMITER WITH SPECIAL ADAPTOR									
	4-4-77 AAC-206N/ACT/2/03									

27A

DIA

510

(75)

FIG. NO.7





AMERICAN AUTOGARD CORP.

P.O. BOX 386


MENOMONEE FALLS, WISCONSIN 53051

PHONE: (414) 251-0085 TELEX 26795

INSTALLATION AND MAINTENANCE DATA AUTOGARD TORQUE LIMITER

BALL TYPES

FIG. 1



"AF" DRIVE PLATE WITH CAM




"AF" ENGAGING PLATE

TYPE "AF" (FREEWHEELING): Figure 1

This ball type consists of balls held in ball seats, located in the drive and slide plates. A 3, 6 or 9 lobe cam attached to the drive plate rolls the balls to an outer path when a torque overload occurs. The balls then roll without encountering ball seats. A plate with elongated slots permits engaging the unit by guiding the balls back into the seats.

BALL SEAT

FIG. 2



"AC" CAGE PLATE

"AC" DRIVE PLATE

TYPE "AC" (CLANGER): Figure 2


This ball type differs from the "AF" type in that the balls are not cammed outward during a torque overload. They roll at the pitch diameter of the ball seats and drop into the seats as they are encountered. This re-engagement is quite audible (hence the reference to the unit as a clanger). In the "AC" ball type, there is no cam. The engaging plate is replaced by a slightly thicker cage plate which assures that the balls are held in proper position.

WARNING: The ratcheting action which occurs with the "AC" ball types can be damaging to the unit. Use of the "AC" ball type is not recommended when:

- 1. Shaft speeds exceed 100-200- RPM or
- 2. Unit will run, disengaged, more than 5-10 seconds.

Consult factory for assistance if these factors cannot be avoided because certain steps, such as operating the unit in oil, can be taken to avoid damaging the torque limiter.


FIG. 3



TYPE "ACT" (single position reset): Figure 3

The "ACT" ball type automatically resets each time in the same position for drives requiring synchronization. The balls are scattered on different diameters so that when an overload occurs the balls must return to their original positions before they re-seat Engagement will occur after two revolutions in either direction.

WARNING: The same restrictions as for the "AC" type above apply, except that the "ACT" type may run at speeds up to 400-600 RPM.



LIST OF PARTS

- 1. HUB
- 2. NEEDLE BEARING
- 3. DRIVE PLATE & CAM
- 4. ADAPTOR (MODEL 201)
- 5. ENGAGING PLATE
- 6. BALLS

- 7. SLIDE PLATE
- 8. LIMIT SWITCH PLATE
- 9. SPACERS
- 10. ADJUSTING NUT
- 11. SPRING
- 12. SPROCKET OR PULLEY

12

COUPLING PARTS SEE PAGE 5

- 13 COUPLING HUB (MODEL 204) COUPLING HUB (MODEL 205)
- ADAPTER (MODEL 205) 15
- COUPLING HUB (MODEL 206N) ADAPTER (MODEL 206N)
- When unit is fully engaged.

Size	Dimension "U"	"M" Dia.
1	5 '32 in.	1-1 '4 ın.
2	5 16	2
3	5 16	2-1 '2
4	13 '32	3-1 2
5	1 '2	5

MODEL 202 FIG. 5

PRIOR TO INSTALLATION

1. Mounting Sprocket or Sheave on Model 201.

A. Mounting with tapered bushings (taper-lock; Q-D; Browning; etc.):

Sprockets, sheaves and timing belt pulleys may be mounted directly on Model 201 Autogard by using taper-lock bushings. Select a sprocket with a bushing to fit "M dia." of the Autogard (Fig. 4). No key is used with these bushings when mounting on the Autogard. Be certain that the bushings are properly mounted and tightened per the instructions accompanying each bushing. Thoroughly clean all grease and oil from "M dia." with solvent prior to mounting the bushing.

NOTE: Check that adaptor and bushing assy. is free to turn on hub after bushing has been fully tightened.

B. Mounting with bolts:

Sprockets, flat sheaves, etc. may also be mounted on Model 201 Autogard by bolting as shown in Fig. 4.


The adaptor, item 4, must be removed for drilling and tapping the mounting holes (Table 2) if they were not ordered with the unit (see Disassembly Procedure page 7).

Attach sprocket, etc., onto adaptor prior to reassembly and inspect to insure that there are no protrusions inside the adaptor which might interfere with the hub. The unit may then be reassembled for use.

2. Direction of the slots ("AF" Type):

The direction of the slots in the "AF" engaging plate has no effect on the tripping action of the torque limiter. The Autogard will trip in both directions no matter which way the slots point. The directions of the slots can be important in resetting when neither side of the drive can be manually advanced or can be advanced in one direction only. A simple bench test will show the proper assembly for a particular drive. If a bench test is not feasible, figure 6 will show proper assemblies.

ROTATION OF DRIVEN PLATE



BOTH VIEWED FROM SPRING SIDE

FIG. 6

3. Number of balls:

Check to see if the proper number of balls are in the unit per Table 3. When changing from a coil spring to a disc spring, it will be necessary to add balls. The balls are standard ball bearing balls and can be obtained from distributor.

TABLE 3

		NUMBER OF BALLS							
UNIT	BALL	AF T	AC TYPE						
SIZE	DIAMETER	COIL SPRING	DISC SPRING	COIL OR DISC SPRING					
1	1.	3		3					
2	1/2	3	3	3					
3	1,	3	6	6					
4	\$ ₈	3	6	6					
5	3/,	3	9	9					

4. Proper spring:

Check to see that the spring will provide the desired range to release torque (Table 4). DO NOT TIGHTEN THE SPRING BEYOND ITS MINIMUM OPERATING LENGTH (with the torque limiter engaged) or the spring will not allow sufficient movement of the slide plate to let the balls leave their seats during an overload. Damage to the machinery or to the Autogard will result.

TABLE 2

RECOMMENDED HOLE PATTERNS ARE AS FOLLOWS:

AUTOGARD SIZE	NO. OF BOLTS*	BOLT SIZE	MAX. BOLT ENGAGEMENT IN ADAPTOR	BOLT CIRCLE DIAMETER	SPROCKET BORE
1	6	#8 - 32	.267	1-5 8	1.252 1.253
2	6	#8-32	.194	2-3 8	2.002 '2.003
3	6	1 4 x 20	.360	3	2.502 2.503
4	6	5 16 x 18	.479	4-1 8	3.5025 3.5035
5	6	3 8 x 16	.610	5-11 16	5.0025 5.0035

^{*}Bolt holes to be equally spaced on bolt circle diameter specified. Care must be taken not to drill into other mounting holes in the adaptor.

TABLE 4

4.75			SPRING			TORQUE	RANGE	MIN. OPERATING LENGTH		
SIZE	TYPE	CODE	COLOR	QTY.	STACK AS	LB. IN.	KG. M.	IN.	MM.	
	coil	1C/1	white & red	1	fig. 7	20-250	.23 - 2.8	.95	24.2	
1 1	coil	1C/2	white & green	1	fig. 7	10-130	.12 - 1.4	.93	23.6	
1	coil	1C/3	white & yellow	1	fig. 7	5-60	.0669	.74	18.8	
	disc	2D/1/S	blue & black	6	fig. 8	500-2000	5.7 - 23	1.00	25.4	
اما	coil	2C/1	blue & red	1 1	fig. 7	120-650	1.4 - 7.5	1.08	27.8	
2	coil	2C/2	blue & green	1	fig. 7	50-400	.57 - 4.6	1.05	26.9	
	coil	2C/3	blue & yellow	1	fig. 7	20-130	.23 - 1.4	.98	24.9	
	disc	3D/1/D	brown & black	8	fig. 10	1400-6000	16.1 69	1.15	29.4	
	disc	3D/1/S	brown & black	6	fig. 8	600-3600	6.9 - 41	.88	22.3	
3	coil	3C/1	brown & red	1 1	fig. 7	400-2500	4.6 • 28	1.55	39.7	
	coil	3C/2	brown & green	1 1	fig. 7	100-1200	1.1 - 13	1.49	38.0	
	coil	3C/3	brown & yellow	1	fig. 7	40-500	.46 - 5.7	1.46	37.1	
	disc	4D/1/S	orange & black	5	fig. 9	2400-10,000	27 - 115	1.25	31.8	
4	disc	4D/2/S	orange	6	fig. 8	1200-7500	13.8 - 86	1.28	32.5	
'	coil	4C/1	orange & red	1	fig. 7	250-2800	2.9 - 32	2.00	50.8	
	disc	5D/1/S	grey & black	6	fig. 8	5500-22,500	63 - 259	2.38	60.4	
5	disc	5D/2/S	grey	6	fig. 8	3000-20,000	34 - 230	1.97	50.1	
'	coil	5C/1	grey & red	1 1	fig. 7	350-3100	4 - 35	1.75	44.5	

FIG. 7




FIG. 8




FIG. 9





FIG. 10



5. Calibration spacers:

Calibration spacers perform two functions:

A. Maintain proper stacking of disc springs.

B. Prevent unauthorized tightening of the adjusting

Calibration spacers are normally supplied in several segments to allow upward adjustment

of the unit in the field. The bottom segment is for the minmum length of the spring being used. This segment should not be removed. If a higher release torque is required, use a stronger spring. Units shipped from the factory, set at a specified storque, have spacers which will allow adjustment to about 125% of the set torque before removal of segments becomes necessary.

6. Lubrication:

The needle bearing, plate faces and balls should be well lubricated with a good grade grease, equivalent to specification MIL-G-3545-13.

A grease nipple is provided on units larger than size 1 to allow greasing of the needle bearings. SAE 30 oil is to be used on size 1 which has an oiling hole instead of a nipple.

INSTALLATION

1 Models 201 & 202 Figs. 4 & 5, Pg. 2

MOUNTING THE AUTOGARD TORQUE LIMITER ON THE SHAFT

Mount the torque limiter by engaging the hub on the shaft. The unit may be moved axially on the shaft to a degree to obtain proper alignment of the sprocket or sheave with the chain or belt. The minimum acceptable shaft engagement is 1½ times the shaft diameter. Tighten the set screws fully. Recommended torque values for set screws are shown in Table 5.

See pg. 2 for parts list.

numbered 1-11 are same for all models.

Mount the torque limiter hubs to the shafts same as per

instructions for models 201 & 202 on this page. Table 7 shows the maximum allowable misalignment for

optimum unit life. See pg. 2 for parts list. Parts

TABLE 6

MODELS 203 *, 204, 205, 206N


FIGS. 11, 12, 13, & 14 Below


		Allowable Angular	Allowabie Parallel	Gap between hub and adaptor			
Model	Size	Misalignment	Misalignment	Min.	Max.		
203*	1.5	0	0				
204	1.5	0	0				
205	1	.5 deg.	0				
	2	.5 deg.	0				
	3	.5 deg.	n				
	4	.5 deg.	0				
	4	.5 deg.	0				
	5	.5 deg.	0				
206N	1	.4 deg.	.016"	5/64"	5/32"		
	2	.4 deg.	.016"	5/64"	5/32"		
	3	.4 deg.	.016"	5/64"	5/32"		
	4	.4 deg.	.032"	5/64"	1/4"		
	5	.8 deg.	.032"	1/8"	5/16"		


TABLE 5

SETSCREW SIZE	#10	1 '4	5 '16	3 %	7 16	12
SEATING TORQUE INCH/LB.	33	87	165	290	430	620










[•] For model 203 the driven member is supplied by customer. If used for offset drive the pulley, gear, etc. must be mounted on its own bearing.

LIMIT SWITCH OPERATION:

Limit switches are easily used to give a warning or shut down a drive in the event of a torque overload. The limit switch is actuated by the movement of the slide plate (or the limit switch plate when used). See Table 7 for guidelines. Always use limit switch with "AC" and "ACT" types.



Size	Movement	Ball plate	Plate
	on break 'X'	dia. 'D'	dia. 'E'
	(inches mm)	(inches mm)	(inches <i>mm</i>)
1	·095	2	3 1
	2·4	51	83
2	·173	3½	5½
	<i>4·4</i>	8 9	140
3	·173	4±	6 <u>1</u>
	4·4	108	165
4	209	5‡	8
	<i>5∙3</i>	149	203
5	·248	8	10
	6·3	203	254




TABLE 7

		RATING			
MANUFACTURER	CATALOG NO.	VOLTS AC MAX.	AMPS MAX.	ENCLOSURE	CONTACT TYPE
ALLEN BRADLEY	802R-DF	250	5	NEMA 12	SPDT
ALLEN BRADLEY	802T-D	600	10	NEMA 12	SPDT
GENERAL ELECTRIC	CR9440 KIMI	600	10	NEMA 12	SPDT
GENERAL ELECTRIC	но1308	575	10	NEMA 12	SPDT
MICRO-SWITCH	5LS1	480	10	NEMA 4	SPDT
MICRO-SWITCH	15LS1	240	10	NEMA 4	DPDT
MICRO-SWITCH	BZE6-2RN80	480	15	NEMA 2	SPDT
MICRO-SWITCH	OP-AR30	480	15	NEMA 4	SPDT
MICRO-SWITCH	SX-AR30	480	15	NEMA 9	SPDT
MICRO-SWITCH	205L\$1 (PLUG IN)	480	10	NEMA 4	SPDT
ALLEN BRADLEY	802-PASJ203	600	5	OPEN	SPDT
GENERAL ELECTRIC	CR115JB0201	575	10	OPEN	SPDT
MICRO-SWITCH	BZEG-2RQ8	480	15	OPEN	SPDT
MICRO-SWITCH	BZ-RW922T	480	10	OPEN	SPDT
MICRO-SWITCH	BZ-2RQ18T	480	15	OPEN	SPDT
CUTLER-HAMMER	SS12ET10-102L3	250	15	OPEN	SPDT
CUTLER-HAMMER	\$\$12BT10-102L3	250	10	OPEN	SPDT
CHERRY	E23-OOK	250	5	OPEN	SPDT
CHERRY	E33-00K	250	10	OPEN	SPDT
CHERRY	E34-00K	250	15	OPEN	SPDT

INITIAL STARTUP

Prior to startup, examine unit to assure it is engaged, i.e., balls are seated fully in both plates. When fully engaged, dimension between the drive plate and slide plate is per Table 1.

Obtain the initial torque setting by one of the following methods:

- 1. Setting torque with unit installed:
 - Start up the drive with a low torque setting and progressively tighten the adjusting nut until the unit will start and drive under normal load without tripping. Peak starting torque is usually the highest torque which the torque limiter must transmit, but occasionally the torque limiter must be set to accommodate higher peak torques.
- Testing with spring scale and lever arm (may be done on a bench or after unit is mounted in drive).

If the unit is mounted, be certain that one side of the limiter or drive is disconnected and free to rotate. The other side must be held stationary. An example of a bench test is shown in figure 13. The spring scale is pulled until the unit trips. Take care to maintain a slow steady pull, keeping the pull on the spring scale at 90 to the arm, and keep the arm approximately vertical or the reading will be affected by the arm weight. Carefully note the load on the spring scale at which the unit trips. The corresponding torque is this load multiplied by the length of the arm ("L") measured to the point of pull. Adjust the position of the adjusting nut until the correct torque setting is reached. Do not confuse 1b. inches and 1b. feet. When working in 1b. inches it is convenient to make the arm 10" so that the load in pounds x 10 = torque in 1b. inches. Similarly, when working in 1b. feet, an arm of 1 foot will give a spring scale reading directly in 1b. feet (i.e. load x 1).

delineral despitables despitations and despitables despitates despitations and despitables despitables despitab

For high torque on the larger units a longer arm will be necessary to avoid excessively high spring scale loads. For example, 2,000 lb. inches would require 200 lb. load on a 10 inch arm, but only 50 lb. on a 40 inch arm.


3. Unit set at factory:

When a torque setting is specified in the order, the unit is set at the factory within ±10%. If the unit must be disassembled, note the spring compressed length prior to disassembly and adjust to that length upon reassembly to obtain the desired torque.

CAUTION: Do not tighten spring beyond its minimum operating length. See Table 4.

TESTING & TORQUE SETTING

PULL SMOOTHLY IN DIRECTION OF ARROW, NOTING THE LOAD AT THE INSTANT THE LEVER GIVES.




RESETTING PROCEDURE

- 1. Shut down drive.
- 2. Investigate and remove cause of overload or jam.
- 3. Reset:

A. "AF" Type

Rotate either side of the drive until a slot on edge of the engaging plate aligns with a slot in the drive plate, and lock these two plates in this position with a bar in the slots (fig. 14).



Note that these slots are not to be confused with those in which the balls run. Further rotation of either side of the drive approximately 80 degrees will give engagement if the correct direction of rotation is selected, (see Direction of Slots) and balls can be heard to re-engage with their seatings quite distinctly. Insure that the resetting bar is removed before resetting the drive. To check full engagement, see Table 1.

B "AC" Type:

It is likely that the unit stopped in the engaged state. Rotation of either side of the drive for a maximum of 240 degrees will re-engage the unit. To check full engagement, see Table 1.

C. "ACT" Type

Rotation of either side of the drive for a maximum of 720 degrees will re-engage the unit. To check full engagement, see Table 1.

DISASSEMBLY PROCEDURE

NOTE: Measure spring length before disassembly.

- A. With spring end up remove adjusting nut, spring, spacers, limit switch plate, slide plate, engaging plate & balls.
- B. Gently drive pins from adaptor & drive plate.
- C. Remove cap screws and gently work drive plate over spline so as not to damage bearing material on LD, of plate.
- D. Remove adaptor carefully so as not to damage bearing material on LD.
- E. Inspect the bearing surfaces prior to reassembly and carefully blend out any scratches.
- F. Apply a liberal coating of a good grade machine oil (SAE 30) to the LD, of the adaptor or drive plate and engaging or cage plate prior to reassembly.
- G. For reassembly, reverse steps A thru D.

NORMAL MAINTENANCE

The autogard torque limiter should be greased regularly when the equipment on which it is mounted is maintained. Maximum time between inspection and maintenance is 2000 hours operation or after each disengagement, whichever is sooner. For unusual conditions, such as very high RPM, high ambient temperatures, high vibration or dirty environments, special maintenance may be required.

Inspect for sprocket wear, tightness of limiter on its shaft, tightness of sprocket, etc. at this time.


TABLE 8


PROBLEM	PROBABLE CAUSE	CORRECTIVE ACTION		
Autogard will not drive	Machine jammed	Carefully inspect machine for signs of jamming, and clear.		
	Torque setting to low	increase torque setting by tightening adjusting nut, removing calibration spacer segments as necessary. Do not tighten beyond minimum spring length (see table 4). Use stronger spring or larger size units if necessary.		
One or more balls will not reset on "AF" bail type or one or more balls will not leave ball seat.	Improper number of balls.	Check the number of balls in the unit against table 3.		
	Insufficient spring pressure	Check to be certain that spring is not completely loose when Autogard is engaged, if so, use weaker spring or smaller size Autogard.		
		If 6 balls are being used with disc springs), ity in- creasing torque by 1 or 2 turns. If this corrects problem, reduce number of balls to 3. If problem continues, warped plate could be responsible.		
	Warped plate	same as insufficient spring pressure.		
		Replace plate. To confum that plate is marped, inspect faces where balls contact. Ball path should be visible, but should not have appreciable depth. Surfaces of plate to be flat within .002 T.I.R.		
Will not rotate freely when disengaged.	Lacks lubrication	Lubricate with grease equivalent to specification MIL-G-3545-13. A good grade machine oil can be applied to the high to work into the resin bonded bearing.		
	Slight eccentricity of internal bearing surfaces.	Lubricate well and rotate hib within unit for 200 to 300 revolutions.		
	Scratch on internal hearings.	Disassemble and inspect. Carefully blend out any blemishes. Lubricate well upon reassembly.		

- 4.7 Ferguson Machine Rite-Torq Torque Limiter, Ref. Fig. #8
- 4.7.1 Rite-Torq offers a newly developed mechanical torque limiter which is a takeoff from their AS-20 light duty unit, using the same basic principle of torque transmittal, with a greater range.
- 4.7.2 The basic unit selected for this application is a Type
 "S" Size 2 unit which resets automatically with a torque
 range up to 520 Lb. In. and is externally adjustable.
- 4.7.3 With the tripping components made from heat treated chromium alloy steel, standard units have been subjected to 50,000 trip cycles under design loading with negligible wear.
- 4.7.4 Other features included in the standard basic unit are,
 - (a) Bi-directional operation
 - (b) All position mounting
 - (c) Fully enclosed
 - (d) Lubed for life
 - (e) Protected against corrosion
 - (f) Setting accuracy ± 5%
 - (g) Locking ring tab for maintaining satting
 - (h) Limit switch operation up to 2000 RPM
- 4.7.5 When a limit switch is used with a totally enclosed unit, a trip plate must be added to provide clearance for the limit switch actuating arm and the spring cover.

- 4.7.6 The clutch half of the unit has a maximum 1 1/8" bore and will require an adapter to accommodate the motor bore sizes of 1 5/8" and 1 7/8". The coupling half of the unit must be a flexible type to allow for shaft misalignment and also provide for a 2" maximum shaft size on the reducer. Figure 9 shows a roller chain flexible coupling mounted to the torque limiter, however, any type of flexible coupling may be used.
- 4.7.7 The manual reset pin (5) shown in Figure 8 is an added feature, making the unit more versatile. However, it is not considered to be a requirement on this application.
- 4.7.8 The setting torque accuracy is possible on request, by supplying each unit with an indicator plate or setting chart which allows the release torque to be set on site to any value within the unit's range with an accuracy of ± 5%.
- 4.7.9 According to Rite-Torq, the ratcheting effect of the detented balls on disengagement has negligible wear on the tripping components and will reset under motor enertia when it becomes lower than the overload trip setting.

 The stopping time will be less than a free rotating motor due to the braking action of the torque limiter resetting or ratcheting.





MECHANICAL OVERLOAD CLUTCH FOR PRECISINSTANT RESPONSE.....AUTOMATIC RESET...

COMPLETE DEPENDABILITY

The Rite-Torq overload clutch protects your machine from damage by terminating power almost instantaneously when an overload-causing jam creates torque in excess of set limits. When the jam is cleared the Rite Torq resets automatically to resume operation, thus it is ideal for remote or inaccessible installations.

Completely mechanical, the Rite-Torq maintains the precisely set tripping point regardless of speed, number of trips or ambient temperatures. Although you may specify a factory set tripping torque and never have occasion to change it, simple external adjustments can be made if desired to afford a wide range of torque protection.

MAINTENANCE-FREE

The Rite-Torq does not rely upon friction surfaces for its operating principle. Rite-Torq safety clutches transmit motion through balls retained in seats between driving and driven hubs. During an overload the hubs separate sufficiently to allow balls to roll from seat to seat under positively controlled pressure. With only rolling friction present, the Rite-Torq is subject to virtually no wear. Its rugged cast housing is sealed by O-rings against abrasive substances and moisture. Except in unusual circum stances, original factory lubrication need not be replenished.

EASILY INSTALLED

Each size unit has a nominal torque rating with a range of adjustments to approximately 50% above or 50% below. Ideally, tripping torque should be at least 40% greater than operating torque; "tripping torque" being the maximum torque load below which the Rite-Torq will transmit power without disengaging.

THE STATE OF THE PROPERTY OF T


Preferred location for mounting a Rite-Torq is between the low speed side of the reducer and the driven machine or mechanism. Under adverse conditions caused by vibratory, intermittent or reversing loads we recommend that you consult a Ferguson representative or distributor for applications assistance.


FOR CHAIN, BELT AND DRIVEN MACHINES

There are nine models for either sprocket (Type C) or coupling (Type S) mounting to provide tripping torques from 65 to 52,000 inch-pounds. They are furnished with stock bore diameters. Other bore diameters may be specified at a slight additional charge (See dimensional table).

SINGLE POSITIONING

Any of the models may be ordered with an optional single positioning feature which acts as a phasing mechanism to insure that your machine resumes cycling when the jam is cleared at the precise point where the interruption occured.





MODEL AS-20 LIGHT DUTY UNIT

EXTERNAL ADJUSTMENT.

SPECIFICATIONS MOUNTING TOLERANCES: Angular 1º Total - Concentricity and Squareness .002" TIR.

	TRIP T	ORQUE ((InLbs.)	MAX. RPM†	NO.	INFOTIA	14/7	BORE	DIAM	ETER	(Inches)	+.001	000
MODEL	NOM.	MIN.	MAX.	WITH LIMIT SWITCH	OF BALLS	INERTIA (WK²)	WT. (LBS.)		STO	CK		MIN.	MAX.
AS-20	130	65	195	1800	31	.028	10	.625	.750	.875	1.000	.56	1.00
AS-30	270	135	450	1800	28	.178	11	.750	.8	75	1.000	.56	1.00
● AM-60	800	400	1670	1800	36	.247	13	.875	1.0	00	1.125	.69	1.18
● AM-120	1620	825	2440	1800	44	.415	18	1.000	1.1	25	1.250	.75	1.38
AS-250	2170	1100	3125	1200	42	.83	28	1.250	1.3	75	1.500	1.12	1.75
AS-500	4335	2200	6760	1200	45	2.20	50	1.625	1.8	75	2.000	1.62	2.38
● AM-1000	12945	6450	20700	900	40	10.30	110	2.0	00	2.	375	1.94	2.68
AS-2000	17240	8700	26500	900	44	22.50	180		2.5			2.38	3.38
AS-4000	34680	17000	52000	500	42	60.70	344	3.1		<u> </u>	250	2.94	4.18

* Factory trip setting unless otherwise specified.

† Single positioning units have maximum speed of 100 RPM and require limit switch -- consult factory for higher speeds.

AM Couplings are interchangeable dimensionally with AS Couplings having the same numerical designations but minimum and maximum tripping torques are approximately 50 percent greater. Lower tripping torques can be provided at slight additional charge.

STANDARD KEYWAY DIMENSIONS

	BORE	DIA.	VEVWAV	BORE	DIA.	WEWMAN
FR	MOS	TO	KEYWAY	FROM	то	KEYWAY
	500	.563	1/8 x 1/16	1.813	2.250	1 2 x 1/4
ا	625	.875	3,16 x 3 32	2.313	2.750	58 x 5 16
	938	1.250	1 4 x 1/8	2.812	3.250	34×38
1.	313	1.375	5/16 x 5 32	3.313	3.750	7 8 x 7/16
1.	438	1.750	3/8 x 3/16	3.813	4.500	1 x 1/2

WHEN ORDERING

Specify Model number, Type S or Type C, bore dimensions and torque setting and indicate if optional single positioning is required.


TO DETERMINE TORQUE

HP $\frac{\text{Torque(In.\cdotLbs.)} \times \text{RPM}}{63025}$ OR: Torque(In.·Lbs.) $\frac{\text{HP} \times 63025}{\text{RPM}}$

FR TRIPPING TORQUES FROM 135 TO 52,000 IN.-LBS.

TYPE 8-COUPLING MOUNTING

TYPE C-SPROCKET MOUNTING



NOTE: If arrester bolt and washer (supplied by customer) cannot be used on Type C model install a set collar next to driving hub to prevent axial movement.


DIMENSIONS

"D" is travel distance for limit switch actuation; for single positioning, couplings use D/2 (see back page). Special hub diameters between standard (max.) and minimum can be provided at slight additional charge. "K" is keyway dimension. A flat key meeting standard sprocket requirements is included.

										J (+.00	0001)				
MODEL	A	B	C	D*	E	F	G	H	ı	STD. (MAX.)	SPEC. (MIN.)	K*	L	M	N
AS-30	5.89	3.81	.80	.16	1.97	1.50	6.09	1.77	1.09	1.75	1.56	¾ x ⅓ ₂	4.53	4.33	2.76
AM-60	6.30	4.14	.80	.16	2.36	1.83	7.00	2.00	1.50	2.00	1.75	1/2 x 1/6	5.43	4.09	3.07
AM-120	7.19	4.97	.80	.16	2.36	2.66	7.91	2.17	2.17	2.12	1.95	1/2 x 1/4	6.34	4.96	3.78
AS-250	7.64	4.97	1.02	.20	2.91	2.44	9.06	2.77	2.17	2.75	2.50	5% x ⅓	7.48	6.06	4.62
AS-500	10.34	7.00	1.38	.23	4.11	3.50	10.23	3.55	3.06	3.56	3.19	% x 1/4	8.66	7.24	5.59
AM-1000	12.44	8.42	1.19	.34	4.11	4.34	13.66	4.12	3.34	4.12	3.89	1 x ¾	12.09	10.08	7.88
AS-2000	15.75	11.14	1.38	.39	5.30	6.34	15.98	5.12	4.92	5.12	4.50	11/4 x 3/4	14.41	12.02	9.00
AS-4000	18.80	12.12	2.75	.52	5.30	6.53	18.91	6.69	5.31	6.69	5.88	1% x %	17.17	14.17	11.25

MODEL AS-20 FOR LIGHT DUTY MACHINES

LIMIT SWITCH ACTUATING DISC IS AVAILABLE.



SPROCKET MTG.

AS-20C FOR

COUPLING MTG.


AS-20S FOR

 $^{\circ}$ The standard hub diameter (J Dimension) for the Model AS-20 is 1.75 incher, Other hub diameters from 1.44 to 2.00 inches may be orde ed for a slight additional charge,

of ₩. ın 1e ut


ŧ.

CONTROLLED BALLS TRANSMIT POWER BETWEEN TWO HUBS




Rotating motion is transmitted by a series of spring loaded hardened steel balls (1) retained in spherical seats between a driving (2) and a driven (3) hub. If load on the machine exceeds set limits for which spring pressure (4) has been established, springs compress (5), allowing the hubs to part sufficiently for the balls to roll over ridges from seat to seat (6), thus terminating the rigid connection between the hubs. Driving hub continues to rotate but the driven hub stops. Balls reseat when load drops to normal and lock the hubs together to resume transmission of power.

An optional single positioning feature (7) insures that balls return only to their original seats so that machine cycle begins at the exact point where disruption occurred. Rite-Torqs with this feature normally have a maximum speed of 100 RPM and require a limit switch (See back page). Consult factory if higher operating speeds are desired.



TITATION INTERNITATION OF THE PROPERTY OF THE






ST


SI


TO STOP MOTOR

At instant of overload there is an axial displacement ("D" movement in dimensional drawings and table) of the driving hub. It is this movement which creates the clearance between the hubs that allows passage of the balls from seat to seat. The displacement may be employed to actuate a limit switch to stop the power supply. The photo shows a typical installation with a Type C Rite-Torq. A similar arrangement is feasible with the Type S models.

In addition to stuffly individed in the power supply the contravity can also be explayed to actuate a visual or autilities your Such an arran ement is particularly so table where installations are remotely to used and frequently chaffen to:








DISTRIBUTED BY:






MISALIGNMENT

MAX. ANGULAR 1/2°

MAX. FARALLEL .015"




(44)

FIG No. 5

DAVID BROWNSADI



Mechanical Torque Limiter



Mechanical Torque Limiter

The David Brown Torque Limiter provides dependable protection for driving and driven machinery accurately, tripping whenever the preset torque is exceeded regardless of rotational speed.

No slip drive below tripping torque. Operates at speeds up to 2,000 rpm in either direction and may be mounted in any position.

Design based on standard electric motor shaft extensions allows input hub fitting to electric motors, gearbox shafts and all driving machinery via chains, vee belts and shafts to driven machinery.

Immediate mechanical action gives accurate tripping indefinitely with virtually no maintenance. Overcomes the delay, friction/heat generation, torque variation, maintenance and resetting problems associated with electrical devices, shear pins and slip clutches.

For long starting times (high inertia drives) or where it is desired that the limiter trips very close to the effective running torque of the machine a simple special feature is supplied.

Wear resistant. Tripping components are in heat treated chromium alloy steel and standard torque limiters have been subjected to 50,000 trip cycles at the design torque loading with negligible wear.

Fully enclosed, lubricated for life unit supplied fully bored to suit your driving shaft and with vee belt pulley, chain sprocket or shaft coupling for immediate operation. May be used in machines fully immersed in oil if desired.

The tripping torque may be preset before despatch or adjusted on site with a C. spanner.

Resetting is automatic or supplied with a simple manual resetting accessory.

A wide variety of versions may be made to order for particular applications, for example; single position reengagement enabling the relative angular position of driving and driven hubs to be maintained; single direction action, tripping limited to 2 revolutions before re-engagement automatically, and minimal backlash.


May be used with a limit switch activated on disengagement to cut-off electricity supply to motor.

Every torque limiter is fully tested before despatch, and protected against corrosion in service

The relatively low cost of a David Brown Torque Limiter will be more than recovered in downtime and equipment damage savings the very first time there is an overload.

PROTECTION


LOW COST!



Patents applied for in U.K., France, Belgium, Spain, Italy, U.S.A., Canada, Germany and Japan.

Selection

The drive is transmitted from the hub (1) to the driving ring (2) and via steel balls to the output ring (3). On overload, when the separating force exceeds the spring pressure (4) the balls move out of their seats displacing the driving ring which will activate the limit switch to cut the motor supply current or activate a warning signal. With the manual reset version the pin (5) prevents the driving ring (2) from returning when the overload is reduced and the hub (1) turns freely on the self lubricated bearing (6) and thrust bearing (7) whilst the ouput ring (3) remains stationary.



The unit is lubricated for life and conforms to DIN P.33 or C.E.I. IP.44 standards of protection. For excessively dusty or adverse atmospheric conditions consult our technical department.

Specify as follows:-

Example Specifies:—

A size 2 Sprocket drive with a 24 mm bore suitable for operating speeds of between 500 and 2,000 rpm, and a torque setting of 4 mkg.

For the types M and P add details of the output hub bore and keyway required.

Add special features required, e.g. manual reset, one position reset, non standard sprocket etc. To enable us to check your selection, add details of the type of machine concerned, the motor characteristics and the proposed mounting position.

All units are uniquely identified by the size and serial number stamped on the face of hub (1).

For the majority of applications select the torque limiter with a maximum tripping torque at least equal to 2 × the normal transmitted torque at the point of mounting. The chosen mounting position should be as near to the expected overload as possible.

With motor speed applications inertia forces are involved which vary with the type of motor and methods of starting used. In particular the limiter has to be set such that it does not trip at start or under slow deceleration conditions but that it does trip under stall conditions. For further details consult technical sales sheet No. 370. David Brown trained engineers are available throughout the world to advise on specific applications.

For variable or multi-speed drives:---

Mount the Torque Limiter between driven motor and reduction gear where the same H.P. is required at the different speeds (constant H.P.). Mount the Torque Limiter between the reduction gear output shaft and the driven machine where the H.P. varies in relation to the speed (constant torque).

To que (mkg.)

H.P. • 716

		Trippin	g Torque Mkg	Max.					
ize		Min. *Also Standard Factory Setting	Max. Speeds between 500-2,000 rpm (H)	Speeds below 500 rpm (L)	Inertia mkg²	Approx. Weight Kg Type T	Standard Bore Sizes mm	Corresponding Standard European Motor at 1,500 rpm HP	
	A B C D E	03	15	45	0087	23	Pre bore (12) 14 14 19 19 Pre	0 33 0 5 0 75 1 0	
	A B C D E F	1 2	60	20 0	0198	3 75	hore (19) 24 24 28 28 28	1 5 2 0 3 0 4 0 5 5	
	A B C D E	5 0	25 (1	<i>1</i> 5 0	0 070	90	Pre hore (28) 38 38 42 42 42 Pre	7 5 10 15 20	
	A B C D E F	15 0	50 G	150 O	0 183	14 0	tore (38) 48 48 55 55 60	25 30 35 40 50 4 7	

*Unless otherwise specified

Specification

TORQUEAD "UST E T

The release torque is normally factory set at the minimum value. To adjust the setting with the limiter installed in position, the adjusting ring should be screwed progressively clockwise using a C. spanner until the drive operates normally without the limiter tripping. The ring should then be locked in position with the locking ring tab.


Alternatively the torque limiter may be supplied accurately preset dynamically to any desired value.

On request, torque limiters may be supplied with an indicator plate or setting chart allowing the release torque to be set on site to any value within the range with an accuracy of \pm 5%.

STALLATION

The standard torque limiter is supplied complete with the limit switch and

- (a) bored and keywayed.
- (b) pilot bore. The operations of boring and keywaying can be made without dismantling. (see illustration below).
- or (c) bored and keywayed to client's specifications.



After fitting to the electric motor or machine shaft it is only necessary to restrain the limiter with a screw and washer as shown on the dimension pages.


To reset the manual reset device after tripping, first check that the motor current is switched off. Turn the screw anticlockwise 5 full turns. The limiter will be heard to re-engage distinctly. Finally turn the screw clockwise until fully engaged.


This feature is specified as standard for type 'H' limiters.

For type 'L' limiters expected to trip frequently and for drives with long acceleration times, specify the single position re-setting.

Axial displacement for unit switch on tripping is 5, 6, 7.5, and 10 mm for sizes 1 to 4 respectively.


A suggested wiring circuit for the limit switch supplied with the coupling is shown below (see figs., 10, 11 and 12), with the limit switch 9 wired in parallel with the starter 'on' button 14 and in series with the starter "lock in" contact. This will enable the machine operator to start up again after the overload has been relieved, even if the coupling has stopped with the limit switch 'open'. An alarm system or relay (to stop a full line of motors) is possible by use of a 'double throw' limit switch.







48


Application examples










PASSACO PAZO PAZO PASSACIA SEREZARA








A standard type 'S' torque limiter with special universal joint half coupling supported on a fall bearing fitted to the output shalt of a gear unit.





Principal dimensions (mm)

Size	.: 'V' A	8		C		D D	1		F	G	· · · · ·	Н	J	К	1	L	M	N	·	0	P	0)	R	Š		ь		1
																													<u> </u>
*	35	5	2	85		90	ę	95	40	6	C	125	45	18	1	20	5	7.9	5	-	95	1	6		SPZ		5 6	14 19	16.3 21.8
<u> </u>	50	7	0	103	l	110	1	20	40	7	5	150	56	19,	5 2	23	7,5	8			114	2	0		SPA		8	24 28	27.3 31.3
3	70	9	2	133	;	141	1	55	60	1	06	200	83	23	;	27	1Ô	15	i		158,	5	_	43	2× SF	В	10 12	38 42	41.3 45.3
ş.	85	1	10	160)	168	1	80	70	1:	25	236 250	105	22	4	40	10	25 33	i	_	202, 210,	5 -	_	62 82	3× SF 3× SF		14 16 16	48 55 55	51.8 5.,3 59.3
Турі	- 'V)	<i>!</i> '																00	,		210,	•				•	18	60	64.4
Size	A	8	_ ,	C	D	-	E	F	G	1	Н	J	K	L	ا	M	N	C	P	 , 	Q	R				ь		ď	
	35	52		85	90	,		40	60	,	101,3	45	18	20) !	5	7	6	1	00	7			1 SIMPLS " DIN 81		5 6		14 19	16.3 21,8
2	50	7Ö		103	110)	108	4Ō	75		133,8	56	19.5	23	3 7	7,5	8	6	1	19	10,5	22 T	TEETI CH: 3	I SIMPLE " DIN 81	X 87	8		24 28	27.3 31.3
3	70	92		133	141	. '	138	60	13	6	178,5	83	23	27	, 1	10	11	11	1	64,5	15,3			1 SIMPLE 7 DIN 81		10 12		38 42	41,3 45,3
ři.	85	110)	160	168	}		70	12	5	202,9	105	22	40) :	10	18	12	3	07,5	18			1 SIMPLI 1 CIN 8		14 16		48 55	51.8 59.3
4	85	110)	160	168	3	168	70	12	5	207.3	105	22	40) ;	10	19	14	2	10.5	23	17	TEETI	H SIMPLI 3" DIN 8	X	16 18		55 60	59.3 64.4
Size	A	В	C	D	E	F	G	H	J	K	i.		r n	0	P	0	!	R	\$	T	u v		Ain.	Max.	Min.	d: M :	ex.	Allow Align Errors Z	ment
							_								•			· ·		•									
March !	52	85	87	90	45	70	40	58	45	18	20	5	16	2	33	7		146	29	8	10 135	1	2	19	10	25		0.5	
2	70	103	110	110	£5	80	40	70	56	19.5	23	7	.5 10	2.	31	1	4	169	29	8	10 153	1	9	28	10	25		0.5	
3	92	133	135	141	85	115	58	95	83	23	27	1	0 22	2	37.5	1	7.5	272	30	15	12 200	2	8	42	15	38		0.5	
4	110	160	162	168	100	158	78	120	105	22	40	1	0 30	2	45	5	1	305	35	20	25 257	3	8	60	28	55		0.7	
Typ	e 'S'	, 																											
Size	A	8	}	С		D			F	G		H	1	K		L	M	N	0		P	Q	R	\$	b		d		
que,	35	5	2	85		90		it	60	7.	2	87	45	18	;	20	5	4	1		93	4	M	5 10	5 6		14 19		5.3 1 . 8
2	50	7	0	103	ŀ	110	-		75	9	0	104	56	19.	5 2	23	7,5	4		-	110	4	M	6 10	5 8		24 28	3	7.3 1.3
3	70	9	2	133	ļ	141	Ş	4	106	1	18	135	83	23	;	27	10	8	4	ı	155	6	M	6 12	1	0	38 42	4	1,3 5,3
Ą	85	1	10	160	ł	168	1	08	125	1.	40	162	105	22		40	10	8	i	0	195	6	M	8 18	1	4 6	48 55	51 51	1.8 9.3
	39	•	,				•			•	•			••		,,		•	•	-		•	***		i	B	60	6	9.3 4.5

mornies mannent charical mannes and an analysi

Davia Dioveri Oriali Ocapinigo




NYLICON

Flexible coupling

Torque: 2,03 to 47,2 mkg Speeds: up to 9,000 rpm Bores: 10 to 55 mm

See publication E.304.11




CONE-RING

Flexible and rigid couplings

Torque: up to 19,000 mkg Speeds: up to 4,420 rpm Bores: 18 to 355 mm

Flange type or with drum for a brake

See publication E.304.18




GEAR TYPE COUPLING

Torque: 203 to 5,420 mkg Speeds: up to 6,000 rpm Bores: 18 to 190 mm Suitable for heavy duty drives

See publication E.304.24

For further details ask for technical documentation or call and see us.

THE REPORT OF THE RESIDENCE OF THE PROPERTY OF



DAVID BROWN SADI S.A.

Rue des Carburants 4 B-1190 BRUXELLES (Belgium) Tel.: 02/345 18:01 Telex: 23 199 DBSADI B

THE DAVID BROWN GEAR INDUSTRIES Ltd, Associated companies in U K, as well as in Australia, Belgium, Canada, France, India, Norway, South Africa, Spain, Switzerland and U.S.A.


- 4.8 Formsprag Reset Clutch, Reference Fig. #10
- 4.8.1 Formsprag clutch type JCB Model #3, uses the ball detent principle with a multiple spring control torque réléase setting.
- By nesting (2) sets of springs (ā set of (20) light and a set of (20) heavy springs), a torque range from 7 ft. Lb. to 150 ft. Lb. is applied to (6) 5/16" diameter balls located on the same radius with a specific spacing which allows disengagement for (1) revolution before resetting. The light set of springs when used by themselves, cover a range from 7 to 40 ft. Lb. The heavy set of springs used separately, have a range of 23 to 120 ft. Lb. The two sets used together provide a range of 32 to 150 ft. Lb. torque.

THE PART OF THE PROPERTY OF THE PROPERTY OF THE PROPERTY OF THE PROPERTY OF THE PARTY 4.8.3 To cover a 3 through 10 HP range, the two sets of springs would be used separately with the light set covering the lower portion of the H.P. range, up through approximately 6 H.P., and the heavy set of springs would use from there onto 10 H.P. maximum.
- 4.8.4 The construction is all steel except for a plastic plug located under the set screw in nut #4 and the bronze Oilite bushings.
- 4.8.5 No provision is made for lubrication of the needle bearing and according to the factory none is required for the entire unit.


- 4.8.6 Other features are,
 - (a) Bi-directional operation
 - (b) All position mounting
 - (c) Fully enclosed
 - (d) Setting accuracy ± 5%
 - (e) Automatic self-engagement on restart
 - (f) Automatic cutoff switch operation (with the addition of a tripping plate welded or brazed to the housing)

and a second of the second of

- (g) Externally adjustable with no means other than a set screw for maintaining any preselected setting.
- 4.8.7 A flexible coupling can be added to the basic clutch, same as the method shown on Figure 9. Due to being somewhat more compact than other designs, only 4" is required for mounting between the motor and reducer shaft. With a 1" maximum standard bore, an adapter is required for one side.



TORQUE LIMITING CLUTCHES



FORMSPRAG FORM-GARD™ (TLC) TORQUE LIMITING CLUTCHES

- YEARS OF TROUBLE-FREE SERVICE
- VIRTUALLY NO MAINTENANCE
- REMOVE OVERLOAD PROBLEMS
- COMPETITIVE FIRST COST

Gone are the problems associated with slow reaction electrical overloads, shear pins which give a wide torque variation and rapidly overheating slip clutches.

Form-Gard Torque Limiters will save you money. The initial cost normally is more than covered by saving of down time during the first overload.

A complete engineering service is available. Let our Sales Engineers assist you on your particular problems.

NOTICE

This catalog provides the required guidance. It is the customer's responsibility to apply and install the torque limiting clutch so that it functions within the limits intended by Formsprag. Since proper selection and application is essential to long and satisfactory service, it is important of give careful attention to the pages which provide information on selection, service, and applications. Any unusual operating conditions requiring selection or application assistance beyond that supplied in the following selections should be referred to the Formsprag Company to assure that the correct size and type of clutch is provided.



Formsprag Company has been marketing and delivering dependable, long-lived, precision-power transmission products for over a quarter century. Formsprag provides one of the broadest lines of industrial brakes, clutches, couplings, sensors and electronic controls in the world. Custom design capability is our specialty.

CPTDA)

Formspray's leadership in motion control results from a conscious, day-after-day striving for product excellence and satisfaction for you, the customer. Our unequalled Engineering, Manufacturing and Marketing team is at your disposal, ready and able to provide you with exactly the right product, exactly when you need it, and competitively priced. Put us to work for you. Formspray. The company that isn't satisfied until you are.



THE PROPERTY OF THE PROPERTY O

Copyright Formspray 1976

CONTENTS APPLICATIONS SECTION MANUAL RESET (BASIC TYPE JAB) mining equipment, conveyors, Types JAB, JAS, JAP, JAR, JAF. machine tools, woodworking and paper machinery, pumps, Complete release - mañual reset. textile machinery, test rigs, rolling mills, quarrying plant, Pages 5, 6, 7 Post Office machinery, extruders, automatic furnaces and ovens. **SECTION AUTOMATIC RESET** (BASIC TYPE JCB) conveyors, bakery equipment, sliding and folding door actuators, packaging, Types JCB, JCS, JCP, JCR. bottling, labelling machines, printing Cômplete rélease for one presses and special-purpose machines. revolution - automatic reset. Pages 8, 9, 10 SECTION **PTO PROTECTION** (BASIC TYPE JFV) Vehicle PTO drives, vone, lobe, Type JrV. screw and centrifugal pumps -Complete release - manual reset. vane and lobe blowers. Page 11. **FEATURES & BENEFITS** Page 4 **APPLICATION INFORMATION** 12 **HOW TO SELECT & HOW TO ORDER** 14

BEYOND THE CATALOG MODIFICATIONS & CUSTOM DESIGNS

STANDARD BORE & KEYSEAT DATA

The wide range of sizes and capacities covered by the Form-Gard Catalog line of clutches will cover most industrial needs; however, your requirements may be better satisfied by other than standard clutches. In many cases standard clutches can be adapted to your special use by a minor modification.

If you require a custom design, Formsprag's quarter of a century experience in the specialized Power Transmission field makes available the depth and expertise required to meet your requirements in the most economical way possible. Please tell us what your requirements are. We will be pleased to quote special designs.

15

ementioned and the construction of the constru

FEATURES

BENEFITS

Automatic and complete disengagement on overload is ständärd on JA and JF models	No torque is transmitted, thus preventing damage and machine downtime due to overload
Easy to reset because no spring conferession or ball alignment is required. Type JC available with automatic reset.	Operator can reset his own machine, avoiding production delays
A single Form-Gard Type-JA Clutch will function as: (1) "Dog Clutch" (2) Overload Release Clutch	Eliminate the need for two separate clutches Reduce system cost, complexity and size
All metal totally enclosed construction	Longer life in contaminated environment Operator safety improved with enclosed springs
Drive torque is transmitted thru tapered jaws on all standard type JA models	Positive drive — no slip or backlash Timing of drive system is assured.
Torque setting accurate within ± 5% is maintained indefinitely	Accurate Ease of maintenance is assured by eliminating the need for continuous adjustment
Bi-directional torque transmission is standard	Selection of proper clutch is simplified Standard unit can be installed on dual direction drive system
Reduced overall length	Reduce the space required and the cost of your drive system
Multiple springs control torque release setting	Increased dependability of drive Larger range of torque setting is available to meet your specific application

OPTIONAL FEATURES

SINGLE POSITION RE-ENGAGEMENT

For use where timing of machine is required. Available for Types JA and JC.

LIGHT DUTY SPRINGS

For systems requiring very low torque levels and greats, range of adjustment sensitivity.

SINGLE DIRECTION OVERLOAD RELEASE For applications where heavy braking is applied. Type JA only.

DUAL LEVEL TORQUE SETTING


For heavy overrunning applications which require normal release torque setting in one direction and a lower torque release setting in the opposite direction. Type JA only.


BASIC MANUAL RESET CLUTCH

TYPE JAB

TECHNICAL FEATURES

Complete disengagement on overload • Simple "one screw" torque adjustment • Positive drive — no slip
Rapid easy reset • Full bi-directional operation • Horizontal or Vertical Mounting • Torque setting maintained indefinitely
All metal totally enclosed construction • Release action can operate a warning device or limit switch
Rugged and compact design • May also be used as a lever operated clutch





	RELE	ASE TO	RQUE			DIME	NSIONS	IN INC	HES AN	D MILL	METER	S			WEIGHT
JAB MODEL	Min. (Note 1)	M	9#.											Anial Inomeren	Mos
	to ft kgm	No ft kgm	HP/ RPM	^	[Note 2]	c	D	E		G mer.	G mm. Note 3;	H	UNC	everload (Note 3)	kg
2	10 1,4	100 14	,02	3,54 90	2.16 55	3.75 95	3.35 85	0.118	2.95 75	1.00 25.4	0.50 12,7	6	% • 20	0.25 6.25	6.5 2.95
5	50 7	500 70	,1	4,70 120	3.15 80	4.92 125	3.54 90	0,118	3.94 100	1.57 40	0.75 19 05	6	₩-16	0.25 6.35	12.3 5.50
7	350 49	1000 140	.2	7,09 180	4.33 110	7.09 180	5.91 150	0.118	5,91 150	2.24 57	1.25 31,75	5	۱ % ۰1:	9.25 6.35	37
8	450 63	2000 280	.4	9.25 235	5.91 150	906 230	5.91 150	0.118	7, 68 195	3.03 77	1.50 38,1	6	%-1	0 25 6.35	66 30
9	600 84	4000 550	л.	12 305	7,874 200	12 205	8.07 205	0.118 3	10 63 270	4.00 102	2.00 \$0.8	6	*-10	0.32 8,13	165

Note 1: Lower release torques can be achieved - Consult Formsprag Company.

Note 2: Tolerance on pilot diameter - Consult Formsprag Company.

Note 3: Dimensions "G min." and "Axial movement on overload" also apply to Types JAR, JAF, JAS and JAP.

Normal running

The drive is transmitted from the hub (1) through the splined ring (2) via the tapered jaws (3) to the coupling flange (4). The jaws are normally held together by spring pressure acting through two angled races (5 and 6) and a full complement of balls (7) located by a step on the hub.

Disengagement

On overload, the tapered jaws are thrust apart, moving the splined ring (2) and lifting the balls (7) over the step on the hub, thus completely disengaging the drive, leaving flange jaw ring (4) free to rotate on bearing (10).

Torque adjustment

The release torque settings are made by adjusting the control ring (8) so altering the spring forces. The adjusting ring is locked in position by a nylon plug (9) or, if preferred, a set screw.

Installation

Clutches can be supplied rough bored or finish bored and keywayed. The hub may be fitted to either shaft and the flange can be connect-

 ϵd to a flexible coupling or can carry a sprocket or pulley. See pages 6 & 7.

Re-engagement

To re-engage, the tapered jaws are aligned using reference marks and the sliding essembly is pushed along the hub until the balls snap back into their original position. This requires no further spring compression.

Application


The clutch can be installed in any drive system, safeguarding against sudden surges or gradual build-up of torque. Modifications are possible to provide manual lever operation of the clutch while retaining the overload release feature. Single direction release and one position mesh can also be provided. (For speeds above 1750 RPM consult Formsprag.)

Note:

For particularly dusty conditions such as cement works we offer neopiene seals at positions (*) above. Please specify when ordering.

TYPE JAR


TYPE JAB WITH RIGID COUPLING



	RELE	ASE TO	RQUE			D1445	MEIONE	141 141	45P 44	****					
JAR	Min.	, Me	×.	1		DINK	NSIONS	IN INC	1169 W	MIE.	LIMETE	:RS			WEIGH
MODEL	#e ft /kgm	No ft Agm	HP/ RPM	٨		С	0	ŧ	F	G	н	J	ĸ	·	Mes kg
2	10 1 4	100	.02	3.54 99	2.5 6 65	1,57 40	0.5 9 15	0.39	3.35 25	3.74 95	1.57 40	1.00 25.4	0.118	6	17.5 5.7
5	50 7	560 70	.1	4,72 120	3.25 85	1.61 41.28	.625 15.9	0.51 13	3.54 90	4,57 125	1.97 50	1.57	0.118	5	72 10
7	250 49	1000 140	,2	7,09 180	4.92 125	2,62 66.7	0.5% 75.4	0.27 77	5.91 150	7,09 180	3.25 85	2.24 57	0.11Z	6	54 25
8	450 63	2000 280	A	9.25 235	4,50 165	3,74 95	1,00 25,4	0,87 22	5.91 150	9.06 720	4.33 110	3.93 77	0,118	"	;;;t
9	690 #4	4000 563	я	12 205	8,46 215	4.65 112	1.18 20	0.98 75	\$.07 205	12	5.51 149	4,00 107	0,118	5	775 125

TYPE JAF

TYPE JAB WITH FLEXIBLE PIN COUPLING




NOTE: THESE PIN COUPLINGS ARE NOT RECOMMENDED FOR HEAVY LOADING

										W. 1000	44 1001 14	a f water	•			
10.5	RELE	ASE TO	ROUE			Dune	****	# 184 184	cus	445						T
JAF	Man,	M	er.	1		VIII.	HOIUN	3 114 IM	CITE D	ANU :	AILLIM	ETERS				WEIGHT
MODEL	Ib ft kem	16 ft kyrn	HP7 RPM	^		c	D	E	*	6	H mes	. H min.	J	K	L	No. kg
2	10 1,4	109 14	20.	6.56 165.6	7.95 75	1,77 45	9,97 27,2	059 15	225 25	2.75 95	1,77 45	n ü	1,00 2,4	0,127 5	4	1457 53
5	50 7	540 70	,1	9.175 7.11,7	4,72	7.54 65	2.95 52,4	0,96 25	2,94 100	4.57 175	7.25 75	Q.15 12	1,57	Q127 S	ŕ	5,3 34
7	350 43	1900 140	.2	9,125 731,6	4,77 170	7,54 63	7.06 3.74	0.3% 25	5.91 150	7,073 120	295 15	a.15 19	7.24 51	Q197 5	*	M.35 34 1
8	490 63	7900 780	.4	11.25 285.8	5.51 140	3.35 85	75A 635	1,1a 20	6.20 160	2.05 220	2.15 R0	1.25 21.75	נתכ וו	0,197 \$	10	178£1 52.46
9	000 54	4000 560		14,75 324,6		4.75 170.65	281 71.37	42,1 E3,65	703 205	17 205	4,85 170.65	759 675	4,50 107	075 435	1.	312 145

MAXIMUM ANGULAR MISALIGNMENT 1% DEGREE

TYPE JAB WITH SPROCKET

TYPE JAS




MULTIPLE SPROCKETS WILL USUALLY BE SUPPLIED WITH BEARINGS TO RUN ON CUSTOMER'S SHAFT FOR ADDITIONAL SUPPORT

FOR SPROCKETS SMALLER THAN LISTED AN ADAPTER IS USED — CONSULT FORMSPRAG


JAS	MELO	ASE TO	NOVE		ELONE IN		394	WLLEST:	STANDA	NO 37400	XET
MODEL	Alla,		.	AMO	MILLIME	TERS		Mo	mber of t		
	Sh Pr Lyan	No Per Agent	NO.	٨		¢	Nº nee	75° Press	16-Page	% -A	I-Aug
2	16 1-4	100 14	, Art	272 27	3,35 35	1,00 25-4	*	×	71	淮	25
5	, 49	344 72	,1	2A3	4,90 125	1 <u>.57</u> 46	\$37	72	37	גֿנ	M
7	350 47	1200	.,	5.79 167	7,000 1,000	7.34 4.7		**	>>	*	×
	440 43	7000 ?≱‡	A	5.79 147	9,9 5 222	2,62 11			50	11	×
,	644 24	4000 (40)	*	7,96 767	12 294	4,00 167				53	\$3

TYPE JAB WITH PULLEY

TYPE JAP



FOR PULLEYS SMALLER THAN LISTED
AM ADAPTER IS USED -- CONSULT PORMSPRAG




	M	LEASE TOR	CIVE	9000	MONE IN IN	THE AND MILLING	TERS
JAP	MA.		.				
	Ba Ay Ligan	Ma Ri Supra	participa.	•	•	•	•
2	10 1,4	966 28	×	452 135	አት ታ		1,44 26.4
5	ů 2	3495 2A	,)	€3A 135	4 257 523	tokat Calestar	2 5.7 ču
7	296 42) piped 181	,Z	34a #31	7 pag 354	Mary Mariant Services	\$ 34 \$4
8	9% 63)446 ;15	.3	94 K3 ;36	31,000 7,500	1 [X ≯ 3

TYPE JCB

BASIC AUTOMATIC RESET CLUTCH

TECHNICAL FEATURES

Instant release at pre-set torque • Smooth and complete disengagement for one revolution Bi-directional • Horizontal or Vertical mounting • All metal, totally enclosed Automatic self-engagement on restart without loss of phasing



JĆB MODÉL	MAX: RELĒASĒ	TÔRQUE		DIN	MÉNSIC	ONŜ IN	INĈH	EŜ AN	DMIL	LIMÉTERS	•	WEIGHT
MODEL	lb ft kgm	HP/RPM	A	Ė	ć	D	É	F	G	aty/unc_ J	K	lbs kg
1	30 4	.006	2.98 76	1.38 35	2.37 60	2.42 62	0 06 1.5	1,23 31	0.63 16	(31 <mark>¼ -20 ^{2,60}</mark>	0.31 8	3 1,36
3	150 21	.03	3.70 94	2.13 54	3.44 87	2.56 66	0.06 1.5	1.33 34	1.13 28	(6) 14 -20 331 84	0,44 11	6.20 2.80

Normal running

The drive is transmitted between the hub flange (1) and the housing (2) by the balls (3), spring-loaded into the pockets on the hub flange face.

Disengagement

On overload, the balls are displaced axially, further compressing the springs. Once out of their pockets, the balls roll between the face of the hub flange and the needle thrust bearing for one revolution before re-engaging and synchronizing the drive.

Torque adjustment

The release torque is set by ā tightening nut (4) thus increasing the spring pressure. After setting, the nut is locked with a set screw and plug:

Installation

Clutches can be supplied rough bored or finish bored and keywayed. The hub may be fitted to either shaft and should be located against a shoulder to resist the resetting spring force. (Fig. 1). The drive flange may be replaced by a sprocket, pulley, etc., or connected to a coupling as shown on pages 9 and 10.

Application

This type of protection is ideally suited to drive systems where it is essential to restart in the correct sequence and where access for manual resetting is not available.




Fig. 1

Note:


Type JC clutches should always be used with a limit switch to bring the drive to rest within a few revolutions thus preventing possible damage by continual releasing and resetting. See Page 12.

TYPE JCB WITH SPROCKET

TYPE JCS

Multiple sprockets will usually be supplied bushed to run on customers shaft for additional support.

For sprockets smaller than listed, an adaptor is used Details on request.




JCS	MAX. RELEAS	E TORQUE	DIM	ENSION ND MIL	IS IN INC	CHES	SMA		TANDARI	D SPROCI	KET
MODEL	lb ft kgm	HP/RPM	A	ß.	Č	D	¾" Pitch	½" Pitch	%" Pitch	¾"Pitch	1" Pitch
1	30 4	.006	2.04 52	2.98 76	2.37 60	0.625 16	30	22	19	17	14
3	150 21	.õ3 -	2.10 53	3.70 94	3.44 87	1.125 28	38	28	23	20	15

TYPE JCB WITH PULLEY

TYPE JCP

Note: Pulleys to suit the following belts can also be supplied — standard 'V' section, flat, poly 'V' and timing.


For pulleys smaller than listed, an adaptor is used Details on request.



JCP	MAX. RELEA	SE TORQUE	DIM	ENSIONS IN	INCHES AN	DMILLIMET	ERS
MODEL	lb ft kgm	НР/ЯРМ	Α	В	С	D	E
1	30 4	.006	To suit	2.98 76	2 37 60	0 625 16	4 00 102
3	150 21	.03	To suit	3.70 94	3 44 87	1.125 28	4 875 124



TYPE JCB WITH RIGID COUPLING



JCR	RELEAS	E TORQUE			DIMÈN	SIONŠ	IN INC	HĒS A	NĎ MII	LLIME.	rĒRŜ		**	WEIGHT
MÖDÊL	lb ft kgm	HP/RPM	A	Ê	c	Ď	Ē	Ě	Ğ	н	J		L .	lbs kg
1	30 4	.006	2.99 76	2.17 55	1.50 40	0.59 15	1.22	2.44 62	2.36 _60	0 63 16	1.38 _ 35	0.06 1.5	3	4.5 2
3	150 21	.03	3,70 94	2,79 7	2,00 50.8	0.59 15	1,34 34	2.60 66	3.43 87	1.10 28	1.73 44	0.06 1.5	6	9.5 4,3

NOTE: This arrangement will not accommodate any misalignment.

THE REAL PROPERTY OF THE PROPE

THE PROPERTY OF THE PROPERTY O


TECHNICAL FEATURES

Prevents expensive transmission damage by automatically disengaging on overload

Flange mates with standard series universal joints

Rélease torque adjustable up to 360 lbs ft maximum

Fully sealed against the environment of a PTO drive



UNIVERSAL JOINT SERIES	PILOT DIA.	BOLT CIRCLE DIA.	UNC THD. HOLE	NUMBÉR OF HOLES
1110 or 1140	2.250/2.252	2,750	₹ ₄	4
1300 or 1310	2,375/2,377	3.125	%	. 4
1350 or 1410	2,750/2,752	3.750	7/4	4

Dimensions in inches

INSTALLATION

The hub is mounted on the drive shaft of the PTO using a clearance fit and key. When installing, do not harmer the flange face (1). Mount universal joint to flange using socket head screws.

Release torque setting


The clutch can be supplied set to your specified torque. To increase the setting, turn the adjusting nut (2) clockwise; to decrease, counterclockwise. Do not unscrew beyond the flush position where the zero marks coincide.

To reset

When the clutch operates and disengages the drive, first locate and clear the cause of the overload. To reset, rotate the flange (1) to align the raised screw (3) in the housing with the set screw (4) in the hub. Hold the flange and, with a pry-bar, turn slightly in the direction of the arrow.

Maintenance

Clutches are grease-packed on assembly with a molybdenum disulphide base of grease. A grease fitting is provided for routine maintenance.




DOG CLUTCH FEATURE

Contract of the second

Townships and the stress and the companies and the second

Typical arrangement of Type "JA" with Shifter Ring for use as remote control "Dog Clutch".




A feature of the Type "JA" Clutch is that it can be used as a lever operated "Dog Clutch". By adding a shifter ring to the clutch a conventional yoke mechanism can be used to provide remote control lever actuation to engage and disengage the clutch.

This feature has been found very useful on conveyors for maintenance work which requires disconnection of the gearbox and motor. The Dog Clutch feature can also be used on large machines such as printing presses to disconnect and isolate specific sections.

The normal overload release feature is retained and the dual purpose clutch forms a compact unit with unique characteristics.

LIMIT SWITCH OPERATION

Typical arrangement of Type "JA" and Type "JC" for use with limit switch for automatic shut-off.



The axial movement of the clutch body on overload can be used to operate a limit switch to shut the drive down or to provide visual or audible warning. Because the Type "JA" clutch is completely free running on overload the use of a limit switch is optional. However, we strongly recommend that a limit switch be used with the automatic Reset Type "JC" clutch unless the operating speeds are very slow.

the contract of the contract o

TYPICAL APPLICATIONS

- BOTTLING EQUIPMENT
- AUTOMATIC FURNACES OR OVENS
- AUTOMATIC DOOR OPENERS
- DRYING DRUMS
- TRANSFER MACHINES
- WASHING MACHINES
- RUBBER PROCESSING MACHINES
- FILM PACKAGING MACHINES
- **TOBACCO PROCESSING EQUIPMENT**
- SPECIAL MACHINERY


one increase and the high of the december of the local of the second of

- TRACTOR PTO DRIVEN WINCH
- PACKAGING AND LABELLING MACHINERY

- CONVEYORS
- MACHINE TOOLS
- BAKERY EQUIPMENT
- WOODWORKING MACHINERY
- PRINTING PRESSES
- PAPER MACHINERY
- TEXTILE MACHINERY
- ROLLING MILLS
- PTO DRIVES
- MIXERS
- PUMP DRIVES
- MINING EQUIPMENT

WHERE TO INSTALL FORM-GARD

In most drive systems there are several alternate locations where the Form-Gard clutch can be installed (Fig. 2). The preferred position for Form-Gard is at the driven shaft. This location places the overload protection clutch at a point in the drive system where actual load torque can be accurately monitored. Alternate locations in the drive system as shown in Figure 2 are usually subject to greater variation in torque loads due to the reduction ratios within the drive system. The preferred mounting location will provide better control of the overload release torque thus preventing unnecessary release at torques below safe operating levels due to system inertia and starting torque peaks.



REDUCTION GEARING

When Form-Gard Clutches are installed on large ratio reduction gear boxes care must be taken since it may not be practical to set a torque limiter mounted on the input shaft low enough to provide the proper torque protection on the output shaft. The large reduction ratio will also decrease the accuracy of the output release torque setting if the clutch is located on the input shaft.

HIGH INERTIA DRIVE SYSTEMS

When selecting Form-Gard for use in a high inertia drive system the location of the clutch must be between the high inertia load (flywheel, large pulley or gear, etc.) and the driven mechanism. Locating the Form-Gard overload release clutch in this position will protect the driven mechanism from the large inertia forces.

energies de la comparación del comparación de la comparación de la comparación del comparación de la comparación de la comparación del comparación de la comparación del comparación del comparación del comparación del comparación del comparación del comparación del comparación del comparación del com

HOW TO SELECT

Select Manual Reset, Automatic Reset or PTO Mounted type overload release clutch to suit your specific application.

Choose a position in your drive system for the Form-Gard clutch. See page 13 for guidance. Calculate the torque setting required for the position selected.

Calculate the maximum permissable torque for the drive components after considering torsional stress in shafting, stress on keys and keyseats, torque capacity of couplings, chains, gears, belts, etc. It is the weakest component in the system that requires protection.

-or-

Determine the torque setting based on motor horsepower, drive speed and reduction ratios calculating the drive torque.

torque (lb. ft.) = horsepower x 5250 RPM

-or-

Determine the maximum permissable driven load based on conveyor belt or chain tension.

noncontractive designations of the contractive designation of

An allowance for starting torque may be required depending on the location of the clutch in the drive. At the motor shaft peak torques of approximately twice normal running torque is possible. At locations away from the motor peak torques will be damped by system inertia, tending to reduce the effect of motor peak starting torque. Field conditions will also tend to change the calculated torque values.

The best way to deal with the above variables is to make some allowance when selecting the torque setting required. Keep in mind that each Form-Gard clutch is adjustable and the final overload release torque setting can be adjusted on the job to meet your specific application requirements.

With the approximate torque required select the right size and type clutch from the tables on Pages 5 thru 11.

Check the clutch selected to make sure the shaft, key, sprocket, pulley or U-joint, etc. requirements of your application can be accommodated.

HOW TO ORDER

Please supply the following information with your order:

Quantity: The number of clutches needed.

Type /model / bore and keyseat. Example: Type JAB-7 / 1.625" bore / 36 × 36 keyseat

When combination units are selected supply additional data as required below:

For coupling combination supply bore and keyseat for coupling.

For sprocket or pulley combination supply complete sprocket or pulley data.

For Type "JF" clutch supply complete U-joint data.

Advise torque setting required.

Special requirements such as shifter ring, neoprene seals, etc. must be specified.

If bore and/ or keyseat sizes other than standard tolerances or shaft fits are required, please specify dimensions completely including tolerances. Standard shaft fits and bore tolerances are listed on page 15.

Please submit a completed application data sheet (forms available from Formsprag) for all Form-Gard Clutch applications which require torque, speed, bore, shaft fits, keyseats, or other special requirements not listed in this catalog.

STANDARD BORE & KEYSEAT DATA

PRICE LISTS REFER TO THESE STANDARDS

TYPE "JA" CLUTCH

CLUTCH SIZE	2	5	7	8	9
INDIVIDUAL	.625	.875	1.250	2.000	ANY BORE
STANDARD BORE SIZES	.750	1.000	1.500	2.500	OR KEYSEAT WITH STD.
	.875	1.125	1.625		TOLERANCE WITHIN BORE
		1.250	1.750		RANGE
			1.875		
MINIMUM BORE	.500	.750	1,250	1,500	2.000
MAXIMUM BORE	1,000	1.575	2.240	3.030	4,000

TYPE "JC" CLUTCH

CLUTCH SIZE	1	3
INDIVIDUAL	.375	.625
STANDARD BORE SIZES	.500	.750
		.875
		1.000
MINIMUM BORE	.250	.500
MAXIMUM BORE	.625	1.125

TYPE "JF" CLUTCH

CLUTCH SIZE	4
INDIVIDUAL	.875
STANDARD BORE SIZES	1,000
	1.125
	1.250
MINIMUM BORE	.750
MAXIMUM BORE	1.500

STANDARD TOLERANCE ON ALL BORE SIZES WILL BE NOMINAL BORE - .000 / + .001 INCH.

STANDARD	KEYSEAT TO	LERANCES
All Sizes	Width	+ .002 000
Al! Sizes	Depth	+ .010 000


STAN	STANDARD KEYSEATS (INCHES)						
Nominal Sh	aft Diameter	Keyseet					
Over	Thru	Width	Depth				
3/8	7/16	3/32	3/64				
7/16	9/16	1/8	1/16				
9/16	7/8	3/16	3/32				
7/8	1-1/4	1/4	1/8				
1-1/4	1-3/8	5/16	5/32				
1-3/8	1-3/4	3/8	3/16				
1-3/4	2.1/4	1/2	1/4				
2-1/4	2.3/4	5/8	5/16				
2-3/4	3-1/4	3/4	3/8				
3-1/4	3-3/4	7/8	7/16				
3-3/4	4-1/2	1	1/2				
4-1/2	5-1/2	1-1/4	5/8				
5-1/2	6-1/2	1-1/2	3/4				

SPECIAL BORE AND KEYSEAT

All units can be supplied with special bore and keysest sizes to meet your specific application requirements in both English and Metric sizes. Full shaft and keysest details including tolerances must be supplied with order.

THE PROPERTY OF THE PROPERTY O

OTHER FORMSPRAG-MT. PLEASANT POWER TRANSMISSION PRODUCTS



Formsprag Warranty

Formsprag Company guarantees all its products will leave the factory in good condition. Formsprag warrants its products against defects in workmanship and material for a period of 365 days (one year) after shipment. Adjustments under this warranty will be made only after completion of inspection of the part or product in Formsprag's factory. Formsprag's liability under the warranty shall extend only to the replacement or correction of any defective part or product determined by Formsprag inspection as not conforming to this warranty.

This warranty shall not apply to any product which shall have been repaired or altered without Formsprag's knowledge and consent or operated or installed contrary to Formsprag's instruction or subjected to misuse, improper maintenance or is damaged by accident or negligence.

This warranty is made in lieu of all other warranties, express or implied, including but not limited to warranties of merchantability or fitness for a particular purpose, and there are no other warranties that extend beyond this express warranty.

Formsprag Company reserves the right to discontinue models or to change specifications at any time without notice. No discontinuance or change shall create any liability on the part of Formsprag in respect to its products in the hands of its customers or products on order not incorporating such change even though delivered after any such change.

Performance Assurance

Rated torque and speeds of Formsprag products are provided in current catalogs to assist the buyer in selecting the proper Formsprag product. In addition, application engineering assistance is offered by Formsprag Company for guidance to the buyer in selection of a catalog product and for design and application of custom designed couplings. Since the actual performance characteristics of the buyer's equipment cannot be reproduced in Formsprag testing laboratories, performance assurance of all Formsprag products in the buyer's application is the responsibility of the buyer. Performance assurance is usually accomplished through manufacture of a prototype by Formsprag, and a test or qualification program on the part of the buyer.

Rotating equipment is potentially dangerous and should be properly guarded. The user should check for all applicable safety codes in his area and provide a suitable guard.



DIVISION OF DANA CORPORATION

801 E. INDUSTRIAL DR. • MT. PLEASANT, MICHIGAN 48858 TELEPHONE (517) 773-5931 • TELEX 227447

> CANADIAN SALES: 17 VALOIS BAY AVENUE PT. CLAIRE, PO H9R 4B4 CANADA (514) 695-7602

70

10M-4/76 - 1st Edition

THE CONTRACT STATES AND STATES AND STATES OF STATES OF STATES AND STATES AND STATES OF STATES AND STATES OF STATES AND STATES AND STATES OF STATES AND STA

4.9 Helland Torq-Tender, Reference Fig. #11

- 4.9.1 The Helland Torq-Tender is a positive mechanical device which uses a detented key that is radially opposed by

 (2) counteracting compression springs for transmitting limited torque in either direction of rotation.
- 4.9.2 Two models, TT3 and the Tandem are required to cover the 3 through 10 H.P. drive range. Also, a large quantity of trip release springs are required to cover the torque range.
- 4.9.3 The torque setting is not externally nor infinately adjustable. To change a spring requires complete removal of the unit from the drive system.
- 4.9.4 Periodic maintenance for lubrication, due to running in excess of 500 RPM, also requires complete removal of the unit from the system.
- 4.9.5 Preferred features are,
 - (a) Different torque settings for forward and reverse movement.
 - (b) Can be sealed (dustproof or waterproof).
 - (c) All position mounting.
 - (d) All steel construction.
 - (e) Automatic reset (below 25 RPM).
 - (f) Accepts 1½0 angular to .015" parallel misalignment.
 - (g) Automatic shut-off.
 - (h) Tamperproof setting.


- (j) Ambient temperature range of sub zero to $+350^{\circ}$ F.
- (k) Cadmium plating or stainless steel construction for corrosion resistance.

AND THE PROPERTY OF THE PROPER

4.9.6 The bore range for both models is 1 1/8" maximum and requires adapters for both motor and reducer shafts.

Installation area required between shafts is 5 to 5½".

SIMPLICITY is the Key to OVERLOAD PROTECTION



HELLAND TORQ-TENDER

REPRESENTED BY HENRY C. (HANK) JAHN

8829 MOUN. CINCINNATI,

45231

AREA COD

521-0172

positive overload protection accurate torque limiting

Effective overload protection in most any environment . .

HELLAND TORQ-TENDER is a positive mechanical unit, designed to maintain accuracy in any position, any atmospheric or moisture condition, under frequent or infrequent overloads and in a variety of other situations often encountered.

HIGH TEMPERATURES do not slow the instant response of the Torq-Tender. One large in-plant installation sees them protecting a complete production line of hot glue extruders which operate at 350 F.

LOW TEMPERATURES do not affect the dependability of these Helland units. Through the sub-zero cold of artic winters Torq-Tenders protect the drive mechanisms of radar tracking antennas.

SMALL SPACE is all that's required. Because of its favorable torque capacity and compact size, the Torq-Tender has been chosen to protect the camera controls on one of this nation's most sophisticated under-sea laboratories.

FREQUENT OVERLOAD is no problem. In a variety of manufacturing plants where assembly is critical it's common to rely on Helland Torq-Tenders for the control of torque in nut-running operations.

DUSTY ATMOSPHERE does not change the pre-set torque setting. Dust-proof models are available where required, though standard units are frequently used for applications such as mine conveyors and construction equipment.

OILY ATMOSPHERE, in which a friction unit cannot survive, is home for a Torq-Tender. Lathes, milling machines and other cutting tools are ideal applications for this Helland unit.

der ticker to manufacture and the control of the co


HIGH HUMIDITY does not dampen the accuracy of the Torq-Tender. Even dairy equipment, which must be steam cleaned on a daily basis, is protected from overload by these dependable Helland units.

SALT WATER, an unfriendly environment for mechanical devices of all kinds, fails to hamper the action of the Torq-Tender. Helland provides stainless steel units to protect the drive components of salt water drilling equipment.

HIGH SPEED installations such as bottling machines, can testing devices and other process equipment operate at minimum down time when Torq-Tenders arrest overloads, prevent jam-up and re-set automatically.

FORWARD/REVERSE does not matter, Torq-Tenders respond accurately in either direction. If, such as in drilling or tapping installations, a different torque requirement is indicated for reverse it can be accomplished by the change of just one spring.

HELLAND TORQ-TENDER®




The Torq-Tender is a positive drive coupling that provides accurate overload protection or torque limiting. It is not a friction clutch and therefore maintains its accuracy after thousands of disengagements. It is compact and easy to install, it operates in any position and both rotational directions. No tools are required for resetting as the Torq-Tender returns to its predeter-

mined torque merely by removing the overload and slowing the driving unit.


Six standard sizes offer a range of torque limits from 1 inchippoind to 3,000 inchippoinds. All are available in dust-proof or water-proof models, in special configurations and with plated exposed surfaces at slight additional cost.

Torn-Tender couplings are manufactured under one or more of the following patients: U.S. #3,124,227, 3,301,362 and 3,147,834 Foreign and other U.S. patents pending. All patents are owned by Helland Research and Engineering, Inc.

No friction unit can match the dependability of a **TORQ-TENDER**®



Helland Research and Engineering, Inc. **TORQ-TENDER**® Standard parts list



1 Housing 2 Thrust Washer 3 Retaining Ring 4 Line Up Washer 5 Drive Shaft 6 Return Spring 7 Spring Slide 8 Drive Key 9 Set Screw 10 Retaining Ring 11 Race Ring 15 Compression Spring 16 Spring Stop 20 Actuating Pin Shaft 21 Actuating Pin Housing 22 Actuating Pin Compression Spring 23 Actuating Pin Retaining Ring

Versatile Torque Control

TORQ-TENDER COUPLINGS


are used to:

- Protect motors
- Protect cutting tools
- Protect tables and carriage mechanisms
- Protect drilling and tapping tools
- Protect gear reducers drives
- Protect conveyors
- Protect tumblers and turntables

TORQ-TENDER COUPLINGS are used on:


- Lathes
- Milling machines
- Mixers
- Drills
- Conveyors
- Tumblers
- Turntables
- Packaging machines
- Gënëral drivës
- Ovens
- Textile machines
- Floor machines

TORQ-TENDER* couplings can be made up in many special configurations, a few examples shown here.



WARRANTY

Parts and performance of each Torq-Tender* coupling are warranted for 6 months when used in accordance with instructions Warranty is void if the Torq-Tender* coupling has been altered or reworked Warranty covers only the repair or replacement of the Torq-Tender* coupling. Transportation is not allowed.




Standard Advantages of the Helland **TORQ-TENDER**®

- 1. Accurate trip releasé
- 2. Torq-Tenders will solve most overload problems
- 3. No adjustments required as torque setting remains constant
- 4. Will last for years
- 5. Single position for machine timing
- 6. Small diameter strong torque
- 7. Easy to install
- 8. Easy to mount gear, pulley or sprocket (see drawing page 7)
- 9. Standard units function in temperatures up to 350°
- 10. Servés às à flexible coupling 1½° angular misalignment and .005° to .030° parallel misalignment, dépending upon the size of the unit
- 11. Will function in a vertical or horizontal position
- 12. Can be used as an indirect coupling as well as a direct coupling
- 13. Törq-Tender will function in both clockwise and counter clockwise direction
- 14. Standard bore sizes of Torq-Tenders will fit most shaft diameters
- 15. Resets automatically once overload is removed and speed reduced
- 16. An optional actuating assembly which strikes a switch and activates a warning signal or shuts off the motor can be provided at small additional cost (see page 6)

Construction


Torq-Tender couplings are built to high industrial standards and will last for years with only minimum maintenance required. Drive key and spring slides are investment castings of hardened steel. Housing and hub are mild steel, case hardened. Springs are carefully selected to give accurate torque settings. Water and dust proofed construction are available for a small addi-

tional charge. Torq-Tender couplings function in ambients up to 350° F. All units are available with Bronze Oilite Bearings in housing bore for through-shaft installations, in which the single shaft must extend to the end of the housing bore to support overhung loads. This is an ideal application for mounting a gear, sprocket or pulley.




Provides Automatic Shut-Off Too!

ACTUATING DISC



The basic Helland Torq-Tender Clutch with Actuating Pin is used with a second pin installed 180° to the first pin. The ACTUATING DISC is mounted on the outside diameter of the Torq-Tender so that when overload occurs, both actuating pins force a sliding member axially an amount equal to the pin ejection. The limit switch is mounted so that the sliding member actuates the switch immediately upon overload thereby shutting down the machine. The unit resets automatically upon reengagement and is bi-directional. This design allows either end of the Torq-Tender to be used as the input end.

ACTUATING PIN



THE THE PROPERTY OF THE PROPER

An Actuating Pin is ávailable as an optional feature on the six largest models of the Helland Torq-Tender. The instant an overload occurs, the actuating pin becomes operative, traveling %" to strike a limit or mercury switch that will actuate a warning signal or shut off the motor.

When the Fail-Safe Pin is used, the Torq-Tender coupling should be installed so that the "F" bore is the input and the "C" bore the output thus allowing the pin mechanism to rotate and strike the switch. When ordering the Torq-Tender with the Fail-Safe Pin, "C" and "F" dimensions must be specified (see dimensional drawing, page 9).

After the overload situation is corrected, the Torq-Tender coupling automatically synchronizes the original setting at the exact previous location and torque rating and the Fail-Safe Pin retracts to its original position.


ACTUATING DISC


Dimensions

ACTUATING PIN

MODEL	Α	Y	R	. N
TT—1X	850	0 094	0.250	0.250
TT-2	1.094	0 125	0 187	0.250
TT—2X	1.375	0 1 2 5	0 125	0 250
TT-3	1.625	0 125	0.125	0.187
TANDEM	1 625	0 125	0 125	0 187
TT—4X	2.000	0 125	0 135	0 075

MODEL	Α	В	С	D
TT1X	2.985	.687	3/32	1.063
TT—2	3 485	.893	1/8	1.097
TT2X	3.935	1.175	1/8	1.097
TT3	4.480	1,425	1/8	1.097
TANDEM	4.480	1.425	1/8	1.097
TT-4X	6.250	1.690	1/8	1.312






Ask us for your special requirements

- 1. Plated nickel, chrome, zinc, cadium, etc.
- 2. Special material such as stainless steel
- 3. Multiple re-engagement
- 4. Metric and non standard bores and keyways
- 5. Torque ratings different torques for forward & reversing applications
- 6. High temperature lubrication and seals
- 7. Can be sealed to make dust and water proof


Whatever your requirements, we'll tailor-make a Torq-Tender® for you!

Instructions for Mounting Gear, Pulley or Sprocket



A. Shown is Pulley and Sprocket or Gear mounted on flange with Bronze Oilite Bearing in bore (See CONSTRUCTION, Page 4).

Above is a typical application showing a pulley, sprocket or gear mounted on the flange with an oilite bearing pressed in the housing (F) bore. Because the Torq-Tender must be supported on both ends, the shaft must extend the complete length of the unit, thereby supporting the outer end of the unit. Upon overload, the housing end revolves on the shaft. Refer to illustration B for the application where the shaft is too short to extend through the Torq-Tender.



B. Shaded area is one piece drive shaft supported with Oilite bushing

Shown above is the self-supporting Torq-Tender to be used in applications where the shaft is too short to completely support the outer end of the Torq-Tender. The shaded area is a one piece drive shaft which supports the outer end of the Torq-Tender. A pulley, gear or sprocket is then mounted on the flange as in illustration A. This self-supporting unit is now available in the TT-2 and TT-3 models.

Instructions for determining torque rating required and TORQ-TENDER® model number for your application.

Computation of the RPM's should be made according to the location you select for the Torq-Tender.

- Refer to the following table to obtain the running torque rating of your application — the rating required to determine the proper strength of Torq-Tender springs.
- 2. From the chart headed Torque Ratings Available determine which models provide the desired overload protection for your application.
- Select the model with the dimensions that most closely match the needs of your application.
- Indicate a unit with a fail-safe actuating pin where automatic warning or shutdown is required.

BENEFIC STREET S

RPM	1/4	1/3	1/2	3/4	1	2	ORSEPO	4	5	6	7	8	9	10
5			• • •	0 , 4	•	-	Ü	-	•	•	•	•	•	
10	1528	2106												
15	1050	1400 1050	2100	2360										
20	764 631	841	1528 1261	1890	2522									
30	525	700	1050	1572	2100									
35	450	600	900	1348	1800									
40	394	526	789	1178-	1578									
45	350	467	700	1050	1401	2802								
50	316 262	420 350	631 525	945 789	1261	2522								
70	225	300	-450	769 675 -×	1050 900	2100 1800	2700							
έŏ	197	293	394	590	789	1580	2367							*
20 25 30 35 40 45 50 60 70 80 100 150 200	175	233	350	525	700	1402	2100	2804						
100	157	-210	315	422	630	1261	1891	2521						
150	105	140	210	315:	420	840-	1261	1681.	2101	2521	2941	2521	-0000	
250	79 63	105 -84	157 126	236 189	315 252	630 504	945 756	1261 1008	1575 1260	1891 1513	2206 1765	2521	2836 2269	2521
300	52	70	105	157	210	420	-630	840	1050	1261	1471	1681	1891	2101
350	63 52 45 39		90	135-	180	360-	-540	720:	900:	1080	1261	1441	1621	1801
400	39	60 53 47 42 38 35 32	79	118	158	315	473	- 630	-788	945	-1104	1261	-1418	1801 1576
450	35	47	70	105.	140	280 252	420	560	700.	840	980	-1120	1261	1401:
500 550	31.5	42	63 57	95 86	126 115	252 229	378	504 458	630: 573	756 688	882 802	1008 :917	1134 1031	1401: 1261: 1146: 1050: 970: 900: 840: 788:
600	29 26	35	EA	70	105	210	344 315	420	525	630	735	840	945	1050
-650 700	24.2	32.	48.5	73.	97	194	291	388	485	582	679	-776	873	970
700	23	30	45	67,5	90	180	270	360	450	540	630	720 672	810	· 900
750	21	28	42	63	-84	168	252	336	420	504	`588	672	756	840
800	19	26	39	:59 55.5	79 74	158 148	236 222	315	394 371	473 445	551 519	630	709 667	788
900	18.5 17,5	23	35	52.5 52.5	70	140	210	315 297 280	350	420	490	560	630	741- 700
950	17	30 28 26 25 23 22 21	33	49	66	133	199	265	350 332	398	464	630 593 560 531	630 597	-663
850 900 950 1000	16	21	42 39 37 35 33 31 28 26	47	63 57	126	189 172	252 229	315 286	378	441	504	567	663 630 573
1100	14 13	19	28	43	57	115	172	229	286	344	401	458	516	573
1300	13	17.5 16	26 24	40 36	53 48	105	158	210 194	263 242	315 291	468 339	420 388	473 436	525
1400	11.2	15	22.5	34	45	97 90	145 135	180	225	270	315	360	405	485 450
1500	10.5	1.4	21	31-	42	84	126	168	225. 210	252	294	336	378	420
1600	10.5 9.5	13 12.5	400	29 28	39 37	79	118	158	197	236 222	276	315	355	394

HOW TO USE TABLE:

- 1. 1HP at 50 RPM:
 - Read across the 50 RPM line to the 1 HP column. Running torque is equal to 1261 inch pounds.
- 2. 25 HP at 600 RPM:
 - Read across the 600 RPM line to the 5 HP column. Running torque to be encountered is five times the amount shown or 525 times 5, the equivalent of 2625 inch pounds.
- 3. 121/2 HP at 600 RPM:
 - Read across the 600 RPM line adding the values found at the ½ HP, 2 HP and 10 HP columns to arrive et the total running torque for 12½ HP. (52 plus 210 plus 1050 equals 1312 inch pounds total running torque).

Instructions For Installing TORQ-TENDER®

It is preferable to mount the unit on the output shaft of the motor or speed reducer with the drive shaft side toward the motor or speed reducer. The direction of the unit can be reversed when used as a coupling. The speed reducer and the driven shaft should be well lined up for mounting of the Torq-Tender but the unit does serve as a flexible coupling for both parallel and angular misalignment. All sizes of Torq-Tenders will accept up to 1½ degrees of angular misalignment. But parallel misalignment varies according to size of the units as follows: T-T-1—.005", T-T-1X—.007", T-T-2—.010", T-T-2X—.015", T-T-3—.030", T-T-4X—.030". When a gear, sprocket or pulley is mounted on the hub of the housing, the output shaft should extend through the unit with an oilite bearing supporting the overhung load.

There's no trick to re-engaging a TORQ-TENDER®

The Torq-Tender develops a clicking sound when in a disengaged position, a warning of an existing overload. The unit will re-engage automatically when motor runs 25 RPMs or less but if running faster simply slow down or stop motor until it re-engages.

How to Order TORQ-TENDER® Couplings

- 1. Specify the catalog number.
- Determine the torque rating required and then select from the torque values listed on page 10. If uncertain about torque, order additional springs of higher and lower torque ratings. These can be easily substituted.
- 3. Specify the bore size for the C bore (drive shaft) end.
- 4. Specify the bore size for the F bore (housing) end.
- Specify if an oilite bushing is needed on the drive side for overhung load to support gear, sprocket or pulley.
- Specify if an actuating pin or actuating disc assembly is to be included. See page 6 for specific instructions.
- Specify delivery time and shipping requirements. For special requirements, contact factory.

TABLE 1


Čatělog No.	Torque Range in Lbs.	C Bore	F Bore	Oilite Bushing	Actuating Assembly	Shipping Weight Lbs.
πı	1 to 15	1/8 3/16 1/4 5/16	1/8. 3/16 1/4. 5/16	Specify	N/A	1/4
піх	2 to 60	3/16 1/4 5/16 3/8 7/16 1/2	3/16 1/4 5/16 3/8 7/16 1/2	Specify	Specify	1/2
	4. tō 140	1/4 -5/16 3/8 7/16 1/2 5/8	1/4 5/16 3/8 7/16 1/2 5/8	Specify -	Specify	######################################
п2х	18 to 350	1/2 5/8 3/4	1/2 5/8 3/4	Specify	Specify	2-1/4
П3	18 to 500	3/4 7/8- 1 1-1/8	3/4 7/8 1 1-1/8	Specify	Specify	3-1/4
Tändem	240 to 1000	3/4 7/8 1 1-1/8	3/4 7/8 1 1-1/8	Specify	Specify	5
П4Х	750 to 3000	7/8 1 1-1/8 1-1/4 1-3/8 1-1/2 1-3/4	7/8 1 1-1/8 1-1/4 1-3/8 1-1/2 1-3/4	Specify	Actuating Pin Supplied	15

Keyway and Hub Dimensions

Bores under ½" will have no keyways. Bores ½" and over will have standard keyways as follows:

TABLE 2

Bore Size Inches	Keyway Width
Under 1/2	None
1/2 to 9/16	1/8"
5/8 to 7/8	3/16"
15/16 to 1-1/4	1/4"
1.5/16 to 1.3/8	5/16"
1-7/16 to 1-3/4	3/8"



Hub sizes and hub keyway sizes are as follows on housing end:

TABLE 3

Model No.	G Hub O.D.	M=Keyway Width		
TT1	.625	3/16"*		
πιх	1"	1/4"		
TT2	1-3/8"	5/16"		
TT2X	1.5/8"	3/8"		
TT3	1-3/4"	3/8"		
Tandem	1.3/4"	3/8"		
TT4X	3"	3/4"*		

*Oilite Models only

NOTE: Bores under $\frac{1}{2}$ " are supplied with no keyway and one (1) set screw. Bores $\frac{1}{2}$ " and over are supplied with standard keyway and two (2) set screws.

Torq-Tender[®]Coupling

(TORQUE RATINGS AVAILABLE)


Trip Release Springs Available For Torq-Tenders:

inch Lbs.	TT1X	TT2 Inch Lbs.	TT2X Inch Lbs.	TT3	TANDEM Inch Lbs.	IT4X
33 5 8 10 12 15	2 3 5 8 10 12 18 20 25 30 40 50 60	44 6 8 10 12 18 25 30 40 50 85 100 125 140	18 24 28 36 40 50 60 90 100 120 135 180 200 250 350	18 24 28 36 40 50 60 65 80 120 150 220 250 300 350 420 500	240 300 360 440 500 600 700 840 1000	750 1000 1250 1500 1750 2000 2250 2500 2750 3000

THE THE PROPERTY OF THE PROPER

These springs can be easily removed and replaced by springs with the required torque. See back page. Springs are not interchangeable between TORQ-TENDER couplings with different catalog numbers.

Dimensions



Standard Dimensions (in inches)

Size	A Body Dia,	B Hub Diğ,	C Bore and Keyway	D Hub Engage ment	É Hoùsing Engage ment	F Bore and Keyway	G Hub and Keyway	H Hub Longth	Flenge	J Body Length	K Overall Length	L Hub Projection
TT12 TT1X TT2 TT2X TT3 TANDEM TT4X	1,000 1,562 2,062 2,500 3,000 3,000 4,625	,625 .875 -1,250 1,500 1,750 1,750 3,000	See Tables 4 & 2, Page 9	.812 1.125 1.500 1.750 2.000 3.312 3.500	512 .625 .812 1.125 1.312 1.312 1.750	See Tables J. & 2. Page 9	See Table 3, Page 9	,500 ,500 ,625 ,875 1,062 1,062 1,125	.500 .600 .750 1,000 1,187 1,187 1,330	.750 .985 1.300 1.500 1.812 3 032 3.500	1,450 1,790 2,450 2,975 3,475 4,719 5,530	.200 .205 .325 .450 .500 .500


CAUTION: When using Torq-Tender for direct coupling be sure shafts do meet inside unit. See dimensions D and E for proper engagement.

INSTRUCTIONS for changing springs

To remove springs, first remove retaining ring from the housing by drawing the retaining ring together with retaining ring pliers and remove the drive shaft from the housing. Then place the drive shaft in a vise. Pinch the springs with a pair of narrow jawed channel lock pliers, unseating and removing them.

To insert new springs, place the drive shaft in a vise and place one end of the spring against the bottom of the spring slot. Using a vise grip or similar pair of pliers, put the lower jaw under the drive shaft and the upper jaw on top of the other end of the spring. Compress the spring by closing the pliers and use a screw driver or blunt instrument to push the end of the spring out of the pliers into the spring slot. Repeat on other side.

When reassembling TORQ-TENDER®, make sure the thrust washer is in place in the groove in the housing. The housing should be properly lubricated with No. 2 Lubriplate with molydisulphite.



The state of the s

THE SECTION OF THE SE

LUBRICATION INSTRUCTIONS. Your TORQ-TENDER® is shipped properly lubricated with No. 2 Lubriplate with molydisulphite. Where overloading is infrequent, no additional lubricant is required. Where frequent overloading occurs, especially at speeds in excess of 500 RPM, periodic lubrication is necessary. Follow the procedure for opening the TORQ-TENDER® stated above. Brush a liberal coating of lubricant inside the housing and reassemble. For moist or dirty atmospheres, specify rubber "O" rings to seal out moisture and dirt and to help retain the lubricant.

Come To A Clean Stop Everytime!

The Helland Stop-Tron automatically and quickly powers AC driven equipment to a complete stop. Stop-Tron minimizes unproductive and risky deceleration periods. Easy to install and completely adjustable. No air, hydraulics or double shafts needed. Available in 120, 230, 460 and 570 VAC Models.





15107 Minnetonka Industrial Road Minnetonka, Minnesota 55343 (612) 933-2223

5. Torque Limiter Comparison and Selection

5.1 In comparison, the previously reviewed units meet most of the requirements except for a few specific features.

5.2 Dalton OSDC Torque Limiter

This unit, the most simplest and economical of all reviewed, cannot maintain an accurate setting and by design is not adaptable to ast vating a motor shut off switch. Its incapability to meet these two requirements, eliminate friction disc type clutches from this selection.

5.3 Helland Torq-Tender

The Torq-Tender unit is unique in design and has several features that no other unit has, in that separate torque settings can be selected for forward or reverse operation and the unit is tamperproof. However, the fact that torque adjustment and maintenance requires extra parts and complete removal from the drive system, makes this unit a less desirable unit than the three remaining devices.

The (3) remaining units all use a positive ball detent type design in conjunction with one or more coil springs which are externally adjustable. The torque range of all three units covers the horsepower range of 2.25 thru 9.79 required for the 20 to 90 ft. conveyor range in height. Pricewise, all (3) basic torque limiters are in the same range of approximately \$150.00 to \$200.00.

- 5.5 Beyond this point there are certain features or requirements where each manufacturer differs from the other.
- 5.6 The features involved are,
 - (a) Accuracy of setting:

Autogard is ± 10% (this percentage might improve after break-in)

Rite-Torg - ± 5%

Form Gard - ± 5%

(b) Method of maintaining setting:

Autogard - set screw

Rite-Torq - locking ring tab

Form Gard - set screw over plastic plug

(c) Totally enclosed standard unit:

Autogard - No (could be enclosed if needed)

Rite-Torg - Yes

Form Gard - Yes

(d) Maintenance:

Autogard - clean and lubricate (scheduled maintenance)

Rite-Torg - none

Form Gard - none

(e) Capable of withstanding frequent overload, using a motor cutoff switch at 1800 RPM:

Autogard - Yes, but questionable, reference para. 4.6.7

Rite-Torq - Yes (tested), reference para. 4.7.3

Form Gard - Yes, although word of caution is advised, reference Fig. #10

- It appears that Ferguson, Rite-Torq, backed by their own testing information, are more sure of their overload wear capabilities. Although it is possible that both Autogard and Form Gard are more cautious in making a direct statement along these lines, it is apparent that both makes use a ball location pattern to alleviate wear in this area.
- 5.8 Based on the above information, Ferguson, Rite-Torq

 Torque Limiter Model "S" Size 2 was selected for application in the drive system.
- 5.9 Kornylak Corporation drawing (2-1026-321f Rev. Sht. l of l) of the torque limiter assembly, shows the above unit attached to a rigid type reducer shaft adaptor per drawing 2-1026-335f. This adaptor should be replaced with a flexible coupling to allow for shaft misalignment.

and and a supplementations of the supplementation of the supplementa

6. Electrical Overload Device Selection

- 6.1 With the conveyor system mechanically protected to within 140 to 150% of rated full load, a supplementary electrical overload control, capable of being set to within 110 to 115% of full load is required.
- 6.2 Furthermore, the type of monitoring device selected should be reliable, easy to set and adjust, economical and above all failsafe in operation.
- Past electrical and/or electronic type overload protection has been provided by several different devices, ranging from a highly sophisticated Tipptronic Control to a current sensing relay used in conjunction with a timing relay for bypassing the initial surge of current to start the motor.

THE STATE OF THE STATE OF THE STATE SEARCH SERVICE STATES SEARCH SERVICE STATES

- 6.4 The main drawback to the Tipptronic unit was trouble shooting and maintenance, due to its complexity. The more common type of relay, Allen-Bradley Bul. 809, provides a simple and rather inexpensive overload device, however, they are less accurate in both setting and repeatability. The list price for the relay and time delay is \$120.00.
- Newer approaches to power monitoring to be reviewed and compared are, Formsprag's TorQalert and a motor and load torque analyzer, manufactured by RFD Instrument Company in Elgin, Texas.

- 6.6 The TorQalert unit (reference Bulletin X-3012A) is a solid state device which integrates the motor input voltage and current to monitor the motor output power which is directly related to torque. The unit is easy and simple to adjust with a meter readout and also has a built-in time delay for motor startup. The price of this unit is approximately \$230.00 per unit.
- 6.7 The motor and load torque analyzer by RFD Instrument
 Company (reference Bulletin RFD2002) detects an overload
 condition by the slip characteristics of the motor with
 a transducer in close proximity to the motor shaft.
 This method is entirely independent of voltage and
 horsepower. The unit is also solid state with a meter
 readout. The accuracy of this unit is ± 1% of relative
 set value. The list price is in the neighborhood of
 \$600.00 per unit.
- 6.8 The motor to be monitored is a 3 speed constant torque 440V, 3 PH, 60 HZ design B motor. The horsepower, speed and full load amp ratings are listed below.

H.P.	SPEED	F.L.A.		
10.0, 6.6, 5.0	1800, 1200, 900	15.4, 10.6, 25.0		
7.5, 5.0, 3.75	1800, 1200, 900	11.5, 8.0, 11.0		
5.0, 3.3, 2.5	1800, 1200, 900	7.3, 5.0, 7.0		
3.0, 2.0, 1.5	1800, 1200, 900	5.0, 3.2, 5.0		

Normally a 3-speed motor would require (3) separate overload controls, however, note that the full load amp rating for each motor is nearly the same for either 1800 or 900 RPM. With this in mind, one trip setting could be selected for the two amp ratings that would satisfy both speeds within the 110 to 115% overload range. For example, a setting of 17.1 amps on the 10 H.P. motor would be a 111% overload setting @ high speed and 114% @ low speed. Under this condition, only two TorQalert units are required per controller.

A CHARLES CONTRACTOR CONTRACTOR

7.0 Although the RFD unit is highly more accurate, it is our opinion that the TorQalert unit with ± 5% accuracy is suitable for this application. Not only is it more pratical, it also offers simplicity both in selection of setting as well as installation.

BULLETIN X-3012-A OCTOBER, 1975

INSTALLATION AND MAINTENANCE INSTRUCTIONS FOR OD MODELS the professionals in motion

FORMSPRAG®


torQalert ** LOAD MONITOR OVERLOAD PROTECTION

BEFORE YOU BEGIN INSTALLATION...

Keep in mind the block diagram below. The TorQalert has two electrical circuits associated with it: The power circuit and the control circuit.

The power circuit is the input to the TorQalert and must be wired as described in section A of the following pages.

The control circuit is the output of the TorQalert and utilizes the output contacts of the relay. The control circuits described in section B of this manual are only uses for the output contacts of the relay. Other uses of the TorQalert output contacts are limited only by the imagination.



SECTION A - THE POWER CIRCUIT

- 1. Mount the unit in a location that is easily accessible to the wiring of the motor to be monitored. (electrical control box, if possible).
- 2. Choose the system from figures B or D that is your application. Figure B is a direct on line wiring diagram corresponding to a one direction motor. Figure D is a two direction wiring diagram employing reversing starters.
- 3. Consult the maximum continuous current column of table A. If the continuous current rating of the motor falls into this range, connect Phase I to the appropriate terminals found in table A. If the continuous current rating is higher than this range, ob-

in a current transformer (2VA min) with a reduction io that will reduce the current to this range. Install the current transformer as shown in fig. C and connect its leads to the corresponding terminals found in table A.


TABLE A

CONNECTIONS TO TERMINALS 5-6-7							
TERMINALS	MAXIMUM CONTINUOUS CURRENT (A)						
5; <u>7;</u> 6; 7; 5: 6;	2.0 3.0 5.0	4.0 6.0 7.5					


4. To complete the power circuit, connect Phases II and III to terminals 4 and 3 respectively. NOTE. that in the reversing starters diagram, terminals 3 and 4 are connected on opposite sides of the starters.

DO NOT ATTEMPT TO TEST THE UNIT UNTIL YOU HAVE READ SECTIONS B & C

POWER CIRCUITS



SECTION B — CONTROL CIRCUITS




Examination of the TorQalert terminal strip in Figures E, F and G, reveals that terminals 8 through 12 are the output contacts of the relay. It is important to distinguish when the output contact states occur.

In Figure G, the output contacts are shown in the TorQalert monitoring state, — when the unit is sensing the power to the motor. The relay is energized.

When the TorQalert senses an overload of power to the motor, the relay is de-energized and the contacts switch to the signal state (figure F) with the contact signal state shown in figure F, any number of control circuits can be designed to fit the particular application.

To aid the installer with his design, the next few pages contain examples of control circuits. Once the control and power circuits are installed on the Tor-Qalert, it must be calibrated as described in Section C.

EXAMPLE 1 -- DIRECT ON LINE



PURPOSE:


To shut down the motor being monitored if any overload of power occurs.

DESCRIPTION: Refer also to Figure B.

Momentary depression of the start button energizes starter 1M, closing its three phase contacts in the power circuit, and the holding contact in the control circuit. Since, the TorQalert is connected after the starter contacts, the relay is energized and its output contact (term 8 and 10) in the control circuit close. The motor starter, 1M, is held through the path containing the TorQalert in the control circuit. An increase in motor power from the preset value (Section C) is detected by the TorQalert in the power circuit and the relay is de-energized, opening the output contact (term 8 and 10). This results in de-energizing the motor starter and the motor is shut jlown.

*NOTE — Control voltage is defined as the voltage that is used to energize the coils of starters, relays, timers, etc.

EXAMPLE 2 -- DIRECT ON LINE WITH FAULT SIGNAL



PURPOSE:

To shut down the motor being monitored and trigger an alarm when an overload occurs.


DESCRIPTION: Refer also to Figure B.

The first half of this control circuit is essentially the same as the direct on line of example 1. Momentary depression of the start button applies the control voltage across the motor starter (1M) closing the three phase contacts of the power circuit. As this occurs, the motor starts and the relay of the TorQalert is energized, closing the contacts across terminals 8 and 10, 9 and 11 and opening the contacts across 9 and 12. The closing of the contact across terminals 9 and 11, energizes an external control relay, 1CR, (supplied by installer), switching its contacts to opposite states than those pictured in the control circuit. The motor starter is now kept energized by the path through terminals 8 and 10 of the TorQalert and its holding contact. When an overload from the preset value (Section C) occurs, the TorQalert relay is deenergized, changing the contacts to their original states shown in the control circuit diagram. The motor starter drops out and the motor is shut down. Since the external control relay, 1 CR, is still energized, its contact completes the circuit to the alarm and the alarm sounds.

or receives the coordinate of the control of the co

Pressing the stop-reset button breaks the circuit to the control relay, 1CR, and resets the control circuit to the original pictured state.

EXAMPLE 3 — REVERSING STARTERS



PURPOSE:

To shut down a two directional Motor when an over-load.


DESCRIPTION: Refer also to Figure D.

The operation of this control circuit is basically two direct on line circuits (example 1). Since the start forward and start reverse cycles are identical, explanation of one cycle also describes the other.

Momentary depression of the start reverse button, energizes starter 2M. closing its three phase contacts in the power circuit and switching the two contacts to opposite states than those pictured in the control circuit. The motor runs in the reverse direction and the TorQalert contacts across terminals 8 and 10 close, providing a holding circuit to starter 2M. Note that the start forward cycle is prevented when the reverse cycle is operating, by the now open 2M contacts adjacent to starter 1M. This same operation applies also to the start forward cycle.

When an overload from the preset value (Section C) in the motor occurs, the relay in the TorQalert is deenergized, opening the contacts across terminals 8 and 10. This breaks the holding circuit to the appropriate starter and the motor is shut down.

SECTION C. CALIBRATION AND LOAD ADJUSTMENT



CALIBRATION PURPOSE:

To match the TorQalert to the motor. This should be done on the first operation only.

LOAD ADJUSTMENT PURPOSE:

To set the TorQalert at the motor's normal working conditions as near to 100% as desired, such that an increase in working load de-energizes the TorQalert

- 1. Set the load adj. control maximum clockwise.
- 2. Set the calibration control maximum counterclockwise.
- 3. Start the motor without load. The meter reading should be between 40% to 60%.
- 4. Gradually turn the calibration control clockwise and note that the meter reading decreases to a minimum and then starts to increase. (If the reading does not decrease, interchange the connections between terminals 3 and 4 in the power circuit.)
- 5. Set the calibration control to a minimum reading on the meter.
- 6. Start the motor at normal load and turn the load adj. control slowly counterclockwise until the meter reading reaches 100%. The TorQalert relay should de-energize (Signal State).
- 7. Turn the load adj. control clockwise so that the meter reading is as close to 100% as desired.

*The TorQalert relay is calibrated to operate when the meter reaches 100%. A setting too close may be pushed past the 100% mark by uncontrollable fluc ations in the voltage supplied to the motor. The max mum stable meter reading can only be found by trial and error.

In some applications, it may be desired that the motor tolerate a percentage of overload. To do this. the load adjustment control should be set at a lower level. The lower the setting, the greater the load increase required to de-energize the TorQalert relay. For example, if it is desired that the motor tolerate a 20% overload, the meter should be set at 80%.



P.O. BOX 778, 26444 GROESBECK HWY. WARREN, MICHIGAN 48089 TELEPHONE (313) 758-5000, TELEX 230-389


CANADIAN SALES: 17 VALOIS BAY AVENUE PT. CLAIRE, P.O. H9R 4B4 CANADA (514) 695-7620

THE STATE OF THE PROPERTY OF T

(512) 285-3385/3386

INSTRUMENT CO., INC.

404 NORTH MAIN . P.O. BOX 548 . ELGIN, TEXAS 78621 . U.S.A.



PATENT PENDING

"PERCENTAGE OF LOAD"

MOTOR & LOAD TORQUE ANALYZER

SERIES PCM2002

FEATURES:

- .Two separate inhibit alarm functions with locking adjustment
- .Readout in direct percentage of load
- .0 to +70°C Ambient temperature
- .Field calibration and alignment
- .Automatic lockout/manual reset
- .Integrated circuit solid state logic
- .Adapts to most motors and rotary loads

GENERAL:

The PCM2002 is a universal motor monitor and control that can be used on single or multiple phase motors, it monitors both motor and load independent of voltage, horsepower, and shaft size. It detects the slip characteristics of the motor with a solid state transducer in close proximity to the rotating shaft. No physical contact, special gears or collars are needed.

The all solid state integrated circuit PCM2002 is designed for the ultimate in reliability. The solid state pickup and shaper provides a noise free signal in most applications. The motor current equivalent is digitally compensated and displayed on a 4 inch meter. An adjustable warning light or horn, also a separate adjustable alarm output for automatic motor shut down is provided if the percentage of load exceeds a preset value.

MODEL OPTIONS:

- PCM-2002... Basic unit with two dry contact relays to monitor or control a specific motor or work task.
- PCM-2002A.. Basic unit as the PCM2002 with an additional 4-20MA two wire transmitter into 600 ohm.
- PCM-2002B.. Basic unit as the PCM2002, but contains a digital readout and BCD coded output.
- PCM-2002C.. Basic unit as the PCM-2002, but enclosed in a Class 1, Div. 2 explosion proof enclosure, glass door and Class 1, Div. 2 armor probe.

PCM2002D.. Basic unit as the PCM2002 with a digital steering and control logic to detect changes in torque, make a set count and stop device for another set period of time.

ENGINEERING SPECIFICATIONS:

Power Input......120 VAC, 5 watts, 50/60 Hz (18 to 30 VDC unregulated 3 watts, special order).

Accuracy.....±.0025% of Full load RPM.

Motor Speeds......From 200 RPM to 10,000 RPM.

Transducer.........Hermetrically sealed Brass/Aluminum head, with cable enclosed in stainless steel armored cable and weather proof connector.

Circuitry.....Solid state digital logic with optional relay or solid state output control.

Range...... 0 to 120% Horsepower, other ranges available.

Inhibit Function I...10 to 90% Horsepower optional 100% scale available, dry, 10 amp, @600 volt relay contacts (optional solid state output available at extra cost).

Inhibit Function II..90 to 120% horsepower optional 100% scale available, dry, 10 amp, @600 volt relay contacts (optional solid state output available at extra cost).

Start......Built in variable time delay from initial start to allow motor to equilabrate. (Please specify when ordering).

Reset......Manual reset and override located on front panel.

Readout.....Special 4 inch jeweled anti-vibration type meter.

Alignment.....Front panel adjustable zero, field calibration.

Protection.....Lightning/Transient protected.

Ambient Temperature... 0 to 70°C. Optional -20 to 85°C.

Enclosure......14 Gauge steel nema 4, water, dust and splash proof.

Size...... 5"x9"x3½" with enclosure. 5"x6"x3" Electronics Module.

DIMENSIONS 8.750" 8.000" 9.500" 9.500"

NOTE: Specifications subject to change without notice.

RFD Instrument Co., Inc. guarantees the PCM2002 Motor Control Monitor to be free from defects in material and workmanship for a period of one year from date of purchase.

RFD P/N 0036-001-0001 MOTOR SLIP VERSES CURRENT CHARACTERISTIC

APPLICATION NOTE:

In practical motor overload detection the current parameter is usually utilized as an indication of load conditions. However; due to ambient temperature variations, difficult field installation and set up the current method is sometimes not adaptable and willnot satisfy some applications.

The slip parameter of a motor can be utilized to obtain more information than that available from the current parameter, as shown from the following excerpt and curve.

1 "The relationships between power function, efficiency, and current at various partial loads of a typical design B 10-Hp motor are shown in fig. 2-7... The percent of full load slip curve in fig. 2-7 is a straight line between 10 and 110 percent, indicating that slip speed is directly proportional to the horsepower load in this range. This relationship provides an accurate means of estimating loads carried by squirrel-cage induction motors in integral-horsepower sizes... A squirrel-cage induction motor no load speed is slightly less than synchronous speed. In the example in fig. 2-7, the no-load slip is approximately 1 rpm, which is equivalent to 1,799 rpm no-load speed... Between zero load and 100 percent load, motor speed changes only 3 percent in the Nema B motor as illustrated in fig. 2-7. The motor horsepower and motor torque are therefore in a direct relationship...".

and the second of the second o


By monitoring the motor slip and utilizing the information derived, a reliable parameter is available for monitor and control.

APPLICATIONS PRETAINING TO MONITOR OF MOTOR SLIP:

- : To protect high ratio gear reducers and spur gears.
- : To monitor and control pumping slurrys or corrosive materials.
- : To monitor and control centrifugal blowers.
- : To monitor and control for direct computor interface with analog or digital readout of most motor types and loads used today.

^{1.&}quot;From Motor Selection and Application," by Charles C. Libby,
Copyright 1960, used with permission of McGraw-Hill Book Company.

²Fig. 2-7. Performance curves of typical 10-hp 1,800-rpm Design B squirrel-cage induction motors, rated voltage and frequency applied.



anning and and and and and an and an and the contraction of the contra

²"From Motor Selection and Application," by Charles C. Libby, Copyright 1960, used with permission of McGraw-Hill Book Company.

Applications:

Municipal Sewage and Water Treatment Plants:

- Utilized on clarifier drives to monitor the motor and gear reducer, allowing the operator to detect less than a 100 lb. load and stop a triple 20,000:1 gear reducer before any physical breakage or malfunction can occur.
- 2. Utilized in conjunction with an RFD TCM4001 temperature indicator to monitor the motor bearing temperatures or blower outlet temperature (PCM2006) plus monitor the load and give a direct readout in CFM. The unit also provides surge and over load protection and control for the complete blower installation.
- 3. Used on thickner drives to detect stoppage of the gear drive assemblies and inhibit operation if a malfunction occurs.

Industrial Applications:

 Bakery industry to monitor and control the mixers, using the PCM-2002A to batch mix bread dough and batter to a set consistency or viscosity. TONITORN DESIGNATION OF THE PROPERTY OF THE PR

- 2. Pulp industry monitor and control slurry pumps along with the temperature parameter of the bearings for proper operation.
- 3. Petroleum industry to monitor and control oil well heads utilizing the PCM-2002D as a pump off controller.
- 4. Utilized by OEM motor manufacturers as an in-house test set for the monitoring and checkout of new induction motors. By applying the PCM-2002B to a checkout stand, the manufacture has a coded BCD output to be interfaced directly to his computor.
- 5. Rendering works injustry to monitor and control the consistency of the cooked meat as it is transferred through the rotary cooking ovens.

The applications noted are but a few possible applications of this device, they are not limited to just induction motors. Wherever there is a job to be done and rotary work over 1000 RPM is doing the initial work, whether it be on a diesel engine on board ship or on a generator at a power plant, (synchronous motors and conditions not applicable), if a slip of at least .5% is discernable, we can apply this device and accomplish the task of monitoring and controlling its load.

How to Calculate Motor Slip:

Motor or work slippage is the difference in turns at no load and the turns at full load. Example: If a motor has a nameplate full load rating of 1750 RPM, then the synchronous speed or no load speed for practical purposes would be 1 RPM less than 1800 or 1799 RPM.

1799 no load -1750 full load

49 RPM slip from 0 to 100%

Percentages of slip can be said that it is the slip divided by the no load speed.

.0272 or 2.72% 1799 RPM 49 RPM

To calculate the times involved, first take 1799 and divide by 60 to put the factor in revolutions per second.

 $\begin{array}{c}
 29.98333333\\
 \hline
 1799
\end{array}$

Then to time

.0333518621 sec. or 33.352 milli-sec. 29.98333333 1.00000

Then find

Then to time

.0342857142 sec. or 34.286 milli-sec. 29.16666667 1.000000 one or some constitution of the second the second of the s

Take:

34.286 milli-sec. Full load speed -33.352 milli-sec. No load speed

.934 milli-sec. or 934 micro-seconds difference between 0 and 100% load on this particular motor. On a 75 to 125% scale, this puts 467 micro-seconds as the standard slip in time. Because the slip is linear, we can shift it from 5 to 120%. The motor will then change from 34.0525 milli-seconds to 34.519 milli-seconds from 75 to 125% of load

To find the "A" time, proceed as follows:

2 233.5 micro-seconds 2 467 micro-seconds

100% time of 34.286 milli-seconds or time "B"

34.286 100% time "B"

+ .2335 50% of time difference derived at calculation above

34.5195 milli-seconds time "A"

34.286 100% time "B"

- .2335


34.0525 milli-seconds time "C"

en konkreden ennnngsprenten fra mede preseden benede by hen beneden by de beneden by de benede en en en en en


PCM2002 INSTALLATION AND OPERATION INSTRUCTIONS

Unpack the PCM2002 and transducer assembly. Inspect for any shipping damages. The shaft or coupling to be monitored must be a ferrous material for proper operation. The PCM2002 transducer detects a void or difference in ferrous material and this produces a resultant signal that is measured against an internal standard.

- 1. Utilizing the universal bracket that is furnished with the PCM2002 mount the transducer assembly in a close proximity to the rotating shaft. (NOTE: The transducer will mount in any position and is impunitive to oil, dirt, and water).
- 2. Reference Figure 1, utilizing the feeler gauge supplied with the PCM2002, adjust the transducer as shown in figure 1.



- 3. Insure your PCM2002 is set up for the proper speed and Nema Type Motor as you are installing it on. This is a factory setup and should not be attempted in the field because of proper test facilities.
- 4. Mount the PCM2002 securely to a solid structure and connect as shown



Disconnect motor starter at point A and reconnect as shown for control operation.

- Unlock the front panel screw driver lock nuts and preset the warning and alarm adjustments to a full CW position.
- Apply power to motor from HOA or circuit breaker, turn on PCM2002 (NOTE: there is a 20 second delay before the control circuit is activated).
- With a clamp on type ammeter or equivalent attach pickup on one of the AC leads going to the motor.
- With the motor connected to the load, apply power and observe the ammeter reading. (NOTE: lock ammeter reading or jot reading down) also with a voltmeter measure the applied voltage across the motor.
- Shut off motor and examine the motor identification plate. the voltage verses current as applied to your particular installation, Example:

RPM Voltage Amps 6.4/3.21750 115/230

TO THE PROPERTY OF THE PROPERT

NEMA TYPE B

Calculate the 100% load figure as follows from the motor identification plate.

Voltage X Amps=Power in watts

E1XI1=P1

$$E_1XI_1=P_1$$

Calculate the actual motor load, using the measured voltage as 11. applied (E_2) and using the current reading (I_2) derived in step 7, multiply as in step 10.

Voltage X Amps=Power in watts

$$E_2$$
 $XI_2=P_2$

12. To derive the correct setting of the meter zero R-8 on the PCM2002, calculate as follows: Divide the motor plate power into the measured power figure.

- Start the motor and turn on the PCM2002, with the motor running 13. adjust the front panel adjustment R-8 for the proper percentages of load as derived in step 12. The other adjustments should not be attempted unless the proper test instrumentation is available. Reference the PCM2002, alignment and maintenance manual.
- Using information derived in step 9 through 12, calculate the warning and alarm set point and adjust for desired warning and alarm condition.

How to calculate horsepower load on the Gear Reducer Drive Motor.

HP= Torque load (inch lbs.) x RPM (Motor)
63,025
OR

HP= Torque load (foot lbs.) x RPM (Motor)
5252.0833

Efficiency= Hp out/Hp in
Required input torque= Torque out
Ratio _____ Eff.

Utilizing the 75 to 125% or the 20 to 120% of load scale, the slip is linear with horsepower.

EXAMPLE: We have a 1725 rpm full load .5 Hp motor driving a 20,000:1 gear reducer, on a 50 ft. diameter clarifier, with an average of 7 lb. per ft. of sludge load, with an overall efficiency of 60%. The PCM2002 has a 75 to 125% of load scale. What percentage of load change will be observed on the meter with a 1 lb. per foot build up of sludge on the scraper arm?

First we know slip is linear with horsepower so 75 to 125% of scale is 50% of the total horsepower on the motor. Each division is equal to .005 horsepower per division or .0025 horsepower per percent of scale. (.5 Hp \div 2 = .25 Hp per 50 divisions or each division equal to .005 Hp at the motor shaft).

Next we must calculate the loading on the clarifier output drive.

CHART ORIGINAL OF VIOLES OF THE CONTRACT OF A CONTRACT OF SECTION

63.025

OR

Hp of output scraper drive=
Torque load (ft. lbs.) x RPM (output Drive)

5252.0833

With a 20,000:1 reducer on a 50 ft. diameter clarifier and a nominal 7 lb. per foot load of sludge. (3 x D^2 x 7) = Torque required 3 x $(50)^2$ x 7= 52500 inch lbs. of torque at the scraper proper.

Next we calculate total Hp at the motor shaft with a 60% efficiency (1725 RPM + 20,000= .0875 RPM).

(60% eff.= factor 1.666)

We can say that at 7 lb. of sludge on a 50 ft. diameter clar-fier tank, operated by a 20,000:1 gear reducer with an efficiency of 60% and 1725 RPM motor the required input horsepower will be .12 Hp, we will align this on the PCM2002 at the 100% point with R-8.

The next step is to arbitrarily select a additional loading such as 1 lb. per foot and recalculate the load for 8 lbs. per foot of scraper using the formulas above.

3 x $(50)^2$ x 8 =60,000 inch lbs. of torque now at the scraper.

Hp= $\frac{60,000 \times .0875}{63,025}$.0833 Hp $\frac{\times 1.666}{.1388}$ Hp

.1388 Hp with 8 lbs. per foot on scraper -.1200 Hp with 7 lbs. per foot on scraper

.0188 Hp increase with 1 ft. of sludge on the scraper

We then calculate the percent of increase in horsepower loading .0188 ÷ .5 Hp= 3.76% increase in Hp at the motor. Relating this to scale change of .005 Hp per division the meter will move up scale 3.76 division, (.0188 ÷ .005=3.76 Div.) or a total scale deflection of 7.52%. With a normal load increase of 1 lb. per foot on the scraper in a 50 ft. clarifier the torque analyzer will go up scale 3.76 divisions or 7.52%.

1